



# **Design Engineering**

FIVE DOLLARS A YEAR


**CHOOSING THE PHOSPHATE COATING FOR STEEL (page 50)**

**Sampling switch characteristics and uses**

**September 1956**

**Optical tooling for accuracy**

PUBLISHED BY MACLEAN-HUNTER PUBLISHING COMPANY, LIMITED, TORONTO, CANADA



*...there's a difference  
going UP, Galileo!*

GOING DOWN, bodies of different weights fall at the SAME speeds. The great Galileo spectacularly proved his theory over 350 years ago—dropping weights from the Leaning Tower in his native City of Pisa.

*...but going up is altogether different—as the world of modern manufacturing and building appreciates.*

The amazingly light weight of today's tough aluminum alloys, for example, makes possible speedier installation, cuts labor and shipping costs. Only one-third the weight of ordinary metals, strong, corrosion-resistant aluminum in ductwork, roofing and siding, and other applications—goes up faster; then lasts a lifetime!

*For full information, write or call your nearest Alcan sales office.*


## **Aluminum Company of Canada, Ltd.**

Calgary Halifax Montreal Ottawa Quebec Toronto Vancouver Windsor Winnipeg

*Distributors for Alcan Mill Products:*

ALLOY METAL SALES LIMITED, Toronto and Winnipeg  
DRUMMOND McCALL & CO. LIMITED, Montreal, Toronto, Winnipeg  
WILKINSON COMPANY LIMITED, Vancouver and Edmonton





# Design Engineering

VOL. 2

SEPTEMBER 1956

NO. 9

## This month's cover

Gates of Hell? Craters on Vesuvius? Mosquito's-eye view of the porch screen or the morning after the night before? Don Dancer said "I think it's the moon." He's wrong but he should know as he was this month's cover artist. The cover is none of these things and nobody's liver under a microscope. It relates to our feature story on phosphate coatings which starts on page 50. Complete answer to its meaning can be found at the foot of page 53.

## Design Engineering

MEMBER



Authorized as second class mail, Post Office Department, Ottawa.

Printed and published by Maclean-Hunter Publishing Company Limited, 481 University Avenue, Toronto. Horace T. Hunter, Chairman of the Board; Floyd S. Chalmers, President; Donald F. Hunter, Vice-President and Managing Director; Thomas H. Howse, Vice-President and Comptroller.

Publishers of National magazines in Canada: Maclean's, Chatelaine, Canadian Homes and Gardens, Business newspapers in Canada: Canadian Hotel Review; Fountains in Canada; Heating and Plumbing Engineer; Bus and Truck Transport; Canadian Advertising; Canadian Automotive Trade; Canadian Aviation; Canadian Grocer; Canadian Machinery; Canadian Packaging; Canadian Paint and Varnish Magazine; Canadian Printer and Publisher; Canadian Shipping; Canadian Stationer; Civic Administration; Drug Merchandising; L'Espresso; The Financial Post; General Merchant; Hardware and Metal; Marketing; Men's Wear; Modern Power; Painting and Decorating Contractor; Plant Administration; Le Prix Courant; Electrical Contractor; Style; Office Equipment & Methods; Home Goods Retailing; Business newspapers in U. S. and U. K.: Inland Printer, Rock Products, Concrete Products, British Printer.

OTHER SERVICES: The Financial Post Corporation Service; Canadian Press Clipping Service; Commercial Printing Division.

Offices at 1242 Peel Street, Montreal; Maclean-Hunter Limited, 125 Strand, London (Eng.).

Subscription rates: Canada \$5.00 per year, two years \$9.00, three years \$13.00. Single copy price, \$1.00. Other countries \$8.00 per year.

## CONTENTS

### Features

Sampling switches now offer more .....	35
Take the headaches out of measuring .....	40
Auto design sheds its strait-jacket .....	44
Canadian Institute of Radio Engineers Convention ....	46
Speaking voice of a movie big noise .....	48
Phosphating can make a finish stick .....	50
Die casting has most of the answers .....	55

### Short features

These glass laminates are new .....	54
These instruments will save your time .....	60
Measurement of friction makes basis for research ....	62

### Departments

Design news in pictures .....	88, 89
Editorial .....	94
File (literature offered) .....	70, 75
Letters from readers .....	90
New products and materials .....	80, 82
Patents .....	84
People .....	33
Quotes from papers .....	64
Reports from industry .....	5

# Project | *your career* *in engineering*

advanced projects


diversification

unlimited opportunities

## **AVRO AIRCRAFT**

OFFERS OPPORTUNITIES FOR  
THESE PEOPLE—WITH OR  
WITHOUT AERONAUTICAL  
EXPERIENCE:

Mathematicians  
Computer Programmers  
Aerodynamicists  
Metallurgical Technicians  
Stress Engineers • Systems  
Engineers • Mechanical Engineers  
Flight Test Engineers  
Controls Engineers  
Aero Thermodynamicists  
Vibration & Flutter Engineers  
Civil Engineers for:  
Structural Analysis, Tests, Design  
Computing Specialists  
Draftsmen & Technicians



Avro Aircraft's broad and diversified range of advanced aeronautical design projects gives engineering people unexcelled opportunities to utilize individual ingenuity, initiative, imagination and creative qualities.

All aspects of Engineering at Avro employ the most up-to-date scientific techniques and modern facilities. These are under the guidance

of some of the world's finest engineering talent. As members of a progressive design team, more concentrated job responsibility means more recognition for individual ideas and accomplishments.

You who are interested in responsible work now, on design concepts which represent the most advanced state of your art, should



APPLY BY LETTER TO: THOMAS W. SHAW, EMPLOYMENT MANAGER

**AVRO AIRCRAFT LIMITED**

BOX 4004, TERMINAL 'A', TORONTO, CANADA

MEMBER: A. V. ROE CANADA LIMITED & THE HAWKER SIDDELEY GROUP

## Design Engineering

## Inside

**William Morse**  
*B.Sc., A.M.I.Mech.E., A.F.I.A.S.,  
A.F.R.Ae.S., P.Eng.*

EDITOR

**John Dennis**  
ASSISTANT EDITOR

**George McKechnie**  
**Adrian Nutter**  
ADVERTISING REPRESENTATIVES

**Michael Cutting**  
EASTERN REPRESENTATIVE

**H. M. Sage**  
EASTERN ADVTG. MANAGER

**Desmond English**  
EDITORIAL LAYOUTS

**John F. Foy**  
CIRCULATION MANAGER

**J. W. Sargent**  
RESEARCH & PROMOTION MANAGER

**W. A. Weir**  
ADVERTISING SERVICE MANAGER

**Kathy Hill**  
ADVERTISING PRODUCTION

**Ronald A. Smith**  
MANAGER

**George W. Gilmour**  
MANAGER, INDUSTRIAL NEWSPAPERS

**J. L. Craig**  
DIRECTOR, BUSINESS PUBLICATIONS

Editorial correspondents in: The United Kingdom, the United States, Germany, France and Italy.

The September issue of **Design Engineering** will carry strong feature articles written by contributors no less experienced than those featured this month.

Feature article in the October issue will deal with circular arcs. This article takes the form of a review of the methods of using circular arcs in place of ellipses. Also featured in the same issue will be articles on the many applications of versatile Neoprene and another on chemical milling. The latter is a newly developed process for handling milling which can't be done by machine.




Cushman

**Rob Cushman** is Vice-President in charge of Technical Sales at General Devices Inc. of Princeton, New Jersey. He joined the company in 1954 to manage their sales of high speed motor driven rotary switches. Born a New Yorker, he has wide sales experience in the electronics field and done research on guided missiles and aircraft explosive protective devices—the latter for the National Research Council. A man better qualified to author the article on sampling switches (starts on page 35) would be hard to find.

**Jack H. Goodyear**, author of our article on phosphate coatings which starts on page 50, is Vice-President and Chief Engineer of the J. W. Rex Company. Goodyear took the first steps to this Vice-Presidency in 1943 when he graduated with a degree in Metallurgical Engineering from Lafayette College. He has worked with Bethlehem Steel, the Naval Research Laboratories in Washington and with Westinghouse. In 1948 he formed Chem-Fin Corporation which, in 1955, merged with the J. W. Rex Co. He is a member of both the American Metals and Electro-platers Societies.



Goodyear



Egy

Third in the string of vice-presidential contributors to **Design Engineering** in September is **W. L. Egy** who combines the position with Director of Sales for the Brunson Instrument Co. of Kansas City. Egy has a long career in optical instruments having been some 30 years Chief Engineer for W. & L. E. Gurney. His article on optical tooling (page 42) is by no means his first journey into print on such subjects. He's a graduate of the University of Illinois and holds a B.Sc. in Electrical Engineering and M.Sc. in Physics.

\* **There's been a**  
**Revolution in Rubber**

## Can **POLYSAR** Bring to Life **Your** Product Ideas?

Yes, Polysar *can* give reality to many product ideas, previously impractical with other materials. Why? Because **\*there's been a revolution in rubber.**

Now . . . with Polysar chemical rubbers and the help of Polymer research chemists . . . you can have a rubber tailor-made to fit the exact requirements of *your* product idea.

**Whether rubber now enters into your products or not,** you owe it to yourself to investigate what Polysar can do for them. You'll find—as have manufacturers in 40 countries—that Polysar can make a world of difference.


Polymer Corporation Limited, makers of Polysar rubbers, has the largest industrial research and development division in Canada. Why not make full use of these facilities and learn how Polysar can improve present products and create new ones?

*Write to our Sales and Technical Service Division, Sarnia, Canada.*


### ***Here's How POLYSAR Beat a Critical Insulation Problem***

When Northern Electric Company Limited was looking for an insulation rubber—to be used in underwater electric dredge cables subject to extremely rugged treatment—they chose Polysar Butyl 100. This special type of Polysar gives high resistance to ozone, water, heat and cold; provides excellent dielectric properties; has good flexibility; and is readily processed.

If you, too, have a critical rubber problem, Polymer will be glad to help find the solution.



*Underwater cable,  
insulated with Polysar  
Butyl 100, used by pipeline  
dredge at Steep Rock  
Iron Range in  
North-Western Ontario.*



**POLYMER CORPORATION LIMITED**  
**Sarnia, Canada**

*Distributors in 28 Countries Around the World*



## Reports

### News in brief from the world's producers

ST. THOMAS, ONTARIO — A recent announcement by T. M. Green, the general manager of Redmond Manufacturing of Canada, Ltd. was to the effect that the firm has expanded its plant by 25% in order to produce a new type AY induction motor.

This new fractional horsepower, 110V AC. induction motor will be suitable for air conditioning, window fans, refrigeration, direct drive blowers in central heating systems and other applications.

The object of this new production phase is to meet the growing demands, in an expanding Canadian market, of the air conditioning, ventilating, heating, refrigeration and appliance industries.

An additional 3,000 square feet of floor space has been provided at the St. Thomas plant to handle the production of induction motors in a wide range of sizes up to 1/3 horsepower.

According to Green, the present addition is just a beginning. Plans call for continued Redmond expansion and the addition of facilities to build a Canadian market.

In addition to manufacturing fractional horsepower induction electric motors, the firm will continue to produce 6, 12 and 24 volt motors for automobile heating and defrosting systems. More than 1,500,000 of these units have been produced by Redmond since Canadian operations began in 1948.

• • •

#### A plant of circular design

OAKVILLE, ONT. — Probably the first of its kind on the continent is a polygonal building of 25 sides being built for Canadian Charts and Supplies and the John Wilkes Press in Oakville.

Each of the sides is 16 feet long and the radically designed plant will provide some 13,000 square feet of floor space on one floor with a smaller second floor section at the centre for staff facilities.

Walls will be of concrete block against which earth is banked almost to the roof line. Windows will be installed only 30 deg. from the horizontal and will be just under the roof overhang. The roof itself will be a shallow dome with a ceiling height of between nine and 18 feet. Laminated-wood beams and cantilever design have eliminated most of the steel normally needed in a building of this size.

F. C. D. Wilkes, Jr., president of the company and himself a professional engineer, claims three advantages to a cir-

cular layout. It allows for efficient work flow through the production departments, staff and materials can move from point to point in the building with a minimum of travel and service facilities can be concentrated at the centre where they are equally available to all.

• • •

#### Westinghouse new plant

LONDON, ONTARIO — A new distribution transformer plant, costing between \$2 and \$3 millions, is to be built by the Canadian Westinghouse Company at London, Ontario. The new plant will be another link in the company's multi-million-dollar expansion and decentralization program.

The move was announced by R. H. Williams, general manager of the firm's industrial products group. The plant will be used for the manufacture of distribution and instrument transformers, power capacitors, lightning arrestors and power fuses.

The new plant will employ some 200 people when peak production is reached. Manufacturing space will include 100,000 sq ft with an additional 12,000 sq ft for offices.

"The establishment of a new plant in London follows our announced policy of decentralization wherever feasible," Mr. Williams stated.

The policy of single-line product decentralization adopted by Canadian Westinghouse has seen manufacturing facilities established at several points distant from Hamilton during the past several years. Major moves have sent the company's lighting and lamp divisions to Granby and Three Rivers, Quebec, respectively, and television-radio manufacturing to Brantford. Television tube assembly was recently switched to Grimsby, Ont., and household meters are now

being manufactured at Stoney Creek, Ont. The most recent decentralization step has sent the production of small motors to Stratford, Ont.

The Westinghouse executive stated that this policy is providing all the benefits of straight-line integrated manufacturing and better operating conditions.

Mr. Williams cited increased activity in the growing market for power distribution products as the reason for establishing the modern manufacturing facilities.

"The demand for electric power is apparently insatiable. There is every indication that in the future, whether it be supplied from water or atomic energy sources, it will continue to increase at an even higher rate than it has in the past," he said.

• • •

#### Search for brain power


PASADENA, CALIF.—Two Southern California electronic companies have enlisted the aid of television in their continuing search for scientific brain power.

Consolidated Electrodynamics Corporation and Electro Data Corporation are co-sponsoring a non-fictional popular science program in an effort to attract engineers, technicians and draftsmen to their firms.

Called "Adventure . . . Tomorrow," the weekly half-hour show unfolds in lay terms the latest advances of modern science. It is designed to appeal to the non-technical person as well as the engineer.

The opening show featured films of early V-2 rockets captured in Germany and an interview with Dieter Huzel, the man responsible for that historic rocket. Huzel, one of Germany's top rocket designers during World War II, is now with Rocketdyne, a division of North American Aviation.

Other programs will dramatize operation units that intercept and strike down enemy bombers without actually seeing the planes, a slow-motion study of exploding bullets and electronic instruments which sense more than fingers, see more than eyes and move faster than minds.



Distribution transformer plant for Westinghouse.

# *the Measurement of Industry...*



## Simpson INSTRUMENTS

With measurement an increasingly important function in industry — and Simpson instruments a major factor in the instrumentation field — then Canadian industry and Canadian made Simpson instruments have much in common.

Instrumentation is a complex field and requires, for solutions to industry's problems, the attention and facilities of specialists. That's just what we at Bach-Simpson feel we are — specialists, backed by complete Canadian facilities for manufacture, design and engineering of panel instruments.

If you have a problem in this field, let us have a look at it, regardless of how insurmountable it may appear. Others have — and found in Canadian made Simpson instruments the answers to their problems.



1255 BRYDGES ST.

LONDON, CANADA

IN U.S.A. SIMPSON ELECTRIC COMPANY, 5200 W. KINZIE ST., CHICAGO 44, ILL.

PLEASE VISIT US AT THE  
I.R.E. CONVENTION

Using

# DU PONT ELASTOMERS

## NEOPRENE • HYPALON®



in Design



### HYPALON® can be compounded in an unlimited range of weather-resistant colors

HYPALON, Du Pont's new synthetic rubber, brings brilliant and varied colors as well as superior performance to the design field. Colored compounds of HYPALON start bright . . . stay bright despite severe exposure conditions indoors or outdoors. The samples shown above, for example, were subjected to two years of outdoor exposure. There is virtually no change in color and negligible change in physical properties.

In addition to outstanding color stability, HYPALON has many other advantages that can help your products give *extra-long service* on industry's toughest jobs. Compared to other kinds of rubber, HYPALON shows unusual resistance to hardening at elevated temperatures (250° to 350°F.). It is completely resistant to ozone and has exceptional resistance to strong oxidizing agents.

When your design calls for a resilient material that must have exceptional resistance to these conditions, it will pay you to take a close look at HYPALON.

## NEOPRENE air-brake tube still in service after 5,500,000 flexings

### No downtime in 4 years

The brake element shown is part of a clutch-and-brake unit which is capable of stopping heavy rotating equipment within 1/10 of a second. One such unit has piled up a record of 5,500,000 engagements in four years *without any maintenance*. The key to this kind of performance lies in the design of the machine and in the use of two rayon-reinforced neoprene tubes.


Typically, two of the pictured elements are used together, one serving as the clutch, the other as the brake. When the stop switch is thrown, compressed air is released from the neoprene tube in the clutch element; this disengages friction plates in the clutch and disconnects the drive motor from the driven machine. At the same time, in the brake element, compressed air is admitted to the neoprene tube, engaging friction plates and halting the machine.

### Neoprene resists oil, high temperatures

Neoprene's superior oil resistance and durability at high temperatures have made the performance of this clutch and brake possible. Natural rubber tubes previously used were deteriorated by heat and by the oil that almost invariably gets into any compressed-air supply. They swelled, and the inside surfaces tended to become tacky and stick together. When rayon-reinforced neoprene air tubes were used, the problem was solved.

### Neoprene makes a better design

In designing new products or improving old ones, neoprene stands up where ordinary resilient materials fail. Neoprene offers the designer resistance to oil, heat, weathering, chemicals and abrasion. It improves product performance—cuts maintenance costs. Complete property data and typical neoprene application data are available.



SECTIONAL VIEW of brake element, with  
Neoprene air tube in red



HYPALON is a registered trademark of  
E.I. du Pont de Nemours & Co. (Inc.)

### MAIL THIS COUPON TODAY!

Please send further information and add my name to the mailing list for your free publications, the "Neoprene Notebook" and "Facts about HYPALON®," which show how the Du Pont elastomers are used in designing new products, improving old. I am particularly interested in

Du Pont Company of Canada Limited,  
Chemicals Department, Room A-4,  
P.O. Box 660, Montreal, Que.

Name \_\_\_\_\_ Position \_\_\_\_\_  
Firm \_\_\_\_\_  
Address \_\_\_\_\_  
City \_\_\_\_\_ Prov. \_\_\_\_\_



DE-9

# New Design Applications of Ductile Iron based on its Many Advantages

Ductile irons are a group of cast metals which combine the processing advantages of cast iron with many of the engineering advantages of steel. This is a result of a low melting point, good fluidity and castability and high machinability plus a useful combination of strength, toughness, ductility and wear resistance.

Ductile iron permits the production of castings which are intricately shaped or have very light sections and yet must withstand severe service conditions.


Ductile iron castings are not subject to size limitations. They are produced commercially in weights varying from 2 ounces to 100,000 lbs. with section thickness varying from 0.10" to 48".



▲ Wheel of ductile iron 80-60-03 type. Part of the suspension and running gear of the famous Spanish-American Cable Car that spans the gorge at Niagara Falls, Ont. Supplied by Welland Iron & Brass Limited, Welland, Ont.


◀ Ductile iron 100" pitch diameter gear of the 86-60-03 type produced by Letson & Burpee Ltd., Vancouver, B.C.





A good example of the intricate castings possible with ductile iron. These 60-45-10 type were cast by Bell Foundry Co. Ltd., St. James, Manitoba, to be used on a grain swather. Notice flat bar test piece, at right, twisted in ductility test.

A sample of an exacting casting that must be able to absorb shock, possess torsional rigidity, have excellent wear resistance and yet be readily machinable. This ductile iron crankshaft of 80-60-03 type was cast by Canada Iron Foundries, Limited, Special Products Plant, Hamilton, Ont.




## Ductile Irons Prove Economy Both in First and Overall Cost

Ductile iron castings are not expensive even in the first cost. But, more important, parts made of ductile iron have proved, in many cases, extremely economical in overall or ultimate cost. The superior properties of ductile iron have enabled castings to replace more costly forgings or welded structures. Their good machinability has effected important savings in machine shop time and labour. Their resistance to wear, shock or elevated temperature frequently permits their replacement of more costly materials and enables them to perform satisfactorily for a longer time.



**THE INTERNATIONAL NICKEL COMPANY  
OF CANADA, LIMITED**  
25 King St. W., Toronto, Ontario



Ductile iron Jungle Trac, a type of equipment which adapts tandem axle trucks to half track for off-the-road service. Parts include adjustable links or "dumbbells", and bushings which were cast by Otaco Limited, Orillia, Ontario, in their 60-45-10 Ductalloy.

**THE INTERNATIONAL NICKEL COMPANY  
OF CANADA, LIMITED,  
25 King St. W., Toronto, Ontario.**

Please send me a copy of "Ductile Iron—The Cast Iron That Can Be Bent", which illustrates many applications and properties of ductile iron.

NAME.....

COMPANY.....

ADDRESS.....




DH



ALUMINUM . . . NICKEL ALLOYS . . . STAINLESS STEELS

**FOR FLUIDS  
HANDLING...**

**ONE  
REFERENCE**



**ONE  
SOURCE**



**for VALVES...**



**for FITTINGS...**



**Pipe and Tubing...**



**in Aluminum - Nickel Alloys -  
Stainless Steels**

Thousands of items in Aluminum, Nickel Alloys and Stainless Steels are available to help you combat corrosion. One reference, the Alloy Metal Sales Fluids Handling Catalogue, supplies complete information, indexed and arranged for your convenience. One source, Alloy Metal Sales Limited, makes all these products available to you through conveniently located stocks. It's all wrapped up in "one package" ready for you.

When you want Aluminum, Nickel Alloys and Stainless Steels in all forms ( . . . even including fastenings) write or phone.



**ALLOY METAL SALES LIMITED**

**TORONTO • WINNIPEG • MONTREAL**

**INCO NICKEL ALLOY PRODUCTS**

(Monel, Nickel, Inconel, Incolay, Nionel)  
are distributed by

Robert W. Bartram Ltd., Montreal, in Quebec and  
the Maritimes

Wilkinson Company Limited, Vancouver and Ed-  
monton, in British Columbia and Alberta.

# SKF


THE FINEST BEARINGS IN THE WORLD



Salute to  
ONTARIO

CANADIAN **SKF** COMPANY  
LIMITED

HEAD OFFICE AND MANUFACTURING DIVISION, 2201 EGLINTON AVENUE EAST, SCARBORO, ONTARIO  
DISTRICT OFFICES: QUEBEC, MONTREAL, TORONTO, FORT WILLIAM, WINNIPEG, REGINA, CALGARY, EDMONTON, VANCOUVER



## In production work too— G-E Silicones prevent sticking...

Now, flies can't read . . . or understand English, either. This one didn't know about G-E Silicone Release Agents and was soon a dead duck . . . or fly. However, a large number of Canadian industries use G-E Silicones to solve many sticky problems. By keeping *things* from sticking together, G-E Silicones are speeding production, cutting costs and improving products. Don't you get stuck. Take the tip and learn more about these amazing release compounds.

**For instance glass molders** are using an especially designed G-E Silicone for releasing glass from molds. It gives a better surface finish, eliminates smoke and fumes and improves working conditions. It provides higher bursting strength, better mar resistance, cleaner molds, longer mold life and less maintenance.

**Paper treated with G-E Silicone** is used as anti-stick or anti-block sheets. It keeps raw rubber slabs, asphalts and resin products and many other materials from sticking together in production and packaging.

**Another G-E Silicone Mold Release Agent** used in making tires, fabricated parts, tiles and plastics give better release, better finish, fewer rejects and saves on mold-cleaning down-time.

**SEND FOR FREE LITERATURE**

**In the revolutionary Shell Molding Process** G-E Release Emulsion No. SM55 has made possible castings that do not have to be machined. The cured sand-resin shells are freed easily from metal patterns, to produce perfect reproductions everytime.

You owe it to yourself to know more about the many G-E Silicone Release Agents and how they can be used in your business.



# SILICONES

Chemical Material Sales  
Canadian General Electric Co. Ltd.  
1601 Davenport Rd., Toronto, Ontario

C.C.-1/457W-1255

Please send the literature checked below to:

- ☐ The Silicone Story
- ☐ General Release—Rubber, Plastic, Tiles, Die Casting
- ☐ Silicones For Glass Molding
- ☐ Shell Molding
- ☐ Silicones For Release Papers

NAME

COMPANY

ADDRESS



CITY  PROV.

**CANADIAN GENERAL ELECTRIC COMPANY LIMITED**



INSTRUMENTATION CAMERA  
AND AUTOMATIC  
TRI-FILM PROCESSOR

# PRECISION'S PERFECT PAIR



## SPECIFICATIONS

### INSTRUMENTATION CAMERA TYPE T232 Mk7

Size: 7½" x 5⅞" x 6½"  
Weight: 13 lbs.  
Power: 28 volts DC; constant demand .4 amperes; intermittent up to 1.8 amperes. The Type T232 DC power supply, which operates from 110v 60 cps, is available to power the camera.  
Lens: 28mm Augenieux F3.5, or to customer specification  
Magazine: 100 ft. 35mm standard sprocketed film, No. 10 daylight loading spool. 400 ft. magazine available on special order  
Picture Formats: 18x25, 25x25 or 25x36 mm.  
Exposure: 1/100 second, or longer with intervalometer control  
Interval Time: 3 cycles per second maximum

### AUTOMATIC TRI-FILM PROCESSOR TYPE T246 Mk3

Size: 54" long, 22" wide, 51" high  
Weight: 400 lbs.  
Power Consumption: 5 KVA maximum single-phase; 110 volts, 45 amps, or according to customer requirements  
Process Capacity: 1 to 4 rolls 16 mm length  
1 or 2 rolls 35 mm to  
1 roll 70 mm 400 ft.  
Rate of Processing: 1½, 3 or 6 ft. per min.  
Temperature-controlled solutions and dryer  
Daylight operation except loading of film into magazine  
Processes perforated or plain film

Here is the perfect answer to the problems of film recording and the obtaining of quick results without loss of quality. The Mark 7 Instrumentation Camera is completely flexible through the entire field of instrumentation and aerial survey positioning photography. The shutter is a focal plane type, the basic exposure speed of which is 1/100 second. The camera may be cycled from 3 frames per second to any desired longer interval. Interchangeable apertures permit photographs of 18x25, 25x25 or 25x36 mm. A high degree of accuracy is achieved in respect to lens alignment, focusing and format positioning. Main components designed on the "module" system make conversion from one camera type to another relatively simple should customer requirements change.

A fitting companion is the transportable Mark 3 Automatic Tri-Film Processor that develops and dries 16, 35 or 70 mm film at 1½, 3 or 6 feet a minute. Four 400-ft. 16 mm films can be handled simultaneously—or two 400-ft. 35 mm films—or one 400-ft. 70 mm length. The various film sizes are accommodated by simple adjustments of film separators. Separate temperature control of the processing solutions is possible on each tank from 60 to 110 degrees F, within ± 1 degree. The latest high temperature chemical resistant plastics and Type 316 stainless steel are used in all chemical areas. Write for literature and quotations.



## PSC APPLIED RESEARCH LTD.

1500 O'CONNOR DRIVE  
PLYMOUTH 5-3371

TORONTO 16, ONTARIO, CANADA

"Visit our exhibit at the Canadian I.R.E. Convention"  
Booths 346, 348 and 350  
Toronto — October 1, 2 and 3

# TORRINGTON CUSTOM-MADE BEARINGS



**"This 63" bearing was custom-made for us—by TORRINGTON!"**

Building custom bearings for industry is a Torrington specialty. Whatever the anti-friction assignment—Torrington can design and build the bearing for the job.

When you specify a Torrington job-designed bearing, you're calling on engineers with extensive experience in custom-bearing applications. Torrington will survey your needs, recommend and design the right bearing to provide peak efficiency, economy and service life.

For *any* standard or custom bearing, backed by broad manufacturing and design experience—specify TORRINGTON.

THE TORRINGTON COMPANY, LTD.  
925 Millwood Road, Toronto 17, Ont.  
*District offices and distributors in principal cities of  
United States and Canada*



## **TORRINGTON BEARINGS**

Spherical Roller • Tapered Roller • Cylindrical Roller  
Needle • Ball • Needle Rollers

DESIGN ENGINEERING SEPTEMBER 1956

# Get this Catalog!

For help  
in fluid line  
system design . . .

Aeroquip's new 64-page industrial catalog is packed with product information on twenty-six types of high, medium and low pressure hose with reusable fittings, plus adapters and couplings.

You'll find 18 pages of valuable fluid line data to help you in the planning, engineering and installation of fluid line systems on all kinds of industrial equipment.

Aeroquip also offers separate catalogs giving complete information on Aircraft and Marine Hose Lines and Couplings. Fill in and mail the coupon below for your copies.

## NO COST TO YOU . . . JUST FILL IN AND MAIL THIS COUPON

Aeroquip (Canada) Ltd., Toronto 15, Ontario

Gentlemen:

Please send me the new, illustrated Aeroquip catalog checked at the right.

Name

Title

Company

Address

City  Zone  Province

☐ Industrial  
No. 200

☐ Aircraft  
No. 100

☐ Marine  
No. 300

**Aeroquip**  
REG. TRADEMARK

**AEROQUIP (CANADA) LTD.**

TORONTO 15, ONTARIO, CANADA


LOCAL REPRESENTATIVES IN PRINCIPAL CITIES

AEROQUIP PRODUCTS ARE FULLY PROTECTED BY PATENTS  
IN U. S. A. AND ABROAD

# OHMITE®

has exactly  
the resistor you need

Ohmite offers the most complete line of wire-wound resistors on the market . . . fixed, adjustable, tapped, non-inductive, and precision resistors in many sizes, types of terminals . . . in a wide range of wattages and resistances.



## Industry's most complete line of wire-wound resistors!

The extensive range of Ohmite types and sizes makes possible an almost endless variety of Ohmite resistors to meet each individual need. Ohmite offers resistors in more than 60 sizes—ranging from 2½" diameter by 20" long to ¼"

diameter by ⅛" long—to meet your exact requirements. **MANY SIZES ARE CARRIED IN STOCK.** These rugged resistors have proved their quality under the toughest operating conditions. Ohmite application engineers will be pleased to help you in selecting the right resistors for your job.

Write on company letterhead for  
Catalog and Engineering Manual No. 40.

**OHMITE MANUFACTURING COMPANY, 3688 Howard Street, Skokie, Illinois (Suburb of Chicago)**



*Be Right with* **OHMITE®**

**RHEOSTATS • RESISTORS • RELAYS • TAP SWITCHES**

A. C. SIMMONDS & SONS  
100 Merton St., Toronto 12







C. M. ROBINSON  
189 Market Ave., East, Winnipeg 2



# WHAT'S IN A NAME PLATE?




for gear units...  
**you name it,  
we supply it!**


- 
**COMPLETE RANGE OF RATIOS**
- 
**ANY APPLICATION**
- 
**ANY SIZE**
- 
**ANY TYPE**
- 
**ANY HORSEPOWER**
- 
**STANDARD OR SPECIAL DESIGN**

write for gear unit bulletin 368-53G

<b>DOMINION ENGINEERING</b>			
COMPANY LIMITED			
<b>INDUSTRIAL DIVISION</b>			
MONTREAL	TORONTO	WINNIPEG	VANCOUVER



## **KNOCKED OUT COLD . . .**



**This COLD HEADER transforms wire into upset parts**



**WITH TWO BLOWS**

## **RAPIDLY, CHEAPLY, WITHOUT WASTE!**

The economy, speed, and versatility of Stelco's Cold Heading equipment offers wide possibilities for savings in contoured and specially shaped parts.

The examples shown above are ordinary every-day ones . . . yet they show savings in metal costs alone of as much as 63.5% in comparison with similar parts produced by machining. In addition, they are produced by Stelco at rates from 60 to 250 per minute, against a maximum of about 40 per minute for automatic screw machines.

On Stelco's Cold Headers, wire up to 1" in diameter, of any forgeable metal, can be upset to  $4\frac{1}{2}$  times its original diameter, with secondary operations such as threading, punching, shaving, or bending being added if desired.

Stelco Engineers will be glad to advise on the adaptability of cold heading to *your* needs. Address your enquiries to any Stelco Sales Office.




### **THE STEEL COMPANY OF CANADA, LIMITED**

*Executive Offices: Hamilton — Montreal*

Sales Offices: Halifax, Saint John, Montreal, Ottawa, Toronto, Hamilton, London, Windsor, Winnipeg, Edmonton, Vancouver, J. C. Pratt & Co. Limited, St. John's, Newfoundland

55121.8



"3M" Coating EC-244 is used to protect underground manifold piping, valves, etc., against soil corrosion.

## Solving the problems of design /

### '3M' offers 1000 different types of adhesives, coatings and sealers

There is virtually no limit to the number of materials that can be joined, coated or sealed with "3M" Brand Adhesives, Coatings and Sealers. Wood, plastics, rubber, glass, leather, metal and many other types of materials, which once were joined with mechanical fasteners, are now being held firmly and permanently with "3M" Brand Adhesives. These same materials can be protected or insulated with "3M" Brand Coatings. Gaps and voids can be closed, metal components separated to avoid galvanic corrosion, by the use of "3M" Brand Sealers. When it's a question of adhesives, coatings or sealers—consult your "3M" representative for complete information.



"3M" Sealers are widely used in the aircraft and automotive industries.



"3M" Adhesive EC-770 being applied to the inside edges of hot air register for bonding a felt strip gasket.



Applying "3M" vinyl protective coating to a part of an offshore drilling rig.



**3M**  
COMPANY

**ADHESIVES, COATINGS, SEALERS**

**MINNESOTA MINING & MANUFACTURING OF CANADA LIMITED • LONDON • CANADA**

Sales Offices: Halifax • Montreal • Toronto • Winnipeg • Saskatoon • Calgary • Vancouver  
Resident Salesmen: Saint John • Quebec City • Ottawa • Hamilton • North Bay • Regina • Edmonton





Morrow  
screws + nuts  
are

FATIGUE PROOF

YOUR PRODUCTS STAY TOGETHER, because Morrow Screws and Nuts are heat treated for stress relief. Vibration and shock won't break down their fastening qualities!

MORROW quality screws and nuts meet and exceed automotive specifications.

In addition to all MORROW "Standards", we would be pleased to manufacture specials to your specifications.

**MORROW SCREW AND NUT**  
I N G E R S O L L   C A N A D A   C O M P A N Y   L I M I T E D


TORONTO — 125 McCormack St. MONTREAL — 389 St. Paul St. W.

MARITIMES — C. D. Murdock, P.O. Box 274, Amherst, Nova Scotia

WINNIPEG — Harry F. Moulden & Sons, 171 Market Ave.


VANCOUVER — Harry F. Moulden & Sons, 9-501 Main St.





**A manufacturer of metal stampings\* writes:**

"There are many outfits offering something like Parkerizing, but we want the real thing."



Some typical parts which are protected from rust by treatment with Parco Compound

Parco Compound† (Parkerizing†) is the original rust-resistant phosphate coating for iron and steel. For forty-two years it has protected hundreds of different types of products—from bolts to boats.

There are other products "like" Parkerizing, but none quite so effective, so dependable, so thoroughly tested and proven.

Parkerizing is simple, fast, and costs very little. It can be used on any iron or steel article which can be immersed in the tanks. Since it does not change the dimensions of the treated parts, it is excellent for threaded or close-fitting components. Parts treated with Parco Compound may be finished with stains, waxes, oils or paint.

**You, too, should demand "the real thing." Use Parkerizing for rust resistance.**

\*Name on request.

†Parkerizing, Parco—Reg. U.S. Pat. Off.

# PARKER RUST PROOF COMPANY'

OF CANADA, LTD.

REXDALE BLVD., REXDALE (TORONTO) ONT.

**BONDERITE**  
corrosion resistant  
paint base

**BONDERITE and BONDERLUBE**  
aids in cold forming  
of metals

**PARCO COMPOUND**  
rust resistant

**PARCO LUBRITE**  
wear resistant for friction  
surfaces

**TROPICAL**  
heavy duty maintenance  
paints since 1883





## Wallace Barnes produces **Two** benefits!

Just as every father is proud of his offspring, we're proud of *our* two babies . . . "quality" and "service."

"Service" means that our outstanding laboratory facilities, engineers and technicians are always at *your* side, ready to help *you* with *your* problems . . . and "quality" means Wallace Barnes precision springs assure the good name of your product even under the severest conditions.

"Quality" springs are the only kind Wallace Barnes will ever make . . . or sell.

PICTURE  
BOOK  
OF  
SPRINGS


### FREE BOOKLET

Our PICTURE BOOK OF SPRINGS is a photographic reference of the many different types of springs made. This indexed book can save time for busy purchasing agents and engineers . . . completely FREE . . . a letter or penny postcard with your name and address is all that is needed!

## WALLACE BARNES CO. LTD.


Department 124

Hamilton, Ontario




# SAGINAW b/b SCREWS are guaranteed 90% EFFICIENT!


Require 2/3 LESS torque than Acme Screws for same linear output on Actuator and Positioner Applications! Saves space, weight!



## WHAT IT IS AND HOW IT WORKS




Let's start at the beginning, with the familiar principle that there's far less friction in *rolling* than in *sliding*. By applying this principle,



the Saginaw ball/bearing Screw radically increases the efficiency of rotary-to-linear motion (and vice versa). Instead of *sliding*, mating surfaces *glide* on rolling steel balls.



Like stripes on a barber pole, the balls travel toward end of nut through spiral "tunnel" formed by concave threads in both screw and mating nut.



At end of trip, one or more tubular guides lead balls diagonally back across outside of nut to starting point, forming closed circuit through which balls recirculate.

## DESIGN ADVANTAGES

- 1. Increases efficiency** — Acme screw is 15%-20% efficient — b/b screws are 90%-95% efficient.
- 2. Saves power** — requires 2/3 less torque than Acme screws for same linear output.
- 3. Saves space** — permits smaller motors, gear boxes; eliminates pumps, piping, accumulators.
- 4. Assures positive positioning** — permits precision control within thousandths of an inch.

## SAGINAW b/b SPLINE



Utilizing the same basic *gliding ball* principle, Saginaw has developed the *Saginaw b/b Spline* which radically increases the efficiency of transmitting or restraining high torque loads. **Averages 40 times lower friction coefficient than sliding splines!**

It can be fitted with integral gears, clutch dogs, bearing and sprocket seats, etc., for use with a wide variety of electrical units. **AVAILABLE IN ALMOST ANY SIZE.** (Units have been engineered as small as 3/8 IN. IN DIAMETER.)

**Saginaw**  
ball/bearing  
Screws & Splines

SAGINAW STEERING GEAR DIV., GENERAL MOTORS CORP., SAGINAW, MICH.

DESIGN ENGINEERING SEPTEMBER 1956

## SEND COUPON FOR 32-PAGE ENGINEERING DATA BOOK

Saginaw Steering Gear Division, General Motors Corporation  
b/b Screw and Spline Operation  
Dept. 9W, Saginaw, Michigan  
Please send new engineering data book on Saginaw b/b Screws and Splines to:

NAME \_\_\_\_\_

COMPANY \_\_\_\_\_ TITLE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY \_\_\_\_\_ ZONE \_\_\_\_\_ PROV. \_\_\_\_\_


# Only MAGIC-GRIP Sheaves Give You These 4 Most-Needed Features

**1** Full-length contact between bushing and shaft. Sheave can't get out of alignment or develop excessive run-out because pressure is applied equally all around bushing along full length.

**3** *Magic-Grip* Sheave installs quickly, easily as a unit instead of in two pieces — simply slip sheave on shaft and tighten screws. Complete sheave can be moved back and forth on shaft to adjust position.

**2** Torque between bushing and shaft, and between bushing and sheave is transmitted by keys instead of threaded screws. Thus jamming of screws from shock overloads is eliminated.

**4** Cap screws in *Magic-Grip* Sheaves are full-threaded, engage full thread instead of partial. This ends stripping and jamming problems.



**TEXROPE**  
Sheaves with  
**Magic-Grip**  
Bushings

All Allis-Chalmers sheaves are available with *Magic-Grip* bushings. For complete information contact your nearest authorized *Texrope* drive dealer, or CA-C Sales Office or write direct to Canadian Allis-Chalmers Ltd., P.O. Box 37, Montreal, Quebec.

Check This Comparison of MAGIC-GRIP Sheave with Other Sheaves

	Magic-Grip Sheaves	Sheave A	Sheave B	Sheave C
Bushing fully split for full-length, full-circumference grip	Yes	Yes	No	Yes
Torque carried by keys instead of threaded bolts	Yes	No	No	No
All screws engage all threads fully	Yes	Yes	Yes	No
Mounts in one piece	Yes	No	Yes	Yes

MADE IN CANADA

## CANADIAN ALLIS-CHALMERS

*Texrope* and *Magic-Grip* are Allis-Chalmers trademarks.





# NODULLOY

... the ductile iron ...  
is being adopted by more  
and more industrial  
groups for applications  
such as :

Crankshaft for high  
pressure power pump  
cast in ductile iron.

- PRINTING ROLLS
- GEARS AND WORM WHEELS
- CAST-TO-SHAPE DIES
- CRANKSHAFTS
- FLYWHEELS
- HYDRAULIC RAMS
- MACHINE TOOL CASTINGS
- FARM IMPLEMENT CASTINGS
- RAILROAD EQUIPMENT

...typical properties...

	TENSILE	YIELD	ELONGATION	BRINELL
AS CAST	80,000 p.s.i. to 100,000 p.s.i.	60,000 p.s.i. to 75,000 p.s.i.	1-3%	225-300
ANNEALED	60,000 p.s.i. to 75,000 p.s.i.	45,000 p.s.i. to 60,000 p.s.i.	10-20%	140-180
HEAT TREATED	80,000 p.s.i. to 160,000 p.s.i.	65,000 p.s.i. to 150,000 p.s.i.	1-15%	160-340

...and when to specify it...

1. As a replacement for conventional cast iron, where greater strength or resistance to impact is needed.
2. In redesigning, where higher strength results in less weight — hence lower cost.
3. In place of large malleable iron castings which can be difficult and costly to produce.
4. To replace many steel castings, where higher yield strength and better machinability are important.
5. Where heat resistance is a factor, because of Noduloy's resistance to growth.
6. For "wear resistance" applications which may involve chilling, induction or flame hardening of wearing surfaces.

If you have an application for NODULLOY or wish to have more information on the subject,  
write to:

**Canada Iron**  
foundries, limited

Foundry and Machine Division

921 SUN LIFE BLDG., MONTREAL


171 EASTERN AVE., TORONTO

# **This hydraulic unit controls air cylinder movement with** *21-Jewel Precision*

**Compact and self-contained, the Bellows Precision Hydro-Check has automatic flow and thermal regulators built-in**

With the Bellows DCP-50A *Precision Hydro-Check* you can make the piston rod of an air cylinder move with clockwork accuracy. Equipped with a DCP-50A an air cylinder can be used to power the most critical tool and work feeding operations . . . because control is virtually 100% uniform.

Hard and soft places in the material being worked do not affect feed rate. Variations in air pressure have no effect on cutting tools. For



this Precision unit sets up a perfectly controlled hydraulic "check" that smooths out the natural bounce and chatter of air. Its built-in flow regulator automatically compensates for changes in work load and air line pressure . . . giving the power stroke of an air cylinder a smoothness unmatched even by conventional hydraulic cylinders.

Once the calibrated control knob is set for the feed rate desired it may be locked and forgotten. Resetting is unnecessary. On Monday morning, after an idle weekend, it duplicates Friday's performance. No "warm-up" periods are needed. There is no "drift" as operating temperature rises. The built-in thermal regulator automatically corrects the DCP-50A for changes in oil viscosity.


The Bellows DCP-50A Precision Hydro-Check will effectively check thrust loads up to 3,000 lbs. Easily installed on Bellows Air Motors or conventional air cylinders, it is available in stroke lengths of 2, 4, 6, 9, 12, 15 and 18 inches to meet a wide variety of needs. It can also be furnished as an integral part of the Bellows Air Motor . . . the air cylinder with built-in control valve.

FOR COMPLETE INFORMATION  
ON BELLWS HYDRO-CHECKS  
WRITE DEPT. DE 956

**Bellows**  
**Pneumatic Devices of Canada, Ltd.**  
14 ADVANCE ROAD TORONTO, CANADA

1327A

# DICTATED BY PRODUCT IMPROVEMENT:



HE'S SPEAKING INTO THE NEW DICTAPHONE "PRESIDENT" dictating machine that puts dictation on your secretary's desk automatically. Power control microphone and cradle are molded of CYMEL® Melamine Molding Compound that speeds up Dictaphone production and gives the finished product a permanent, brand-new look. Reason: Color is molded in, can't chip or wear off in handling, needs no coating. Molded CYMEL has a pleasant "feel," rich appearance, strength and scratch resistance that assure long life. Pick up your Dictaphone dictating machine and write for complete information.



**NEW HEIGHTS IN SAFETY AND STRENGTH:** Putnam Rolling Ladder Company utilizes sandwich construction of glass fiber and LAMINAC® Polyester Resin to create light-weight ladders with non-conducting properties that make them ideal for power and electrical work. Their non-corrosive properties and superior strength make them ideal for chemical plants—in fact, they're excellent for any kind of plant under any kind of condition. Consider the advantages of chemical, abrasion, impact, arc- and weather-resistant LAMINAC for your product.

There's everything to gain in learning how your product or process can use the proved superiority of Cyanamid melamine, urea and methylstyrene molding compounds... polyester resins... resin adhesives... resins for surface coatings. Dictate a letter or give us a call.

#### IN CANADA:


North American Cyanamid Limited, Toronto and Montreal

#### OFFICES IN:

Boston • Charlotte • Chicago • Cincinnati • Cleveland • Dallas • Detroit  
Los Angeles • New York • Oakland • Philadelphia • St. Louis • Seattle



**NO GLUE FAILURE IN THREE YEARS:** White Furniture Company, respected maker of many kinds and styles of fine furniture, uses Cyanamid's URAC® 185 in cold press operations for gluing woods into proper thicknesses for columns, legs and curved portions. Before using URAC 185, various bonding problems were encountered. Since its use, three years ago, *White hasn't had one instance of glue failure!* URAC 185, the glue that does hold a square peg in a round hole, is the rotproof, lifetime glue that can eliminate your rejects and complaints.



***Designed to meet rigid  
Government specified drop-test***

## **C-G-E DESIGNED AMMUNITION BOX SOLVES PROBLEM**

***Re-use Feature Saves Money for RCAF...***

This unique ammunition box below is just another example of G-E Polyester Moldings at work... solving problems and saving money. This moisture-proof, explosives container can be stored outside... can be opened regularly for inspection and *re-sealed* with no adverse effect. The container is lightweight, easy to handle, strong, durable, and proved superior to other materials. RCAF ordnance was handicapped by the lack of these advantages in previous containers.

The applications of G-E Polyester Moldings are many and varied. Every day new uses are discovered for this versatile plastic, uses that create new products and new markets. For instance—Polyester Moldings could be used in a wide range of products, from lawn furniture to luggage, from safety helmets to wheelbarrows. Polyester Moldings resist chemical action and are available in every colour of the rainbow.

Perhaps such versatility could give your product a helping hand. Many times low-cost Polyester Resins have added new life to an old product, have duplicated the favourable characteristics of materials formerly used at worthwhile cost savings.

For further information—contact the Plastic Advisory Service, Canadian General Electric Company Limited, Cobourg, Ontario.





***Wins Industry Awards!***

This Ammunition Box won First Award in its Division in the 1956 Canadian Plastics Achievements Competition and won top honours in the 1956 Canadian Industrial Container Competition sponsored by Packaging Association of Canada.

## **CUSTOM MOLDED PLASTICS**

**CANADIAN GENERAL ELECTRIC COMPANY LIMITED**





## Braking big wheels won't burn SIRVENE H-T OIL Seals

**Now generally available, C/R's new sealing material resists temperatures up to 350° F.**

**Why the heat's on**—Bigger engines, higher speeds, faster deceleration . . . these factors have pushed up temperatures in brake drums, axles, pinions and transmissions. Burn-out of oil seals has become a costly problem. With miles per year jumping to 120,000 and more, maintenance men know that standard oil seals can't take the heat, won't go the distance required on today's high-mileage fleets.

**C/R research solves it**—Sirvene HT Oil Seals are available in a series of high temperature synthetic rubber compounds developed from special polymers for exceptionally hot applications. They seal effectively at temperatures up to 350° F. With a longer service life than any previously known heat-resistant sealing material, Sirvene HT Oil Seals mean big savings for operators of trucks, buses, tractors, road machinery, automobiles and aircraft.



**PERFECT  
Oil Seals**


**SUPER OIL SEAL MFG. CO., LIMITED  
HAMILTON, ONTARIO**

IN THE U.S.A., CHICAGO RAWHIDE MANUFACTURING COMPANY, CHICAGO 22, ILLINOIS



—Other C/R Products—

SIRVENE: (Synthetic Rubber) diaphragms, boots, gaskets and similar parts for critical operating conditions • Rawhide hammers and mallets




(Courtesy MacCraft Industries Ltd., Sarnia)

## TOUGHENED FOR A TOUGH LIFE... BY **C-I-L FINISHES**

These moulded plywood chair seats and backs, made by MACCRAFT INDUSTRIES LTD., lead a tough life, to equip them for rugged service. MacCraft uses C-I-L 4021-1 Pale CILUX Rubbing and Polishing Varnish. Scuffproof, protective, good-looking, this durable finish actually toughens the chair-units, and increases the length of their life.

Meeting such requirements is a regular achievement for C-I-L. In Canada's most modern Laboratories new finishes are constantly being developed — for metals as well as for wood. Find out now how a C-I-L finish can protect *your* industrial product.



Spraying chair units at the MacCraft plant in Sarnia, Ont.

For Technical Information Bulletin  
No. 76 — 4021-1 Pale CILUX  
Rubbing and Polishing Varnish  
write: Canadian Industries Limited,  
Paints Division, Dept. 405,  
Box 10, Montreal, Que.

# industrial finishes

**C-I-L**  
**PAINTS**

HERE IT IS

# Cleveland Speed Variator



NOW available in 9 sizes, ranging from one-half to 10 horsepower at 1750 input RPM.

**I**NFINITELY variable, stepless speeds within a 9:1 range (from  $\frac{1}{3}$  to 3 times the input speed).

Smooth, instant change of speed by simple manual adjustment or by remote control devices, either manual or power operated.

Operating efficiencies—75% to 90%.

Coaxial input and output shafts, rotating in same direction, either clock-wise or counter clock-wise.

Ample bearing support for both input and output shafts to carry overhung pulleys.


Compact and inherently quiet and smooth running, due to simple construction.

Minimum maintenance and long life, due to absence of belts and other complicated linkage.

Performance proved by prolonged tests in the laboratory and field operation.


These are the outstanding advantages of the Cleveland Speed Variator. It is now ready for service. Immediately applicable to a wide variety of machines and equipment where a dependable variable speed drive is required. For detailed description and specifications, write for Bulletin K-200.

## HOW THE CLEVELAND SPEED VARIATOR WORKS




Power is transmitted from input shaft to output shaft through alloy steel driving balls which are in pressure contact with discs attached to the two shafts.

Relative speeds of the shafts are adjusted by changing the positioning of axes on which the balls rotate (see diagrams, left, and cutaway view, right).



Made in U. S. A. by

**CLEVELAND WORM & GEAR COMPANY**



Sold in Canada by

**PEACOCK BROTHERS LTD.**

P. O. Box 1040, Montreal 3, Que.

Branches in SYDNEY, TORONTO, SUDBURY, WINNIPEG, EDMONTON, CALGARY AND VANCOUVER

## THE BIG WIND IN CANADA

Now available to major producers of heavy-duty air moving equipment: an important new Torrington line of complete blower units for domestic heating, central air-conditioning and other high-capacity cooling. The new units are available in these sizes:



9½" x 9½"	10⅝" x 8"
9½" x 7⅛"	12⅝" x 12⅝"
10⅝" x 10⅝"	12⅝" x 9½"

Many advanced construction features are incorporated in all units. In addition, Torrington introduces an entirely new principle of blower wheel construction:

*The center disc is dovetailed under pressure into the encircling blades. As a result, the interlocking joint tightens under centrifugal force, thus eliminating blade rattle and angle warp at high speeds.*

The advanced engineering behind this announcement is backed by Torrington research and development of air impellers now contributing to the success of products valued at nearly 4 billion dollars a year.

Quite a breeze!...Your inquiries are invited.



---

THE  
**TORRINGTON**  
MANUFACTURING COMPANY  
OF CANADA LIMITED  
OAKVILLE, ONTARIO  
TORRINGTON, CONNECTICUT • VAN NUYS, CALIFORNIA




## People

### Important people who are in the news

On June 5 the Dominion Council of Professional Engineers elected its president at the annual meeting in Saskatoon. Elected to the presidency of the 32,000-member Council, which represents the engineering associations of all provinces, was 53-year-old **Edward J. Durnin, P.Eng.**, of Regina.

Mr. Durnin's birthplace was Dauphin in Manitoba though his public and high school education took place in Saskatchewan at Melfort. He received a Bachelor of Arts degree from the University of Saskatchewan in 1924 and later returned to the province of his birth where he qualified for his degree as a Bachelor of Applied Science in Electrical Engineering at the University of Manitoba in 1928. From 1924 to 1927 he had been



**The man the engineers elected**

active on forestry patrol operations as a Pilot Officer with the RCAF.

On leaving the University of Manitoba Mr. Durnin joined Canadian Westinghouse in Hamilton, Ontario, and on graduating from the company's engineers training course in 1930 he went with the Saskatchewan Power Commission—an association which, with the exception of the war years, stretches unbroken up to the present. His career with the commission is traced as follows: assistant engineer, Regina; district superintendent, Saskatoon; assistant superintendent, Saskatoon power plant; commercial superintendent, Regina; and finally his present post with the commission which is that of engineer in charge of construction, transmission, distribution and substations.

Logically enough, Mr. Durnin's war service was with the Corps of Royal Canadian Engineers and he cast off his

major's uniform in 1945 after overseas service in the United Kingdom and Europe.

He has been married for 25 years and he and his wife Edith have two children. Barbara is a graduate nurse at the Toronto General Hospital and son William carries on the engineering tradition as a student on the mining side at McGill University.

Edward J. Durnin has been a member of the Engineering Institute of Canada since 1930 (served on Council 1949-1950) and a Registered Professional Engineer (Saskatchewan) since 1936. He is the current president of the Association of Professional Engineers of Saskatchewan and is active in the Canadian Electrical Association. Under clubs and societies Mr. Durnin lists the United Services Institute, Military Engineers Association, Canadian Legion, Emulation Lodge and A.F. and A.M.

Hobbies? Gardening, woodworking and an active interest in the welfare of diabetics through the Canadian Diabetic Association.

• • •

Word of three important appointments within their organization comes from General Motors Diesel at London, Ontario. Messrs. **A. G. Shugg, N.D. Love** and **G. M. Lynch** are those with new appointments.

Mr. Shugg has been appointed District Manager in Vancouver for Diesel Engineering Sales. He had been district Engineer in Calgary for Locomotives since early in 1954. Until that time, he had been Service Repair Engineer in London. Shugg was born in Kelowna, B.C. He attended school there and obtained his Mechanical Engineering degree at the University of British Columbia in 1950 after serving in the RCAF from 1941 to 1946.

District Manager Shugg's territory covers an area from Vancouver east to Winnipeg.

Mr. Love has been appointed Engine Distribution Manager at London for Engine Sales. He had been District Manager at Winnipeg since 1953. He joined General Motors of Canada, Oshawa, in July 1939 in the Electrical Maintenance Department. During the war, he worked in the Twin Gun Mount Division and Experimental Engineering Division at Oshawa. From 1945 to 1949 he attended General Motors Institute, Flint, Michi-

gan, receiving a Bachelor of Mechanical Engineering degree in 1950.

During 1950-51 Manager Love was in the Engineering Department at Oshawa. He joined Diesel Sales at Oshawa in 1951, moving to London with the Division in 1952. He is married and has two children.

Mr. Lynch has been appointed District Service Engineer for the vast territory from British Columbia to the Manitoba-Ontario border.

He has more than 25 years of service with his company, having started with General Motors of Canada in Oshawa in April, 1930. In 1939, he went to Regina, Sask. and served in several capacities there, becoming District Service Manager in 1941 and Parts and Accessories Representative in 1947. In 1951 he was appointed District Manager for Alberta territory in the Diesel Sales Division. In his new capacity he still calls Edmonton his home town.

District Engineer Lynch attended elementary school at Westbourne, Manitoba, and secondary school at Wesley College, Winnipeg. He is married and has one son.

• • •

Newly appointed to the vice-presidency of Bakelite Company, Division of Union Carbide Canada Ltd., Belleville, Ontario, is **Philip O. Jeffrey**.

A graduate in chemical engineering from the University of Toronto in 1936, Vice-President Jeffrey crossed to Europe for post-graduate studies which he carried out at the Technische Hochschule



**Jeffrey—Bakelite's new V-P**

in Berlin. From these studies he went to the Bakelite organization where he has served in several capacities—Assistant Factory Manager, Assistant Sales Manager and Assistant to the President among them.

Bakelite's new vice-president is active in the work of the Society of the Plastics Industry (Canada) of which he is currently councilor-at-large.


THE SURPRISINGLY VERSATILE

# Suspension Hangers

## HEIM Unibal


... right out of stock!

Because of the very name of the piece, we think of a "rod end" as a sort of universal joint at the end of a rod when used in a linkage mechanism for pull-push operation. And for transmitting motion at varying angles, the Heim Unibal Rod End is the most dependable and most efficient of all.



However...

the ability of the Heim Unibal to correct misalignment in any direction, the smoothness of its oscillation, and its low cost, are just the qualities looked for in some unusual shaft supports.



HEIM MALE  
ROD END

Take this Kidde Knitter as an example of how Heim Unibal Rod Ends have been used as suspension hangers for the guide bars. It is essential that these bars move laterally, both smoothly and freely.

The hanger arm is drilled and tapped, and the male Heim Rod End is screwed into place. Assembly is simple, yet alignment of the bars is positive, and vertical adjustments can be made quickly and easily.

*Perhaps you have a place where Heim Rod Ends can improve mechanical function and cut the cost of parts and assembly. Submit your problem to the HEIM engineering department for advice and assistance.*

## R&M BEARINGS CANADA LTD.

QUEBEC CITY 755 Blvd. des Capucins MONTREAL 1006 Mountain St. WINNIPEG 1302 Notre Dame Ave. THREE RIVERS 375 St. Georges St. TORONTO 50 Edward St. VANCOUVER 1066 Seymour St. LONDON, ONT. 1024 Oxford St. East HAMILTON 130 Ferguson Ave. N.  
FACTORY REPRESENTATIVES AND DISTRIBUTORS FOR CANADA

HAS MANY USES OTHER THAN STRICTLY ROD END APPLICATIONS

## Sampling switches now offer more

**The versatile sampling switch now offers a new high in speed with reliability. Less space and maintenance come as an extra dividend**

**By Rob Cushman** GENERAL DEVICES INC.

The basic sampling switch, in its most common form, consists of a stationary plate containing a circular row of contacts, a concentric collector ring and a rotor containing two brushes (or wipers). One brush sequentially touches each contact in turn as the rotor revolves. This brush is directly connected to the second brush, which continuously rides on the collector ring. Thus, the collector ring is connected in series through the two brushes to each of the contacts in turn. This is a single-pole sampling switch in its simplest form.

Before reviewing specific time-sharing applications, it is interesting to consider the controlling characteristics of high speed switches.

High speed switch designers are concerned with dynamic characteristics such as phasing, make-and-break characteristics, accuracy and the relative duration of ON and OFF times, brush wear, contact resistance and its variation, driving torque, sampling rate and so forth.

Close tolerances, precision ball bearings and generally precise techniques afford a reasonable likeness to watch-making in complexity. These requirements are considerably different from those

required for conventional hand-operated switches.


The variation in design of the sampling switch is practically unlimited. Available designs afford switches with 8 or more poles with 200 or more contacts per pole, each with many different types of drive source and packaging.

With the advent of semi-molded contact plate construction and constant force Perma Brush Wipers, the period of service-free life has steadily advanced, so that 500 hours or more are often the specified minimum.

A total life (or life with service) of many thousands of hours is practical, thanks to simplified techniques. Current designs allow field replacement in a few minutes of all the brushes in multi-pole switches without requiring wiper force or phasing adjustments, as has been necessary in the past.

The latest semi-molded contact plate construction technique begins with a standard contact plate in which contact pins are pressed or screwed into precision jig located holes. After all the leads are attached, the plate is molded with specially selected high temperature molding materials. Finally, the contact pins are finished in order to provide a polished, truly flat surface. This molding process

*A typical two-pole thirty-channel dc switch of medium life particularly well suited to missile projects.*





## Sampling switches continued

locks each contact pin into permanent and precise alignment after all the soldering has been done. This is a distinct advantage over earlier construction techniques, where it was necessary to make connections by soldering to the back of the contact pins with considerable danger of expansion and contraction causing permanent distortion or loosening of a contact pin. This, of course, invariably upsets the flatness of the contact pin circle and hence affords markedly increased brush wear and shorter life.

The constant force wiper design ensures such slight wear of the contact pins that resurfacing of the contact plate is normally not required with brush replacement. Therefore, the life of the semi-molded contact plates frequently exceeds the life of the associated equipment itself.

Perhaps the most significant advance in technology has come from the perfection of these constant force wipers. Previous wiper designs utilized a form of cantilever spring arm with hand filled brushes producing a rapid, continuous decrease in brush force and unpredictable brush wear.

The new wipers are precision machined to shape, and use close tolerances to hold the change in brush force within 5% or 10% from start to finish. Such close tolerances provide improved duty cycle and phasing accuracies and greater reliability.

The diagram illustrates the more common wiring methods used and the resulting types of operation provided. The wiring method chosen determines whether a make-before-break (Shorting) or a break-before-make (Non-Shorting) operation will be provided.

As can be seen, the shorting operation is to be preferred whenever the circuit allows, as it provides twice as many channels for a given switch design as the non-shorting operation. Note that in the non-shorting operation it is necessary to provide one unused contact between each active channel to prevent the wiper brush from touching two adjacent channels simultaneously. Occasionally contacts are tied together in groups to provide longer or shorter ON times for special requirements. Duty cycle accuracies of  $\pm 3\%$  or better are now available for critical applications. The gating operation shown is a popular variation of interest, frequently used to provide a short duration pulse for timing synchronization. Note that no collector ring and only one brush is required.


### Optimum values by test

The shorting and non-shorting cycles are the preferred, optimum values determined by extensive testing for maximum reliability, accuracy and low level performance. When necessary, however, these values can be modified by varying the brush lengths, the contact diameter or the air gap.

In multiple pole designs, the phase (or timing) relationship between corresponding channels of each pole becomes very important.

Advanced design multiple units now provide fixed phasing where up to 8 or more poles are permanently locked within close phasing tolerances by means of precision jigs. This alleviates an expensive and time-consuming customer phase adjustment. This is made possible by the new, precision machined constant force wipers which offer the distinct advantage of maintaining their duty cycle and phase tolerances throughout the complete working life of the switch.


**The improvements are many but space, weight and cost are the greatest**



*Design target of this three-pole stacked type switch is a long service-free life with ease of adjustment.*




## Some of the more common wiring methods used




### The break-before-make operation.

*In the non-shorting operation it is necessary to provide one unused contact between each active channel to prevent the wiper brush from touching the two adjacent channels simultaneously.*



### The make-before-break operation.

*The shorting operation is preferable whenever the circuit allows as it provides twice as many channels per given switch design as the non-shorting operation shown in the first illustration.*



### A popular variation of interest.

*This layout is frequently used to provide a short duration pulse for timing synchronization or gating purposes. Note that no collector ring and only one brush is required in this circuit.*

## Sampling switches continued

Results of many tests indicate that the major factors of concern for successful sampling are:

(1) **Dynamic Contact Resistance Variation.** The variation of the dynamic contact resistance of the switch during the centre portion of each channel ON time is normally of little concern unless the load impedance is quite low (1,000 ohms or less). The tolerable resistance variation can be conveniently expressed by the simple formula: Maximum allowable contact resistance variation equals (Sum of source and load impedance) times (target system component accuracy desired) times (0.01).

(2) **Pick Up Potential:** Pick up can produce signals in the low millivolt region when relatively high impedances are required along with strong field intensities. However, the judicious choice of location of parts and proper shielding, filtering and placement of connections can usually reduce pickup to allowable values.

(3) **Edge Noise:** This refers to the trailing and leading edges of each ON time or pulse where any inconsistency in making or breaking can result in considerable contact resistance variation. This is usually more difficult to measure accurately than Item 1 above, but the same general formula holds true. Certain applications utilize gating circuits which select the centre portion of each channel ON time to assure freedom from edge noise. Careful investigation and experience in the choice of brush and wiper design, their physical sizes and materials and so on has been


successful in limiting edge variations to normally inconsequential values.

(4) **Generated Noise:** Tests to date indicate that generated noise is normally in the sufficiently low microvolt region as to be of little relative concern. This is of course dependent on the frequency response and impedances involved. Thermo-electric, electrostatic and thermal noise sources fall into this category.


(5) **Bounce or Breaks:** This can be a severe cause of error and is due to the wiper temporarily lifting from the contact surface due to vibration and/or mechanical resonances. Careful mechanical design has effectively eliminated this problem, even under relatively severe environmental conditions.

When high system accuracies and high impedances are specified (100K to 1 megohm), the maintenance of a high insulation resistance between adjacent channels can be of interest. In practice, the initial insulation resistance between adjacent channels is many thousands of megohms. This condition normally remains until the wiper wear material collects sufficiently between contact pins so as slowly to reduce this value. Since this brush wear material can be designed to be non-adherent, the switch insulation resistance can therefore be returned to its initial high value by means of a simple cleaning at the end of each period of service free life. In critical applications of this type, a value of 100 megohms is frequently used as a criterion for the end of useful service-free life. Hence, this figure is used in all life figures mentioned in this article. For maximum service-free life, it is usually wise to limit the load impedance to about 1 megohm or less, so as to minimize possible insulation resistance problems.

## Continued technical advances in high-speed rotary switch design provide



*Used in the early stages of system development this six-pole switch allows rewiring without disassembly.*



*A five-pole hermetically sealed switch doing a job in airborne installations. It has a 400-cycle ac motor.*

## high performance components to tax the ingenuity of the design engineer

High speed switches are provided with integral or attached, 400 cycle ac, 60 cycle ac, 6 to 115 volt dc motors, dynamotors or suitable drive shaft extensions for external drive. The proper choice of drive source for each application is very important. Care is required to ensure sufficient starting and running torque at the temperature extremes, proper shielding and/or filtering for low level applications, and last but not least, sufficient life for the intended application. (Miniaturized motors can often have a shorter life expectancy than the switch itself). Accuracy of the sampling rate is of constant interest, usually requiring the use of synchronous ac motors or governed dc motors.

In several cases, it has been necessary to design and manufacture special motors as an integral part of the switch, where readily available types would not satisfy all conditions.

Current sampling rates range from below 1 rpm to 100 rps. However, the majority of requirements are below 30 rps, as brush wear is proportional to the switch shaft speed. The sampling rate is determined by the needs of the system. For example, in sampling potentials whose amplitudes vary, sampling principles state that in order to reproduce the original information accurately and completely from amplitude samples, the rate of sampling must be greater than twice the highest frequency component of the signal to be sampled.

This principle applies to systems in which the samples are eventually integrated to produce the original signal. Because practical components must be used in this process, the actual rate of sampling must be two

or three times that mentioned above. This is usually due to the limitations in cut off and phase characteristics of practical filter networks.

For display or recording of unintegrated samples, the rate of sampling to achieve reproductions of reasonable accuracy is higher. For example, if there is a recording of the instantaneous samples representing a sampled signal whose amplitude is varying, a technique is applied known as optical integration, which involves drawing the best curve of reproduction.

The following portion of this article will describe high speed applications. These time-sharing applications fall into the following natural categories:

### Telemetry

As might be expected, telemetry remains the leading source of time-sharing applications.

The term telemetry covers applications in almost every field imaginable. The largest percentage of switch applications, however, occur in airborne, plane and missile evaluation.

In frequency division systems, a typical application would be for the switch to subdivide one or more of the available FM-FM subcarrier telemetry channels into 30 to 90 (or more) low frequency subchannels. The sampling switch is used as the primary time sharing or multiplexing device in time division systems such as Pulse Duration Modulation (PDM-FM), Pulse Amplitude Modulation (PAM-FM), Pulse Position Modulation (PPM-AM) and Pulse Code Modulation (PCM-AM). In some cases, an additional switch is used in the same system for subcommutation. The

*(Continued on page 76)*




Figure 1. One of the biggest users of the optical method of tooling is the aircraft industry. This completely square set-up can also physically check the completed objects for accurate measurement.

### Workshop practice

## Take the headaches out of measuring

**The errors inherent in conventional methods of measurement often make them unsatisfactory. Optical tooling can solve most of these problems**

By W. L. Egy

BRUNSON INSTRUMENT CO.

The principle used for general co-ordinate measurement is to set up a grid (or box) system of lines through space, from which measurements can be made. These lines are established and maintained by telescopes sighting into each other, into mirrors and upon fixed targets (Fig. 1). Planes at right angles to one of the established lines passing through given points furnish the means of measurement between those points.

Inasmuch as the lines of sight furnish the control, the means of support for the instruments is not critical.

The basic instrument in optical tooling is the optical transit square. This instrument will perform all the functions of optical tooling except linear measurement. It resembles the surveyor's transit, but is much more precise in every way. The line of sight is straight at all distances from 18 in. to infinity and passes exactly through the centre of the instrument. A large hole through the horizontal axis carries a semi-transparent mirror which can be observed from either end of the axis. This feature makes the optical transit square

self-checking, right on the job. The plane of the mirror is at exactly 90 deg to the axis, and parallel therefore to the line of sight. Sights by other scopes can also be made through the axis.

To establish a plane at right angles to a reference line, the optical square is placed so that the axis mirror intercepts the reference line. The square is then leveled and rotated until the axis mirror is at exactly 90 deg to the reference line, as for auto-reflection or auto-collimation.

For auto-reflection, a target is centred in the front end of the line telescope and illuminated from the inside of the telescope. When a mirror in front of this telescope is exactly square with the line of sight, the target image (reflected from the mirror) will be superimposed upon the reticle of the Line Scope.

Auto-collimation is similar to auto-reflection except that the reticle of the Line Scope is illuminated and the image of this reticle reflected back onto itself. Auto-collimation can be used at very short distances and with accuracy. Auto-reflection can be used farther and also offers a pattern that always permits accurate register.



### What is optical tooling?

Optical tooling has been a "must" in the aircraft industry for many years. Today many other industries find that the convenience, speed and accuracy of optical instruments will pay dividends in many cases.

Conventional methods of measurement, using a surface plate, angle blocks, micrometers, height gauges and so forth, require time and patience, even on simple work. Where structures are complicated, extreme accuracy is impossible. These limitations are due to errors in squares, the sag of long scales or bars, distortion due to unequal temperature, as well as the inaccessibility of points to be located. Optical tools, on the other hand, furnish right angles accurate to 0.003 in. in 100 ft lines of any length which do not sag; readings on any visible point; and scales always at the most convenient location. Installations need not be complicated and are quite easily operated by shop men.


When properly located by either of these methods the telescope of the optical transit square will sweep through a plane at exactly 90 deg to the reference line. Two planes, so located, will be parallel and therefore the same distance apart at any point. If two such planes pass through two selected points, the distance between the planes (measured at any convenient location) will be the distance between the two selected points, in a direction parallel to the reference line.

The same method is used to locate a second reference line at 90 deg to the first one. The telescope of the square is used to sight-in the second line which, in turn, is permanently established by means of another line scope, optical square, or a target (Fig. 2).

### Second direction measurements

An optical transit square moved from point to point along this 90 deg reference line is used to set up planes at right angles to those planes mentioned above, and is thus used for measurements in this second direction. In this way, measurements (Fig. 2) can be made between any two points that can be seen through the telescopes, even though objects may lie between these points.

The most convenient way to make linear measurements is to mount the optical transit square on tooling bars, as shown in Figs. 1 and 2. The position of the



Establishing the second line with another line scope

Figure 2. With the instruments rigged as shown here, measurements can be made between any two points visible through the telescopes even though objects may lie between these points.





Figure 3. The instrument resembles the familiar surveyor's transit, but is much more precise. The line of sight cuts the instrument's exact centre and is straight from 18 in. to infinity.

## Optical tooling

continued



Four of the targets

Figure 4. White space between the lines varies according to sight length. Centre is 1 in. from V edge.

square on the tooling bar is measured by a vernier and scale, plugged into a jig bored master index bar (Fig 3). The tooling bars need not be exactly straight, since the reference line of sight, together with the axis mirrors of the squares, furnishes the control for the system. The line scopes that hold the reference lines are mounted on independent stands beyond the ends of the tooling bars.

### Target type is important

The type of target used for sighting is a very important factor when precision measurements are being made. A single line on the telescope reticle cannot be accurately pointed at a single line on the target. Precise pointings will be made consistently if the target carries a double line, with enough space between the lines to show white on both sides of the cross hair (Fig. 4). These targets are commonly 2 in. square, with the width of white space between lines 0.005 in. for short shots of 5 to 10 ft and wider for longer sights. The space is not critical, since the centre will be accurately located. The centre of the white space is exactly 1 in. from the edge marked with the V. For regular sights, repeated often, the white space selected should include the **tolerance** allowed—then any sight between the lines will be within tolerance, even though not in the centre.

So far, a few general principles used in optical tooling have been explained and illustrated. The manufacturer should be consulted when selecting equipment

for any specific problem and instruments purchased to give results needed. More instruments and attachments can be added as needed.

The optical transit square can be obtained with a plain telescope and an ordinary level dial. The following attachments can be added in the field as needed:

- (1) Co-incidence level, either plain or reversible. This level is read from the eye-end of the telescope. The prisms show both ends of the bubble brought together, but moving in opposite directions. It is several times more accurate than the older type of open bubble.
- (2) Optical micrometer for objective end of telescope. This will shift the line of sight 0.100 in. each way (shift measured to 0.1001 in.).
- (3) Elbow eyepiece, swivel, for taking high angle shots.
- (4) Auto-reflection target, for use with external lighting.
- (5) Auto-reflection target, with internal lighting.
- (6) Auto-collimation lighting attachment to illuminate reticle.
- (7) Projection of reticle image onto the object or target. This requires a special reticle that should be factory installed (Fig. 5).
- (8) Combinations of the above items.

The principles described above will be illustrated by an imaginary problem of the simplest type—that of aligning several rollers (or other members) parallel to one another. Imagine a lengthy machine with cross rollers which must be accurately parallel, though the distance apart is not critical. A reference line can be

established along one side, parallel to the centre line of the structure, as described above. A line scope on an adjustable stand will serve to maintain the reference line.

An optical square, mounted on a second stand, can be set on the reference line, opposite one of the rollers. It is then squared by auto-reflection, using the line scope for control. The telescope of the square provides accurate alignment of the roller. The square can be moved to each of the rollers in turn and the operation repeated.

If it is necessary to level the rollers, a prismatic reading level can be attached to the optical square telescope. By using a double line target (Fig. 4) attached to the slider of the height gauge, readings can be taken to 0.001 in.


### Spacing the rollers

Should it be necessary to space the rollers accurately, a tooling bar beneath the reference line can be used to support the optical square. The location of the rollers can then be easily measured by the master index bar, scale and vernier on the tooling bar.

From this simple problem let the imagination travel to some large complicated structure, surrounded by a double-deck system of tooling bars, one set above, the other below, carrying a dozen or more instruments that are being operated simultaneously.

Wherever measurement becomes a problem, whether simple or complicated, it is likely that optical tooling, carefully selected and conscientiously used, will save money, time and some unnecessary headaches. ★

## Optical tooling gives high returns in convenience, speed and accuracy



**The projection attachment**

*Figure 5. It is sometimes easier to project an image of the cross-wires instead of looking through the telescope. A turn of a knob disconnects the projection feature for normal use.*

## Auto design sheds its strait-jacket

**A common sight in Germany, the DKW car is new in Canada. Two-stroke engine and front-wheel drive are two of its original design features**

Have you sometimes wondered if Detroit has not got itself into a sort of strait-jacket in car design? Of course, the American car buyer seems to prefer evolution by easy stages, as witness his cool reception to the Stout "Scarab" and the Chrysler "Airflow," while the high cost of tooling a new model (about \$200 million) puts a severe penalty on mistakes. But surely there must be other ways of putting two seats on a wheeled platform and propelling them over the countryside.

So the innovations presented by a newcomer from Germany, the DKW car, are welcome. It has two special features, each of which makes it unique over here. Though it has been manufactured in Germany for the past 28 years, it is the only car, on the Canadian market, with a two-stroke engine and the only one with a front-wheel drive.

Originally, DKW stood for "Dampf-Kraft-Wagen,"

a steam-powered car built in Germany 40 years ago. Later on, the factory turned to the manufacture of a two-stroke motorcycle, Das Kleine Wunder (The Little Marvel) and later still, to the manufacture of a car fitted with this same type of engine. The DKW company then became part of the Auto Union, a group famous for its successful racing cars. After the second war, the factory was completely rebuilt at Dusseldorf.

The advantages of the two-stroke gasoline engine, as every outboard marine engine user knows, are its light weight and compactness for a given power output. In the DKW, this compactness is a great advantage, since, in a front-wheel-drive car, the engine must be placed ahead of the front axle. The engine is water-cooled and again for compactness and weight distribution, the radiator is placed behind the engine. Thus the whole installation is most accessible and any part of the engine may be reached from the front of the car.

The engine has 3 cylinders and thus has a smoothness of torque equal to that of a conventional 6-cylinder, 4-stroke engine. The mixture is drawn from a Solex downdraft carburetor and is pumped into the cylinders by the changing displacement in each of three separated crankcases, just as in a marine outboard engine. In fact, the DKW engine can best be considered as a large outboard engine (in the 25 to 30 hp class) to which one more cylinder has been added. Its bore and stroke, 2.8 x 3 in., and its maximum power output of 14 hp per cylinder (42 hp in all) at 4,200 rpm happen to be almost exactly equal to the average figures for the six largest American outboard engines.

### Gasoline-oil mixture

Since it is not practicable to have oil flying about in the crankcase of a crankcase-pumping two-stroke engine, lubrication is not under pressure and the oil is mixed with gasoline in the fuel tank. Without pressure lubrication, plain bearings are not too reliable under heavy loading, so the main bearings are three roller and one ball bearing and the connecting-rod big-ends are fitted with needle bearings. This means that the crankshaft must be built up by pressing the crankpins and main journals into the crank throws. Accordingly it can only be serviced as an assembly, complete with bearings and connecting-rods.

The engine has no camshaft and, in fact, no auxiliary shafts of any sort. There is no oil pump and the gasoline pump is driven by the changing pressure in No. 1 crankcase. The distributor, which runs at engine speed, is driven from an extension of the crankshaft; it distributes low-tension current to three separate ignition coils. There is no water pump and the two outside




**The two-stroke powerplant**

*Doubly strange appearance of the three-cylinder unit results from mounting the radiator behind the engine.*





*The DKW has a large rear window. It is now easier for the back seat driver to say who the driver just missed.*




*A flattening of the steering wheel's lower arc gives the driver's legs clearance between seat and wheel.*

accessories, the generator and the fan, are belt-driven.

A three-cylinder, in-line engine has an unbalanced primary couple and secondary couple. The engine is mounted on large rubber pads, but is rather rough when idling, possibly because the mounting pads are too low down. It is remarkably smooth when pulling, however, and the acceleration is very good. The top speed is said to be 78 mph and the fuel consumption 32 mpg.

The layout of the front-wheel drive is conventional, with a single transverse semi-elliptic spring above and wishbone links below. The engine is in front of the axle and the transmission behind. The passenger cars have a single transverse spring at the rear, while the light trucks have torsion-bar springing at the rear, so as to leave an ideal loading platform, without any encroachment other than the small wheel boxes. ★

### **Only seven moving parts and roller bearings spell long engine life**



*Unit dispenses with camshaft, valves and tappets and has unconventional fuel pump, distributor.*

*Right diagram shows loop scavenged two-stroke principle. Intake port is at the gap below "D".*

# Canadian Institute of Radio Engineers Convention

Interest in the Canadian IRE Convention and Exposition at Exhibition Park, Toronto, on October 1, 2 and 3 runs high. Here are the exhibitors at time of going to press.

## List of Exhibitors

### A

ADAMS ENGINEERING LTD. 534.  
AEROVOX CANADA LTD. 544.  
AIRCRAFT-MARINE PRODUCTS OF CANADA LTD. 342.  
ALFORD MANUFACTURING CO. INC. 461.  
ALPHA WIRE CORP. 362.  
AMPEX AMERICAN CORP. 545.  
AMPHENOL CANADA LTD. 146, 245.  
ANDREW ANTENNA CORP. LTD. 159.  
ATLAS RADIO CORP. LTD. 240, 242, 343.  
ATOMIC ENERGY OF CANADA LTD. E-18.  
AUTOMATIC RADIO OF CANADA, LTD. 263.  
AVIATION ELECTRIC LTD. 452.

### B

BACH-SIMPSON LTD. 130, 231.  
BAYLY ENGINEERING LTD. 249.  
BEACONING OPTICAL AND PRECISION MATERIALS LTD. 441.  
BEAMA ENGINEERING LTD. 235.  
BOMAC LABORATORIES INC. 556.  
BUDD-STANLEY CO. INC. 239.

### C

CANADA WIRE AND CABLE CO. LTD. 529.  
CANADIAN AVIATION ELECTRONICS LTD. 349.  
CANADIAN BROADCASTING CORP. E-10.  
CANADIAN ELECTRIC RESISTORS LTD. 155.  
CANADIAN GENERAL ELECTRIC CO. LTD. 352, 354.  
CANADIAN MARCONI LTD. 135, 137, 139, 141, 143, 145.  
CANADIAN WESTINGHOUSE CO. LTD. 252, 254, 355.  
CANADIAN WILBUR B. DRIVER CO. LTD. 464.  
CANNON ELECTRIC (CANADA) LTD. 158.  
CAPITOL RADIO ENGINEERING INSTITUTE. W-18.  
CAPRIN LTD. 570.  
CENTRALAB CANADA, LTD. 253.  
COLLINS RADIO CO. OF CANADA LTD. 434, 436.  
COMPUTING DEVICES OF CANADA LTD. W-2.  
CONRAD, INC. 566.  
COPPER WIRE PRODUCTS LTD. 146, 245.  
COSSOR (CANADA) LTD. 565.

### D

DAWE INSTRUMENTS LTD. 138.  
DECCA RADAR (CANADA) LTD. 536.  
DEFENCE RESEARCH BOARD. 361, 363.  
DEPARTMENT OF NATIONAL DEFENCE. W-6.  
DESSER E-E LTD. 558.  
DIAMOND STATE FIBRE CO. OF CANADA LTD. 255.  
DOMINION ELECTROHOME INDUSTRIES LTD. 256.

### E

EDWARDS HIGH VACUUM (CANADA) LTD. 568.  
EITEL-McCULLOUGH INC. 153.  
ELECTRODESIGN. 447.  
ELECTRO IMPULSE LABORATORY, INC. 243.  
ELECTROMECHANICAL PRODUCTS. 560.  
ELECTRO SONIC SUPPLY CO., LTD. 538.

ELECTRONICS & COMMUNICATIONS MAGAZINE. 336.  
ERIE RESISTOR OF CANADA LTD. 358.  
ESSEX ELECTRONICS OF CANADA LTD. 463.

### F

T. S. FARLEY LTD. 259.  
FERRANTI ELECTRIC LTD. 165.  
FILTRON CO. INC. 466.  
FLEET MANUFACTURING LTD. 260.

### G

GENERAL COMMUNICATIONS LTD. W-12.  
THE GLENDON COMPANY, LTD. 360.

### H

HACKBUSCH ELECTRONICS LTD. 234.  
HAMMOND MANUFACTURING CO. LTD. 564.  
HELLERMANN OF CANADA LTD. 540-A.  
JOHN HERRING & CO. LTD. 443.  
THE HOLDEN CO. LTD. 160.

### I

THE INDIANA STEEL PRODUCTS CO. OF CANADA LTD. 446.  
INDUSTRIAL ELECTRONICS OF CANADA LTD. 551.  
INSTRONICS LTD. 353.  
THE INSTITUTE OF RADIO ENGINEERS. 454.  
INTERNATIONAL RESISTANCE CO. LTD. 146, 245.

### K

G. F. KELK AND CO. 344.  
KESTER SOLDER CO. OF CANADA LTD. 537.

### L

LEONARD ELECTRIC LTD. 563.  
E. G. LOMAS CO. 162.  
J. R. LONGSTAFFE CO. LTD. 146, 245.

### M

MARSLAND ENGINEERING LTD. 338.  
McCURDY RADIO INDUSTRIES LTD. 247.  
MEASUREMENT ENGINEERING LTD. 440, 444.  
MEASUREMENTS CORP. 540-B.  
MICROWAVE SYSTEMS. W-8.  
MINNEAPOLIS-HONEYWELL REGULATOR CO. LTD. 452, 453.  
M. J. S. ELECTRONIC SALES LTD. 333, 335.  
MOFFATS LTD. 456.  
MYCALEX CORP. OF AMERICA. 132.

### N

NATIONAL CARBON CO. 448, 450.  
NATIONAL FIBRE CO. OF CANADA LTD. 251.  
NATIONAL RESEARCH COUNCIL. 351.  
R. H. NICHOLS LTD. 246.  
NORDEN-KETAY CORP. 346.  
NORTHERN ELECTRIC CO. LTD. E-4, E-6, E-8.  
NORTHERN INDUSTRIAL PRODUCTS LTD. 562.

### O

OKI & WILLADSEN LTD. 531.

### P

PHILCO CORP. OF CANADA LTD. 539.  
THE PLESSEY CO. OF CANADA LTD. 161.  
CHARLES W. POINTON LTD. 465, 467.  
POTTER & BRUMFIELD INC. 163.  
POWERLITE DEVICES LTD. 238.  
PRECISION ELECTRONIC COMPONENTS (1956) LTD. 236.  
PSC APPLIED RESEARCH LTD. 348, 350.  
PYE CANADA LTD. 356.

### Q

QUALITY HERMETICS LTD. 233.

### R

RADELIN-KIRK LTD. 261.  
RADIO COLLEGE OF CANADA. W-4.  
RADIO CONDENSER CO. LTD. 136.  
RADIO ELECTRONIC TELEVISION SCHOOLS OF CANADA LTD. 437.  
RADIO ENGINEERING PRODUCTS LTD. 347.  
RADIONICS LTD. 445.  
RAYTHEON CANADA LTD. 258.  
ROGERS MAJESTIC ELECTRONICS LTD. 150, 152, 154.  
R-O-R ASSOCIATES LTD. 553, 555.  
ROTRON MANUFACTURING CO. 455.  
RUTHERFORD AGENCIES. 535.

### S

SIGMA INSTRUMENTS INC. 359.  
A. C. SIMMONDS & SONS, LTD. 250.  
SINCLAIR RADIO LABORATORIES LTD. 262.  
SPARTON OF CANADA, LTD. W-10.  
SPERRY GYROSCOPE CO. OF CANADA LTD. 345.  
THE SPHERE CO. INC. 140.  
SPRAGUE ELECTRIC INTERNATIONAL LTD. 532.  
ST. REGIS PAPER CO. (CANADA) LTD. 339.  
STANDARD TELEPHONES & CABLES MFG. CO. (CANADA) LTD. 449.  
THE SUPERIOR ELECTRIC CO. 131.

### T

TEKTRONIX INC. 241.  
TENATRONICS LTD. 257.  
TENSOLITE INSULATED WIRE CO. INC. 340.  
TMC (CANADA) LTD. 341.  
TROP-ARCTIC INC. 439.

### U

UNITED-CARR FASTENER CO. OF CANADA LTD. 542.

### V

VARIAN ASSOCIATES OF CANADA LTD. 364.

### W

WHITE RADIO LTD. 533.  
WIND TURBINE CO. OF CANADA LTD. W-14.

## Technical Programme

The wide range of subjects covered by some 125 papers so far accepted promises a busy time for technically minded visitors determined to attend all those in their special fields. The papers are divided into groups under: semi-conductors, nucleonics, electronic tubes, etc. No attempt has been made to give a complete list—just a representative selection.

**The Control of Guided Missiles**, A. Ratz, Canadian Westinghouse Co. Ltd., Hamilton.

**Problems in Radiation Instruments for Defence**, A. Hendrikson, D.R.-T.E. Defence Research Board, Ottawa.

**Use of Transistors in Nucleonics**, F. S. Goulding, A.E.C.L., Chalk River.

**Testing Facilities for Colour Television Receivers**, R. Anthes, Canadian Westinghouse Co. Ltd., Brantford, Ontario.

**Design Considerations for Colour Television I.F. Amplifiers**, K. R. Van der Keyl, Canadian Radio Mfg. Corp. Ltd., Toronto.

**Wide Band Power Amplifiers**, P. Gomar, T. S. Farley Limited, Hamilton.

**A New Approach to Variable Frequency Oscillator Design**, F. A. Bailey, Canadian Marconi Co., Montreal.

**Electronic Instrumentation for the Location and Assaying of Radio Active Ores**, G. G. Eicholz, Dept. of Mines & Technical Surveys, Ottawa.

**Magnetic Amplifier Servo Control for NRU**, N. F. Wood, Ferranti Electric Ltd., Toronto.

**A Tuning Indicator for Television Receivers**, W. E. Liddell, Canadian Radio Mfg. Corp., Toronto.

**Closed Circuit Television**, W. M. Booth, Rogers Majestic Electronics Ltd., Leaside.

**Microphonic Testing of Tubes**, S. Love, Radio Valve Co. of Canada Ltd., Toronto.

**Cold Cathode Tubes**, A. K. Knowles, Rogers Majestic Electronics Ltd., Leaside.

**Some Applications of Electronic Data Processing Systems in the Air Transport Industry**, L. E. Richardson, Trans-Canada Air Lines, Montreal.

**Applications of Symbolic Logic to Electronic Engineering**, G. B. Thompson, Northern Electric Co. Ltd., Belleville.

**The Canadian Post Office Electronic Mail Sorter**, Mr. W. J. Turnbull, Deputy Postmaster General.

**Fundamental Principles of the Canadian System**, Dr. M. Levy, Post Office Dept., Ottawa.

**A Reflection Theory for Beyond the Horizon Propagation**, H. T. Friis, A. B. Crawford and D. C. Hogg, Bell Telephone Laboratories, Holmdel, N.J.

**Scatter Propagation**, P. L. Rice, C.R.P.L. Bureau of Standards, Boulder, Colo.

**High Frequency Transistor Amplifier Design**, G. T. Lake, D.R.T.E. Defence Research Board, Ottawa.

**Logical Use of Transistors in Communications Applications**, S. Kagan, Crosley Defence and Electronics Div., Moffats Ltd.

**Analysis of Heart Murmurs by Electronics**, R. S. Richards, National Research Council, Ottawa.

**Electronics in Medicine**, W. E. Hodges, Consultant, Toronto.

**Mechanized Processes for Design and Manufacture of Printed Wiring Units for Data Processing Systems**, D. E. Nuttall, Ferranti Electric Ltd., Toronto.

**Discussion of Methods of Producing Prototype Printed Circuit Boards**, I. Meitlis, Canadian General Electric Co. Ltd., Toronto.

**Magnetic Recording Tape**, L. F. Bennett, CAMSA, Ottawa.

**Ferrites in Microwave Work**, D. J. Whale, Canadian Westinghouse Co. Ltd., Hamilton.

**The Cost of Decibels**, Frederick Gall, Canadian Marconi Co., Montreal.

**Electronics in Meteorology**, W. R. Smith, Department of Transport, Ottawa.

**Computer Circuits Using the P-N-P-N Transistor Element**, C. D. Florida, DRTE, Defense Research Board, Ottawa.

**Transistorized Logical Building Blocks**, D. C. Redpath, Crosley.

**A Canadian Designed 150 mc Vehicular Communication Equipment**, G. M. Koch and W. Ornstein, Canadian Marconi Company, Montreal.

**An Experimental Radio Teleprinter Broadcast Service for North-Atlantic Air Routes**, B. G. Dautre, Trans-Canada Air Lines, Montreal.

**Magnetoresistive Amplifiers**, A. Aharoni and E. H. Frei, Weizmann Institute of Science, Rehovoth, Israel.

**Electronic Power Supplies**, T. C. Gams, NJE Corp., Kenilworth, N.J.

**Common Errors in Measurement and Design**, W. C. Bengner, Northern Electric Co. Ltd., Belleville.

**Cascade Co-operative Education**, Richard Scott, Canadian Aviation Electronics Ltd., Montreal.

**A Graphic Volume Unit Recorder**, D. H. McRae, Canadian Broadcasting Corp., Montreal.

**The London-Windsor Microwave System**, R. D. Pynn, Canadian General Electric Co. Ltd., Toronto.

**Thermal and Field Effects in Point Contact Diodes**, R. E. Burgess, University of British Columbia, Vancouver.

**Recent Developments in the Diffusion Technique Used to Produce Semi-Conductor Devices**, J. Y. Perron, Northern Electric Co. Ltd., Montreal.

**Automation in the Laboratory — Description of a Strain Recording and Plotting System**, G. F. Kelk, G. F. Kelk and Co., Toronto.

**Video Transmission Requirements and Testing Techniques**, A. Ste. Marie, Canadian Broadcasting Corp., Montreal.

**Electronics for Defence**, M. L. Card, Dept. of National Defence, Ottawa.

**Packaging Guided Missile Electronics**, J. W. Keenan, Canadian Westinghouse Co. Ltd., Hamilton.

**Automatic Range Radar for the F-86 Aircraft**, E. Herbert, Canadian General Electric Co. Ltd.

**Pattern Range for HF Shipborne Antennas**, J. Y. Wong and J. C. Barnes, National Research Council, Ottawa.

**Some Conductivity Characteristics of Canadian Terrain at Medium Radio Frequencies**, P. A. Field, DRTE, Defence Research Board, Ottawa.

**New Scaling Techniques**, W. D. Howell, AECL, Chalk River.

**Sub-carrier Matrixing in Color Television**, A. E. Kimmel, Canadian Radio Mfg. Corp. Ltd., Toronto.

**The Application of Phase Locked Frequency Control Systems**, E. H. Hugenholtz, Rogers Majestic Electronics Ltd., Leaside.

**Design Considerations for Reliability**, A. S. Best, Canadian General Electric Co. Ltd., Toronto.

**Applications of Statistical Quality Control**, J. J. Fitzsimmons, Canadian Marconi Co., Montreal.

**Two-Dimensional Slotted Arrays**, G. C. McCormick, National Research Council, Ottawa.

**System Reliability in Reactor Control**, E. E. Siddal, AECL, Chalk River.

**Development of Cross-Polarized Antennas**, R. Meier, RCA Victor Co. Ltd., Montreal.

**Interference Immunity of TV Receivers**, E. Luedicke, RCA Victor Co. Ltd., Renfrew.

**Design and Performance of a 2KW CW Klystron Amplifier for C-Band**, E. A. Conquest, Varian Associates of Canada Ltd., Georgetown.

**An Investigation Into Simple Methods of Forecasting the Life of Electron Tubes with Indirectly Heated Cathodes**, R. H. Taplin, Canadian Marconi Co., Montreal.

**Automatic Recording and Processing of Operating Data at Hydro's Niagara River Plants**, J. R. Leslie, HEPC, Toronto.


**Magnetostriction Delay Lines**, J. V. Scott, Ferranti Electric Ltd., Mount Dennis, Toronto.

**The "Scad"—A Servo Calibrating Auto Densitometer**, P. D. P. Smith, Electrodesign, Montreal.

## Speaking voice of a movie big noise

European ears first heard the Cinemascope  
soundtrack over this new design 'speaker

Side view of BTH loudspeaker at right shows twin flare HF horn.



When it had its first showing in Europe, the Cinemascope sound-track reached the audience over a loud-speaker of completely new design. This speaker is a product of the British Thomson-Houston Company and they supplied the entire projection and sound equipment.

The unit, type K10A, is a co-axial dual-channel speaker with an 18 in. diameter LF cone assembly having a twin-mouthed HF horn mounted in the centre pole. This is coupled by a special form of phase-equalizer to an anodized aluminum alloy diaphragm. To divide the high and low audio-frequency energy from the amplifier, an external filter unit with a cross-over frequency of approximately 1700 cycles per second is used.

The speaker was originally designed, and has been used with considerable success, for the auditorium sound channel of large Cinemascope installations throughout Great Britain, where the wide frequency range and low level of distortion, coupled with the high power handling capacity of approximately 20 watts audio, have proved extremely effective. The speaker is now being offered to the general public and should prove of special interest to the enthusiast.

The HF metal-diaphragm electro-dynamic unit has high stability, good power-handling capacity and low-

level distortion. During development, various alternatives, such as electro-static, ionic and ribbon reproducers, were tried for the HF duty, but none of these was found as satisfactory as the final design.

By extending the HF horn in front of the centre LF diaphragm, distortion due to intermodulation has been kept to a relatively low level, while still maintaining the good "presence" for which coaxial sound sources are noted, even close to.

The twin flare of the HF horn has a wider polar characteristic in the plane through the line joining the mouth centres than in the plane at right angles to this and so uses the high-frequency sound energy to the best advantage.

The "pepper pot" construction at the end of the centre pole provides a mechanically stable and acoustically effective phase equalizer. This minimizes turbulence and interference of the phase of the sound pressure at the higher audio frequencies, which frequently occur due to variation of path lengths from parts of the diaphragm to the throat of the horn. The horn flaring nearly conforms to the standard expression:

$$A = A_0 e^{mx}$$


Here,  $A$ =area at mouth,  $A_0$ =area at throat,  $e=2.7183$ ,  $m$ =flaring constant and  $x$ =distance from throat to mouth.

This gives a flaring constant which allows for effective coupling of the diaphragm to the air down to a frequency of approximately 1200 cycles per second. With a 3x3 in. dimension for each mouth of the twin horn, the low frequency cut-off due to the mouth dimensions is also in the same region.

The above factors determine the cross-over frequency of approximately 1700 cycles per second, together with the narrowing polar diagram for an 18 in. cone assembly above this frequency. The frequency chosen allows relatively small components, particularly the air-cored chokes, to be used in the filter circuit.


The company's filter unit, type G2A, is a two-section inductive/capacity type with an attenuation of 12 db per octave at cross-over.

(Continued on page 79)




A method of delayed resonance response measurement determined the frequency characteristic of speaker.






*A sectional view of the BTH loudspeaker showing the arrangement of the HF horn and diaphragm.*

**Wide frequency range is coupled with a very low level of distortion**



*The BTH loudspeaker's excellent characteristics can be quickly seen from this polar diagram.*



*The box is entering the first of five spray phosphating stages. Pipes at left are emerging from the drying oven.*

## Phosphating can make a finish stick

**Treatment improves paint-holding and gives resistance to salt spray**


**By Jack H. Goodyear** J. W. REX CO.

Design engineers should always remember that phosphate coatings, by themselves, do not drastically increase the corrosion-resistance of steel, but act as an intermediate agent to hold supplementary coatings. The illustration shows how effective is treatment with phosphate solution in holding paint and giving superior resistance to salt spray.

Basically, four types of phosphate coating are used

on steel. Each has certain physical characteristics and applications which must be weighed against cost to assure selection of the proper coating.

The first is the so-called **amorphous type of iron phosphate**. Chief advantages of this type of coating are its paint-holding characteristics and low cost. In general, it is the cheapest type of phosphate coating to apply. Weight of the coating is usually around 20 to 60 milligrams (mg) per sq ft. While the corrosion resistance of this coating is not comparable to the other types of phosphate coating, it is superior to that of



Same five stages by the dip coating process. The drawing of wire is made easier by zinc-iron phosphating first.

steel which has received no surface treatment at all.

Amorphous iron phosphate coatings are usually applied to certain types of consumer goods where the paint system has to be as cheap as possible and where the painted product will not be exposed to the elements.

The second type to be considered is the **zinc phosphate** coating, crystalline in nature, with a coating weight of 100 to 600 mg per sq ft. This coating is used more extensively than any other type. It has excellent paint-retention properties and prevents blistering and undercutting of the paint by corrosion, should the paint coating become scratched or damaged in some manner.

Zinc phosphate coatings are used for both commercial and government work. Consumer products, such as automobiles, refrigerators, cooking ranges and the like, generally use a zinc phosphate coating as a pre-treatment to paint.

The third type of coating is also a **crystalline zinc phosphate**, differing from the above type in the thick-

ness of coating applied to the metal surface. This coating generally weighs 1,000 to 4,000 mg per sq ft and possesses a larger crystal structure than the previous type.

Basically, this larger crystal, zinc phosphate coating is used as a corrosion-resistant base, usually being supplemented by the addition of oils, waxes and similar additives. Occasionally, however, this type of coating is used without the addition of these supplementary treatments. This, the writer feels, is a mistake, because the addition to it of even very small amounts of oil will keep the manufacturer out of trouble under normal atmospheric conditions.

The large crystal zinc phosphate coating is not recommended as a paint base. In order to obtain the required thickness of phosphate coating, the crystalline structure becomes too large and too absorptive for paint. Paint applied on top of this coating will not give the expected "mileage." In addition, the paint will lose

its lustre due to the surface condition.

The chief use of this particular phosphate coating is for hardware, nuts and bolts, ordnance parts and items in which appearance is not too important but corrosion resistance is.

The fourth type of coating is also a thick (1,000 to 4,000 mg per sq ft) crystal-type coating, consisting basically of a **manganese phosphate structure**. This type of phosphate coating has not the same uses as those previously described.

The main advantage of a manganese phosphate coating is its anti-friction qualities. This imparts good wear-resistance to bearing surfaces.

### Similarity to ice on water

In using this coating, however, always bear in mind that it is similar to ice on water: any gouging or digging will break through the coating. Yet for sliding wear it has excellent characteristics, especially when some type of oil or wax lubricant is used as a supplementary treatment.

This supplementary treatment is often used on cylinder walls, piston rings, gears, cams and other sliding surfaces. Another interesting use for this material is on steel which is to be pressed, drawn or reshaped in some way. By using a manganese phosphate coating, the metal can be made more workable and tool life prolonged.

For a better understanding of phosphate coatings and their properties, it is necessary to know the basic steps necessary in applying them. These are:

(a) **Cleaning.** Basically, the procedure begins with a cleaning operation. As with any chemical process—whether it be a conversion coating, electrochemical coat-

ing or plating—proper cleaning is a “must,” in order to obtain satisfactory coatings. Not only must the surface be free from oil, grease and other physical dirt; it must be chemically clean as well—free from oxides and other products of corrosion.

This operation may call for several stages in the phosphate treatment. The initial step is to remove the physical dirt by alkaline cleaners, emulsion cleaners, solvents or vapors. Next comes chemical cleaning by means of a pickling operation. In many instances, this step can be eliminated, provided the surface is free from rust and other corrosion products. In some instances it may be more economical to remove heavy rust and scale (due to forging, heat-treating or welding) by mechanical means such as wire brush, sand-blasting, grinding and so on.

(b) **Phosphating.** After proper cleaning, the material is subjected to the phosphate bath, where the reaction between the chemicals and the metal surface takes place.

(c) **Rinsing.** After initial rinsing, the coating which has formed is rinsed a second time with an acidulated rinse. Generally, these steps are performed in one of two ways: dipping or spraying, the method finally chosen usually being determined by production requirements and the size or shape of the articles.

In dipping, the parts are handled in baskets, barrels or on racks, a method which does not, however, lend itself to high production.

In the spraying operation, the parts are generally hung from an overhead conveyor or laid on a moving belt. The speed of the operation is determined by the speed of the belt and the size of the spraying chambers. There is a more rapid formation of the coating in the spraying operation, due to the impingement of the solution on the surface.

The cost of spraying can be reduced to three stages. This is accomplished by cleaning and phosphating (amorphous iron-phosphate) in the same bath, and then following with the rinse and acidulated rinse. As mentioned previously, however, this is a coating primarily designed for a paint base.

### Defects of the process

There are certain difficulties and defects to watch out for:

A powdery and nonadherent coating can cause considerable grief when followed by paint. The result is usually poor paint-adhesion and a rough finish.

A nonuniform coating is usually caused by improper cleaning or by poor chemical balance in the phosphate bath. Again, poor paint adhesion results.

The size of the crystalline phosphate is very important. On those surfaces which are prepared as a paint base, a coarse crystalline structure will cause roughening of the painted surface. The result is poor paint “mileage” due to high paint absorption.

On surfaces which are being prepared for anti-friction service, and so receive supplementary treatment with oils, waxes and similar lubricants, the coarse crystalline structure is, of course, quite helpful.

The formation of a rust flush during the processing operation is one of the most prevalent difficulties encountered. There are several reasons why this rust flush forms: Improper chemical balance of the phosphate solution, improper cleaning, improper rinsing—any of these will cause difficulties. Even though it is light, rust can cause trouble when it comes to paint adhesion. ★


### Points you must consider

Phosphate coatings have a variety of uses. They offer a flexible, versatile tool for use by the design engineer. They represent a good, economical, easy-to-apply coating—if the phosphate is chosen correctly.

Next time, before you are tempted to dismiss the job summarily with “phosphating,” think of the:-

- ◆ Requirements of the job
- ◆ Cost
- ◆ Thickness required
- ◆ Type of protection needed
- ◆ Types of coating available for use
- ◆ Methods of application
- ◆ Possible difficulties that might be encountered should processing methods prove faulty. Then you will be ready to specify phosphate coating to fit your job.







*Die cast zinc parts for a new television set, just phosphated, move from the drying oven to priming stage.*



*Improved paint adhesion after phosphating is clearly shown here. This steel panel received only chemical*



*cleaning whereas this one was cleaned and then phosphate coated before the painted finish was applied.*



Abstract pattern of parts made from polyester resin.

## These glass laminates are new

Resistance to most acids is good

A line of polyester resin glass mat laminates, having properties similar to the reinforced plastics used in sport car bodies, is available from National Vulcanized Fibre Co. The advantages of the sheet laminates are: dimensional stability and exceptionally high impact strength with more than average arc resistance.

The properties of dimensional stability and impact strength suggest important mechanical applications, such as fabricated containers, cams and so on. The new materials can also be used for armature slot wedges, spacers, switchboard panels, arc chutes and the like. Their chemical resistance makes them useful materials in areas of high humidity or acid fumes.

There are three standard grades of these laminates, obtained by impregnating glass fibre mats with a liquid polyester resin containing inorganic fillers and a catalyst. The treated mats are heat cured under low pressure to produce a hard laminate. General properties of the three grades and their identity are (see Table) as follows:—

GP-9100 A general-purpose, medium-cost sheet with good electrical and mechanical properties.

GP-9104 Low-cost grade with lower mechanical properties than GP-9100 and fair electrical properties.


GP-9202 Flame resistant grade. Also the best electrical grade, except for arc resistance.

The Table summarizes the physical and electrical properties of the three grades. Standard sheet sizes are: 32 x 36 in., 32 x 48 in. and 32 x 74 in.

The polyester resins generally have good chemical resistance to most acids and most solvents, such as carbon tetrachloride, toluene, gasoline and ethyl alcohol.★

Typical properties of glass mat laminate 1/8 in. thick.

Grade	GP-9100	GP-9104	GP-9202
Color (natural) .....	Tan	Light Cream	Dark Cream
Flexural Strength (psi)			
Lengthwise .....	26,000	20,800	29,800
Crosswise .....	22,800	20,200	22,000
Impact Strength (ft lb/in)			
Lengthwise .....	11.0	9.0	10.0
Crosswise .....	10.0	8.0	9.0
Bond Strength (lb) .....	1000	1200	1200
Rockwell "m," 23C .....	98	98	108
Dissipation Factor, 1 megacycle, Condition A .....	0.0130	0.012	0.011
Dielectric Constant, 1 megacycle, Condition A .....	4.40	4.78	3.97
Dielectric Strength			
Parallel to laminations (kv) Cond. A .....	52.0	57.5	51.0
Perpendicular to lam. (volts, mil) Cond. A .....	400	475	500
Insulation Resistance (megohms) Condition A .....	1 x 10 <sup>6</sup>	1 x 10 <sup>6</sup>	1 x 10 <sup>6</sup>
Arc Resistance .....	88	96	3
Water Absorption (% gain) Cond. D-24/23 .....	0.21	0.31	0.14
Density .....	1.75	1.82	1.79



Three thin-walled lightweight zinc die castings form the frame, base and dial for a new portable radio.

## Die casting has most of the answers

**What are the advantages of the die casting method? Speed and economy often happily married to little necessity for machining top the list**

### Die casting is like this.

Die casting has been aptly termed the shortest distance between raw material and finished part. Into one end of a die casting machine goes molten alloy—out of the other comes a stream of identical metal parts. Many such die castings are ready for use “as is.” When machining and finishing are required, these operations can be performed efficiently and economically.

As in most other fields of endeavor, however, die casting is not as easy as it appears. A great deal of “know-how” must be applied before die castings can spew from a machine at maximum speed and with the utmost in physical and mechanical properties. Prospective users of die castings should take their problems to the job shop die caster at an early stage in the design.

One of the greatest advantages of die casting is that most dimensions can be held within limits so close that little or no machining is required. Most holes can be cored, sometimes as small as 3/32 in. diameter. Coring is usually done to tap drill size. A die can produce many thousands of castings without removal and usually without significant change in the dimensions of the die casting. The minimum size produced is smaller than for other methods of casting.

Properties of die cast parts are superior to those of corresponding parts cast by other processes. Surfaces, as die cast, are smoother than for any other form of die casting. Alloys of four different base metals afford a fairly wide choice. In general, corrosion resistance rates are good. Most alloys are readily plated and all can be otherwise finished with a minimum of surface preparation.

Flexibility of design means that die castings have more complex shapes than other types of casting. They can have thinner walls and integral fastening elements can be die cast in place and result in economies in assembly. External threads are readily cast whilst internal threads can be cast economically in some instances.


## Die casting continued

The economies of the die casting process can be fully realized only when the part is designed specifically for this method of manufacture. Basically it should be remembered that the ease with which a die cavity can be filled—and the die casting ejected—dictates the speed of production. It is therefore an important factor in the ultimate cost. The ideal design for a particular die casting is best determined by consultation with the job shop die caster.

The table gives data on maximum weight, minimum wall thickness and dimensional tolerances. This information if for average conditions and the approximate limits set may be varied under special conditions. When there is doubt about producing a part that does not come within the limits indicated, the advice of an experienced die caster should be sought. In fact, any new die casting design should be presented to the die caster for criticism before it is too late to make changes. His experience will often point to possible economies or an alternative construction that may decrease both die costs and die casting costs, without having any bad effect on the function or appearance of the die casting.

The dimensions and limits in the table apply to the die casting as it comes from the die and without machining, other than flash removal.

Since the castings are made in steel dies, the design must provide a definite parting line to ensure removal of the casting from the die. General data on drafts required



Die cast aluminum components for the camera at right. Shown here are two sides of the case and lens mount.

## Flexibility of design means that die

is given. Cores must be capable of ready withdrawal from the die casting and must not involve undercuts, unless "loose pieces" are used.

Simple forms that are easily cut into the die blocks help to reduce costs but it is quite possible to make

### Approximate Dimensional and Weight Limits for Die Casting in Different Alloys


Data apply to average conditions. For exceptional conditions, larger castings, closer dimensional limits and thinner sections may be feasible.

Type of Alloy (base metal)	Zinc	Aluminum	Magnesium	Copper
Maximum weight of casting (lb.)	35	20	10	5
Minimum wall thickness, large castings (in.)	0.050	0.080	0.080	0.090
Minimum wall thickness, small castings (in.)	0.025	0.050	0.050	0.050
Minimum variation per inch of diameter or length from drawing dimensions over one inch†	0.0015	0.0015	0.0015	0.002
External cast threads (max. no. per in.)	24	24	16	10
Min. diameter of cored holes (in.)††	0.094	0.125	0.125	0.250
Minimum draft on cores (in. per in. of length or diameter)	0.005	0.010	0.010	0.020
Minimum draft on side walls (in. per in. of depth)	0.007	0.015	0.010	0.020

†Larger variations may be anticipated across die partings or where fits of slides or cores are involved.

††Depends to a considerable degree on length of core, although smaller cores than here indicated are seldom employed.





*An exposed side view of the turret-type movie camera. The "works" fasten mechanically to the housing parts.*




*The lens mounting plate can be clearly seen here. The die cast surface proved ideal for a "wrinkle" finish.*

## **castings can have more complex shapes than any other type of casting**


complex forms when necessary. Parts having external undercuts, or projections on side walls, often require slides that materially increase die costs. In many cases, however, there are resultant savings of metal in the die casting or other advantages, such as more nearly uniform

wall sections, that offset the extra cost or effect a net economy in over-all cost of the part. This is especially true when large quantities are involved, as a small saving per casting may fully justify a much more expensive die.

Rules for the design of any die casting must be



*The parts laid out for this picture make up a window awning assembly. They were all die cast from zinc.*




The framework of this typewriter was formerly comprised of six iron sand castings which required extensive machining, finishing and assembling. Here's a better result achieved from a one-piece aluminum die casting.

## Die casting continued

somewhat general in character and subject to many exceptions. It is possible, however, under certain conditions, to frame rules that indicate what is desirable or otherwise, especially when it is desired to produce at the minimum cost likely to yield a satisfactory product. Rules here given are intended merely as a guide to good design. Most of them have exceptions and there are numerous cases in which other considerations outweigh the advantage that may be attained by following a particular rule. Where the rules can be followed, however, costs are likely to be lower or better die castings will result, or both.

- Keep wall sections of uniform thickness for low production costs. Where variations in thickness are necessary, the transition from thin to heavy sections should be as gradual as possible, to avoid stress concentration.
- Keep over-all dimension as small and weight as low as other requirements permit.
- Specify sections as thin as can be die cast readily, if they still give adequate strength and stiffness. Ribs frequently help in giving maximum strength with minimum weight.
- Remember that plain flat areas are the most difficult to die cast. If slightly curved surfaces or decorative effects can be employed, minor surface imperfections can be avoided.
- Coarse external threads are easily die cast, particularly if located at the die parting, but internal threads are frequently obtained more economically by machining.
- Avoid nonessential projections and keep shapes as simple as other requirements permit. Any obstruction to removal of die casting from the die naturally retards the casting cycle and adds to cost. Every possibility of avoiding undercuts by slight changes in design should be fully explored.
- Coring should be specified where holes or recesses can be cored without undue die cost, and where savings in metal and over-all cost will result. Design cores so that withdrawal is facilitated to avoid complicated die construction and operation. Make cored holes and recess of such shape that core will be minimized and still satisfy




Points marked "X" eliminate machining and assembly. "Y" is the casting's gate discarded after machining.

other requirements. Where cores are specified, see that they are not so slender as to be easily bent or broken. Frequent replacement of cores can increase costs substantially.

- Do not specify the coring of holes in walls less than 3/16 in. thick, or of very small holes, unless assured of a net saving in cost over subsequent drilling or piercing.
- Never ask for tolerances closer than are actually needed. Unusually close cast dimensions can be achieved, when necessary, but such tolerances add considerably to casting costs and in some instances can be obtained more economically by subsequent machining.
- Provide for sufficient draft on sidewalls and cores to ensure removal of the die casting from the die without distortion.
- Provide for fillets at all inside corners and avoid sharp outside corners unless deviation from this practice is warranted by some special consideration.

As the metal cools, it tends to shrink with considerable force against parts of the die. The location and magnitude of this shrinkage stress in the die casting determines the location and size of the necessary ejector pins. The die casting design must provide for the location of



*Eight hydraulically pulled side cores were part of this intricate die for casting a new type of gas meter. Aluminum, zinc and bronze parts make the meter an outstanding example of creative design in die casting.*

these pins, and the effect of the resulting ejector marks on the appearance and functioning of the die casting must be considered.

Specify integrally die cast fastening elements if they result in lower assembly and over-all costs, and specify die cast threads when a net saving over cut threads will result.

Die castings which have a significant effect upon the appearance of the finished product should be designed to have adequate eye appeal and to harmonize with mating parts. Where inserts to be die cast in place are essential, they should be so designed as to be readily inserted and firmly held in the die and proper anchorage provided to retain them in the die casting.

Design the die casting so that a minimum of machine work is required and flash removal costs minimized. Also allow sufficient metal to clean up properly where machining is specified but not so much as to require cuts of unnecessary depth. In die castings to be polished or buffed, all areas to be finished thus must be so disposed as to be brought easily into contact with the wheels or belts to be used for the purpose, avoiding sharp edges.

The following is a comparison with other methods:

**Stamping:** An assembly made up of die castings may result in lower die and tool costs. It frequently requires fewer parts and few assembly operations; can be held, in general, within closer dimensional limits; can have almost any desired variation in section thickness; involves less waste in scrap; and can be produced in more complex shapes than can be obtained in stamped form.

**Screw Machine Products:** Die castings are often produced more rapidly, involve much less waste in scrap; can be made in shapes difficult or impossible of production from bar or tubular stock, and may require fewer operations.

**Sand Casting:** Die casting requires much less machining; can be made with thinner walls, can have all (or nearly all) holes cored close to size; can be held within much closer dimensional limits; can be produced more rapidly in dies that make many thousands of castings without renewal; do not require new cores for each die casting; are easily provided with inserts cast in place; have smoother surfaces and involve much less labor cost.

**Permanent Mold Casting:** The die casting can be made to closer dimensional limits and with thinner sections;

*(Continued on page 66)*




# These instruments will save your time

Design engineers need mathematical instruments to do their tedious work

## DERIVIMETER


The derivimeter, made by Ott of Germany, is used for determining the direction and numerical value of the tangent at a point on a given curve. No. 332 GOJAG is for use on a tee-square only whilst No. 334 GOJOK can be used both on a tee-square and a drafting machine. The instrument is most useful, for example, in evaluating dilatometer curves from material tests. Its net weight is 2 lb, including case.

For Type 334, it is necessary to know exactly on which drafting machines the derivimeter will be used, so that the required joint parts can be supplied.



## INTEGRIMETER


An instrument which permits the direct reading, from point to point, of the integral value of a curve while tracing it, is the integrimeter. On taking readings of the measuring roller at definite intervals, the operator is thus able subsequently to plot the integral curve at the finish of the tracing. Owing to this property, the integrimeter is a substitute for far more expensive integrators, in the solution of problems in the domain of mechanics, (static moment, centre of gravity, moment of inertia) ship-building and ballistics. One important application is the formation of mean values from extended curves, such as the daily means from the weekly diagrams of water level recorders.



## AREA-MOMENTS EVALUATOR


This new area-moments evaluator is claimed to surpass (for powers higher than 2) all existing multiple-integrators, because it works with a more convenient mathematical rule and gives each result directly and independently.

The instrument shows (with three rollers) the area  $\int y dx$  and its moments  $\frac{1}{2} \int y^2 dx$ ,  $\frac{1}{3} \int y^3 dx$  and  $\frac{1}{2} \int xy^2 dx$  and, with a fourth roller, the moments  $\frac{1}{4} \int y^4 dx$  and  $\frac{1}{2} \int x^2 y^2 dx$ . The tracer arm is throughout divided and the tracing pin adjustable by micrometer screw and vernier. Length of tracer arm is 20 in. maximum deflection  $\pm 16$  in. Ruler 90 in. for a range of 67 in. No. 192 with three measuring rollers, code word PAWAT; No. 193 with four measuring rollers, code word PAWIK. ★





Here, we convert **IDEAS**  
to products and profits




for all Canadian industry

**Improved fastening methods created and developed  
by completely integrated Canadian company**


"Imagination is given the reins" at the Hamilton plant of Dominion Fasteners Limited. Here, through a combination of up-to-date facilities and creative personnel, this Canadian company is constantly inventing, developing and producing better fastening methods for industry.

Manufacturers of the famous line of SPEED NUT brand spring tension fasteners, Dominion Fasteners Limited are always ready and able to provide any industry with an efficient and economical solution to any attachment problem.

**here's an example of how  
the construction industry profits...**



Working with ROBERTSON-IRWIN LIMITED, a major supplier of steel roof deck to the Canadian construction industry, Dominion Fasteners Limited created and developed a new type SPEED CLIP for the attachment of insulation to roof deck. The precarious fire hazard associated with former methods was completely eliminated... as well as many other installation problems. Designed and developed entirely in Canada by Canadians, this new addition to the SPEED NUT family of over 6000 types and sizes of fasteners is now being adopted in the U.S.A.




Robertson-Irwin Q-Deck mechanical insulation fastening method

**TINNERMAN**

*Speed Nuts®*

FASTEST THING IN FASTENINGS®

over 6000 types and sizes



DEPT. C

Exclusive Canadian Licensee

**DOMINION FASTENERS LIMITED - Hamilton, Ontario**  
*a Geo. A. Tinnerman corporation*

*Serving people  
every day...  
Stan Steel Tubing*



At a three alarm fire...or in the comfort of your own home. In hundreds of places...and hundreds of ways. Wherever the emphasis is on modern living...that's where people are served by products made from Stan Steel tubing.

**STANDARD TUBE AND T.I. LIMITED**  
WOODSTOCK • TORONTO • OTTAWA • MONTREAL



**STAN STEEL**  
WELDED TUBING

Seamless Tubing • Fabrications •  
Aluminum

## Testing

# Measurement of friction makes basis for research


The basic laws of friction were first enunciated by Coulomb in 1785 and are still regarded as being more or less valid. These laws state that when one body rests on another the static friction, that is, the tangential force to start sliding, is (1) proportional to the normal load and (2) independent of the geometric area of contact. The tangential force to maintain sliding (kinetic friction) is generally less than the static friction. However, it is generally found that over an appreciable speed range the kinetic friction is constant.

Two main types of theories have been advanced to explain the frictional behavior of sliding solids. Coulomb attributed it primarily to the surface irregularities. In this view one surface has to be lifted over the asperities on the other and in the course energy is expended. If, as Coulomb suggested, there is no surface interaction one would expect all the energy lost in going up the asperities to be regained on coming down. This is like a frictionless car on a roller coaster: it can travel any horizontal distance without loss of energy if the final and initial levels are the same.

Energy can be dissipated only if the roller coaster has saw teeth so that after traveling up the slope the car falls catastrophically over the edge and destroys all its energy in impact. This aspect of the nondissipative nature of the Coulomb theory is rarely discussed in engineering texts.

In addition, it is generally found that over a very wide range of surface roughnesses the surface finish has very little effect on the friction between clean metals. If, however, the surfaces are very rough (e.g. if a file is pulled over another file) there is a very marked effect due to an inter-locking of the asperities. For sliding to occur the asperities must be sheared or filed away.

The phenomena that occur when solid surfaces make contact have long fascinated scientists and this interest has motivated the Stanford Research Institute to correlate and interpret an abundance of information gathered by many scientists, and to sponsor further basic research in the field. Studies are in progress in the Control Systems Laboratory relating to the following problems in surface physics: electrical contact phenomena and related catalytic effects, friction and wear, lubrication under high pressure and at high temperature, static electrification and adhesion. With the advent of transistors and other low level electronic devices,



*Dr. K. R. Eldredge of the Stanford Research Laboratory has developed this new friction measurement apparatus.*

the group's investigation of the cause of failure in electrical switches and relays is highly significant.

Dr. K. R. Eldredge, manager of the Laboratory, has developed a friction measurement apparatus for measuring the friction, or tangential force, which resists sliding between surfaces. Dr. David Tabor (from whose paper much of this material was taken), international fellow from the University of Cambridge, England, and Dr. Wilbur W. Hansen, senior research engineer, are utilizing this and other apparatus to measure friction of clean surfaces or those covered with suitable lubricants. A study is also being made of the effect of high temperature and of electrical current on surface damage.

With the friction measurement apparatus and other associated equipment, the following types of problem will be approached:


Reduction of friction and wear between heavily loaded sliding mechanisms.

Investigation of wear and conduction phenomena in commutators.

Development of techniques for increasing relay reliability, particularly under low-level switching conditions.

Evaluation of techniques for the determination of the adhesion between plastic laminates and metals. ★

*When it's  
aluminum...  
Stan Steel is ready  
to serve you*



More and more Canadian companies are relying on Stan Steel for all their aluminum requirements. Sheet, bar, extrusions, tube and wire . . . small lots for special jobs . . . large quantities for continuous production runs. If it's to do with aluminum, Stan Steel is ready to serve you.

**STANDARD TUBE AND T.I. LIMITED**  
WOODSTOCK • TORONTO • OTTAWA • MONTREAL



*Welded and Seamless Steel Tubing -  
Fabrications*



## Quotes

### Points from current papers and speeches

In the study of high temperature phenomena, the arc image furnace provides many advantages, such as ease of control, stability, reproducibility and moderate size and cost. While a certain amount of the discussion given in this lecture by **T. P. Davis** at the high temperature symposium sponsored by Stamford Research Institute is applicable to high intensity arc discharges in general, only the high current carbon arc was treated specifically. Hence, it will be of some interest to discuss this source, particularly those features which have direct bearing on the problems of arc image furnaces.

The earliest form of high current carbon arc was developed by Beck about 1914, and employed a positive carbon, cored with cerium fluoride and oxide, operated at current densities of 100 to 400 amps per sq cm. Finkelnburg determined that the cerium compound core was not a necessary condition, and that many kinds of positive carbon could be employed, provided the anodic current density was sufficiently high. This led to the characterization of a general high current arc, with certain properties among which are: (a) anodic current densities from 100 to 400 amps per sq cm, and (b) a rather deep positive carbon crater filled with brilliant, high temperature vapor, ejected from the base of the crater. While other properties are of considerably more importance with respect to the fundamental mechanism of this discharge, these two are of most direct concern in an imaging-type furnace. First, because of the high current densities required, the majority of high current arcs in practical application employ positive carbons of 16 mm diameter or less in order to limit the power requirements to a reasonable value. Secondly, while the positive carbon crater is thus somewhat limited in area, it presents a source of extraordinary brilliance. The principal source of irradiance is not an incandescent carbon tip, as in the low current arc, but rather the high temperature vapors within the positive crater. A total radiation of over 6 kw per sq cm of crater cross-section can be attained, corresponding to that from a black body at 5,800 deg K.

#### Car of the Future

In a recent banquet address at the semi-annual meeting of the ASME, **Arch T. Colwell** expressed the opinion that gas turbine-powered automobiles will be coming off the production lines as present

production equipment requires replacement. They will probably appear one model at a time, since the job of re-tooling will cost millions of dollars. Gas turbines will appear on automobiles before they appear on trucks and other commercial vehicles because they offer the industry a new selling point.

Fuel-injection systems for piston engines will come even before the gas turbine. These, too, will create a selling point, since they will eliminate the carburetor and the air filter, making it possible to lower the hood and restyle the front end.

Changes in suspension systems are "right around the corner." Springs and shock absorbers will give way to hydraulic and pneumatic cushions.

#### Nuclear Heat Engines

Five to ten years ago, few people would have predicted that in 1956 engineers would be building nuclear power plants of 100,000 to 200,000 kw, or that by 1970, 25% of all new public utility power plants will be nuclear power plants. In England, where the cost of fuel is high and the shortage of both domestic petroleum and coal is acute, the rate of growth of nuclear power plants may exceed that of the United States. Therefore, it may not be out of place to look at the question of nuclear powered vehicles at this time, stated **F. L. Schwartz** and **H. A. Ohlgren** of the University of Michigan, in a recent SAE paper.

Nuclear heat engines can be considered as power plants for vehicles, locomotives, aircraft and ships. Currently, about 25% of the total energy consumed in the United States is for the operation of automotive power plants.

Some interesting questions come to mind. How small would a nuclear power source be? How much shielding is necessary? Could one buy an automobile, with its supply of fuel adequate for the life of the car included in the purchase price of the car? How much will nuclear fuel cost? Will enough of it be available? How will it be produced? What is to be gained, in the way of car performance, by having a nuclear power plant?

It is conceivable that a nuclear power source could be very small if only the fissionable material needed to be considered. If the average life of a vehicle is 160,000 miles, the average speed 40 mph, the average horsepower 25, and the average hydrocarbon fuel cost 2.5 cents per mile, then the total cost of fuel

for the life of the vehicle is \$4,000, and the energy used is 100,000 hp-hrs. One gram of U-235 is capable of producing 1,000 kw hrs. In addition to requirements for critical mass for a given geometry and fissionable atoms necessary to overcome neutron losses to absorbing materials, about 300 gm (2/3 lb) of nuclear fuel is required if used in an engine of 25% efficiency for the life of the vehicle. To compete with the cost of hydrocarbon fuel at 2.5 cents a mile for the conditions mentioned, the nuclear fuel's cost must approximate \$13 per gm.

#### Product Design Costs

Speaking at the semiannual meeting of the ASME **Lad J. Bayer**, chief industrial engineer of the Warner & Swasey Company, Cleveland, presented a set of charts tabulating the cost differentials for different standards of dimensional tolerance and surface roughness.

He limited himself to data readily available in his own company, but stated that the technique of plotting design features against their respective costs can be expanded into other manufacturing fields. The design engineer's main task is to attain as nearly as possible a balance between the function, durability, appearance and cost of a product.

#### Selecting Machine Tools


An engineer has devised a means for taking 10 variables, such as initial cost, space requirement, depreciation, hourly wages and power consumption, and feeding them into a single formula that will tell management whether and how it ought to select new machine tools.

The formula, expressed as a nomogram, uses such different dimensions as dollars, square feet, percentage and kilowatt hours. It was presented at the semi-annual meeting of the ASME by **Realf Ottesen**, senior designer of McCulloch Motors Corporation, Los Angeles.

The system was originally put into practice when the speaker was research head of the Motor Engine Manufacturers Institute at Trondheim, Norway. It was used to set up general rules for the re-tooling program of Norwegian motor manufacturing plants.

The nomogram not only allows management to determine, from the swivel chair, which machines should be replaced and how much their replacements would cost, but can be used to indicate the company's status in terms of expenses, price level, trend of wages and salaries and the cost of modernization. It can be further extended to take in groups of tools and to condense the cost of an entire factory into a single, although necessarily more detailed, nomogram. He said complete factory cost levels showing profits can be made at a moment's notice.





# DESIGNERS' DELIGHT

Almost every design problem is a problem of materials. Is the price right . . . is it strong enough . . . light enough . . . colourful and bright enough? Can it be cheaply formed and produced at speed . . . is it resistant to corrosion, rust, denting or scratching?

That's why so many design problems simply cease to exist when the designer begins his planning with a full appreciation of what can be done with Fibreglas Reinforced Plastics.

**F.R.P.**

could be the answer  
to your problem



**FIBERGLAS CANADA LIMITED**

GENERAL SALES OFFICES:


10 PRICE STREET, TORONTO, ONT.

BRANCH OFFICES:

MONTREAL • OTTAWA • TORONTO • WINNIPEG • VANCOUVER


**IT'S AMAZING THE DIFFERENCE FIBERGLAS MAKES!**

# MICRO SWITCH PRECISION SWITCHES FOR MULTIPLE CIRCUIT CONTROL



**SUBMINIATURE ROTARY SELECTOR SWITCH**

MICRO SWITCH rotary selector switches provide a means of switching two to eight different circuits with one small compact assembly. The switch consists of two to eight single-pole, double-throw subminiature basic switching units operated by cams on a common shaft. The cams are pre-set to operate the basic switches at 45° detents. Cams can be set to your specifications at the factory, permitting any combination of the switching units to be actuated in any position.




**MULTIPLE CIRCUIT PANEL MOUNTING  
PUSH BUTTON SWITCH**

Small, panel mounting manually operated push button switch containing two to fourteen basic switching units. Each unit may be wired either normally open or normally closed providing numerous combinations of "off" or "on" circuits in either depressed or released plunger positions.


**SUBMINIATURE TOGGLE ASSEMBLY**

An assembly of up to sixteen subminiature basic switches operated by a single bat handle. Eight switches can be operated with each direction of the toggle motion. This assembly makes an unusually efficient, compact, lightweight component . . . each of the subminiature switches are less than 3/4" long and weigh less than 1/15 ounce.



**2-POLE PANEL MOUNTING TOGGLE SWITCH**

Conforms to "AN" and "JAN" specifications and provides superior service and life characteristics through (1.) greater over surface creepage and clearance distances; (2.) sealed toggle lever; (3.) no return springs in momentary versions; (4.) solid silver contacts; and (5.) copper moving contact carrier to provide maximum conductivity.



**MICRO SWITCH  
A PRINCIPLE  
OF GOOD DESIGN**

MICRO SWITCH produces a complete line of extremely reliable snap-action precision switches for single and multiple circuit control. For complete information, write to Honeywell, Dept. DE-OEC-9.



## MICRO SWITCH

A DIVISION OF MINNEAPOLIS-HONEYWELL REGULATOR COMPANY, LTD.  
LEASIDE, TORONTO 17

## Die castings (Continued from page 59)

holes can be cored; it is produced at higher rates with less manual labor, has smoother surfaces and commonly costs less per die casting.

**Forgings:** Die castings can be more complex in shape; can have shapes not forgeable; can have thinner sections, can be held to closer dimensions and can have coring not possible with forgings.

**Plastic Moldings:** Die casting is much stronger; can be produced faster and in more complex shapes; usually involves lower tooling cost; is much more stable dimensionally; can be held within closer dimensional limits and can be finished, as by plating, in ways that are not feasible (or slower) with plastic moldings.

## Typical applications

The chassis of the new Westinghouse miniature portable, encased in polystyrene plastic, is supported by the frame which is shaped like a wide U. Attached to the frame (see illustration) is the die cast base sectioned off by thin internal walls, to house the batteries, and easily detached from the base for battery replacement. Depressed lettering cast into the base attractively spells out the name. The dial, with a serrated edge at its perimeter perpendicular to the dial plane, is also a zinc die casting. Calibrated numbers are cast-in as depressed lettering.


Die casting's ability to produce a smooth surface finish was a major consideration in specifying the process because these die castings had to take a "jewelry" finish. In fact, all the die cast parts receive a brass satin lacquer finish. The depressed lettering on the dial and base is blacked-in, resulting in a handsome black and gold combination that adds to the radio's appeal.

A combination three-cavity die is used to produce the three parts. Except for two 1/16 in. holes which are tapped, all dimensions are cast to size in these two die castings.

By working closely with their job shop die caster, Westinghouse engineers were able to get components meeting rigid specifications at the most economical cost.

Denison Corporation design engineers devised a window operating mechanism that motivates all windows in one case-moment simultaneously by the turning of a single handle. Certified zinc die castings were specified for the entire mechanism, including hand crank, drive gears and gear housing, window hinges and hinge brackets (see illustration). The high strength of die cast zinc and its equally important ability to hold close tolerances in bearing recesses despite the corrosive action of all types of weathering, was the basis for its selection in these components.

(Continued on page 72)



## Which is the **RIGHT** Fine Grain Brass for a Job?



Write for a free copy  
of this folder  
on Grain Size —  
"The Fourth Dimension."

High finish on decorative brass can be produced at much lower cost by using a fine grain metal. But severe cupping, drawing and forming operations require ductility which decreases, generally, as grain size gets finer.

The right metal for the job, then, is often a compromise between fineness of grain and ductility: *no one fine grain brass can do all jobs well.*

By offering a range of grain sizes, Noranda can supply you with the right fine grain brass for every application, assuring you optimum production at lowest costs.

Noranda Technical Service will be glad to work with you in finding the right brass for your product if you will contact them through your local Noranda Sales Office.



## Noranda Copper and Brass Limited

SALES OFFICES: MONTREAL • TORONTO • WINDSOR • EDMONTON • VANCOUVER

# HOW TO MAKE 1000 CALLS A WEEK



## ... IN CANADA

From St. John's, Newfoundland, to Victoria, B.C., is a distance of 3,980 miles. Scattered throughout this tremendous area are your customers and prospects. With even the largest sales force you must inevitably ignore some accounts at times . . . unless you also use selective business paper advertising to keep your customers informed.

No matter what your product or service, there are one or more Canadian business papers to carry your messages to exactly the field you want to reach. Supplement your personal calls by regular contacts through business papers, and keep *all* your customers informed, *all* the time.

This paper is a business paper—one of 100 trade . . . technical . . . service . . . and management publications covering every section of Canadian business and industry.



WHEN YOU WANT TO TALK BUSINESS  
USE A BUSINESS PAPER

### BUSINESS NEWSPAPERS ASSOCIATION

OF CANADA

137 WELLINGTON ST. W., TORONTO, CANADA

*New!*

FIRST TO STRESS  
DYNAMICS AND  
MACHINE DESIGN

## CAMS

Design, Dynamics,  
and Accuracy

By HAROLD A. ROTHBART,  
*College of the City of New York*


THIS is the first work on cams to go beyond simple drafting techniques. Exceptionally wide in scope, the book offers a thoroughly modern treatment of dynamics and machine design, using cams as a basis. Theoretical and practical aspects are thoroughly covered. On the practical side the author makes concrete recommendations concerning such topics as mass, acceleration, materials, and the type of cam and follower to be used. Profile accuracy and errors are discussed. Mathematics is kept at a minimum throughout the presentation.

This book fills a vital need in the light of today's trends toward high-speed machinery, automation, mechanical computers, and servo-mechanisms.

1956      350 pages      210 illus.      \$9.50

Send TODAY for Your ON-APPROVAL Copy!

JOHN WILEY & SONS, Inc., Dept. MD-66  
440 Fourth Ave., New York 16, N.Y.



## Send a Copy of Design Engineering To Your Business Associates ... FREE OF CHARGE.

DESIGN ENGINEERING,  
481 University Ave.,  
Toronto 2, Canada.

Please send a FREE copy of Design Engineering with my compliments to the persons listed below.

To .....

Address .....

City ..... Prov. ....

To ..... • • •

Address .....

City ..... Prov. ....

To ..... • • •

Address .....


City ..... Prov. ....

Sender .....

Address .....



# Morse Cam Clutches make slicing machine infinitely more accurate




## Here's how they work:

The first Morse Series 200 Cam Clutch controls indexing (though not required on this job, it can handle up to 500 indexes per minute). When driven in one direction, inner and outer members rotate as one unit. When driven in the other direction, one member overruns freely, other member remains stationary. The second Cam Clutch is used to prevent backfeed between strokes.



Series 200 Cam Clutch with retaining end plate removed. This Cam Clutch Series fits standard Series 200 bearing housings.



## Versatile, compact clutches can help designers control indexing, free-wheeling, backstopping

This modern slicing machine is infinitely more accurate because a Morse Cam Clutch replaces the old ratchet and pawl mechanism controlling the feed.

When U.S. Slicing Machine, Inc., used the ratchet and pawl, feed variations (slice thickness) could only be made in 1/128-inch increments. Now, the Morse Cam Clutch provides, in effect, a self-contained ratchet with an infinite number of teeth . . . and literally makes it possible for the machine to slice accurately to any desired thickness.

In addition, another Morse Series 200 Cam Clutch is used as a backstop device to maintain one-directional

drive. It instantly engages to prevent backfeed between forward strokes.

Morse Cam Clutches are manufactured in capacities ranging from 4½ inch-lbs. to 20,000 ft.-lbs. Their low-cost accuracy and dependability make them ideal for a wide range of industrial indexing, overrunning, and backstopping applications.

Like other precision-built Morse power transmission equipment, they are quickly available from your local Morse Distributor. For more information, or free Catalog C 11-54A, call him, or write us today. MORSE CHAIN OF CANADA LTD., SIMCOE, ONTARIO

# MORSE



**CHAINS, CLUTCHES,  
AND COUPLINGS**

## New booklets and books written for you

A new, six-page, illustrated brochure on the leak detector is now available from **Beckman Instruments, Inc.**

Bulletin 483, contains the latest technical data of this versatile instrument, as well as information on many applications. It has been designed to locate minute leaks in pressure, vacuum and hermetically sealed systems and units.

Covered in the brochure are methods by which leaks may be detected, particular applications of interest and instrument specifications. Descriptions of accessories available for use with the leak detector are given also. (200)

### Constant delivery pumps

Twenty-one different sizes of Type C constant displacement, radial piston pumps built by **The Oilgear Company** are described in a new bulletin 46000. Construction, operation, speeds, capacity and pressure ratings are included.

These constant delivery pumps are used individually on small and medium presses, on calender hold-down systems and with variable displacement motors to provide variable speed, constant power drives. These pumps are also used in series with other constant displacement pumps, or in combination with variable displacement pumps. They are extensively used in the iron, steel, metalworking, plastic, automotive, rubber, printing, paper, lumber, food, chemical and textile industries. (201)

### Test equipment

In a catalogue just published by **The Narda Corporation**, a complete line of coaxial and UHF equipment, microwave test equipment, bolometers and thermistors is covered. Text, specification tables and photographs describe existing equipment and such recent additions as fixed and variable attenuators, high power impedance meters, tees, fixed and sliding terminations and UHF coaxial directional couplers. (202)

### Snap action thermostats

A condensed catalogue listing physical, electrical and performance specifications for many types of snap-action, locally adjustable thermostats is offered by **Fenwal Incorporated**, manufacturer of precision temperature controls.

The four-page, two-color catalogue de-

scribes in convenient pictorial and tabular form the assortment of head styles, snap switches, electrical ratings, temperature ranges and modifications for the Series 20000 Thermo-switch, by which the user can specify a thermostat exactly suited to his requirements.

The catalogue also presents general information about snap-action thermostats and discusses the various installation and service factors affecting temperature control, regardless of the type of controller used. (203)

### Corrosion resisting steel castings

A new designation chart (Bulletin 556-C) for corrosion resistant stainless steels has been issued by **Empire Steel Castings, Inc.** The chart identifies ACI and Empire designations with the corresponding AISI type number, the ASTM designation and with other designations and trade names. This correlates the various stainless types for easy selection and reference.

The new chart also gives the percentage of principal alloying elements and typical mechanical properties for the twenty-three steels listed. Helpful remarks indicate the application and performance of many of the steels in use.

As a further guide to alloy selection, the chart includes a graph showing the effect of individual elements on corrosion penetration rate and also a graph showing the resistance of cast alloy type CF-8 to various concentrations of nitric acid as a function of temperature. (204)

### Oil-Hydraulic systems

A new 20-page two-color illustrated catalogue (Bulletin M5101A) describing oil-hydraulic systems and components for all mobile equipment in the truck and bus, construction machinery, material handling, agricultural and allied industries is now available from **Vickers Incorporated**.

The new catalogue contains discussions of performance characteristics, design features, construction details and applications for their line of single and double vane pumps, power packs for mobile equipment, multiple unit valves, relief valves, reservoirs, fluid motors and power steering boosters. Each section includes photographs, cutaway views and all the relative performance curves. (205)



**Servospeed**  
HEART OF  
AUTOMATION


**MODERN  
ELECTRONIC  
ENGINEERING  
GIVES PRECISE  
MOTOR SPEED  
CONTROL**

Modern industrial electronic engineering has been coordinated with electric motor design to provide a versatile means for obtaining the full possible advantage of speed control in DC motors while operated from the regular alternating current power line. Grid controlled "Thyatron" tubes are utilized for power controlled stepless variation to supply motor armature power. Patented feedback, or "Servo" circuits provide constant torque capability over wide speed ranges of as high as 60 to 1 in some models and a minimum of 20 to 1 in others.


**Servospeed**  
DIV. OF ELECTRO DEVICES, Inc.  
4 Godwin Ave., Paterson, N. J.  
ARMory 4-8989



Entrance to the Fairbanks-Morse building in Winnipeg.



The rich, neutral luster of the metal contributes to handsome architectural effects as illustrated in the Albert G. Baker Limited building in Quebec City.



Wilkinson Company Limited chose stainless for the entrance to their building in Vancouver.




This modern stainless steel entrance to the Bank of Canada building in Winnipeg resists rust and corrosion.

From  
coast to coast...  
entrances to  
be proud of...

...with  
**nickel-  
containing  
stainless  
steel**

**THE RICH, NATURAL BEAUTY  
OF STAINLESS IS  
LONG LASTING—ECONOMICAL  
TO MAINTAIN**


Architects and designers have found that stainless steel is an enduring construction material that does not deteriorate with age and exposure. Stainless is easy to keep clean, cuts maintenance time and costs. But, above all, stainless steel is a decorative material that gives buildings grace and dignity... pleasing and unobtrusive beauty.



THE INTERNATIONAL NICKEL COMPANY OF CANADA, LIMITED

25 KING ST. W., TORONTO, ONT.

# DALIC in Industry



Copper plating bore of pinion prior to carburizing.

Reclaiming overmachined or damaged I. D.



## THE DALIC PROCESS!

### An Advanced Method of Electroplating

- New, non-toxic organic solutions.
- High current densities and fast deposition.
- Plates defined areas without masking.
- Easy plating on aluminum, stainless steel and other "problem" base metals.

A plating shop on a table top — you can take it to the job.

#### DALIC SOLUTIONS AVAILABLE

BISMUTH  
CADMIUM  
CHROMIUM  
COBALT  
COPPER

GALLIUM  
GERMANIUM  
GOLD  
INDIUM  
IRON

NICKEL  
NICKEL (Black)  
PALLADIUM  
PLATINUM  
RHODIUM

LEAD  
SILVER  
THALLIUM  
TIN  
ZINC

for further information write to

**DALIC METACHEMICAL LIMITED**

121 LEICESTER AVENUE, TORONTO 18, ONTARIO

**MARLANE DEVELOPMENT CO., INC.**

153 E. 26th STREET, NEW YORK 10, N.Y.

## Die castings

(Continued from page 66)

To reduce weight, maintain low production costs and modernize their standard typewriter Model 150, engineers of the Underwood Corporation have effected a major product improvement with a one-piece aluminum die cast main frame, which replaces the former assembly of six iron sand castings. The immediate advantages of the changeover are obvious: (1) rigidity of the frame — markedly increased; (2) weight — 4½ lb less; (3) assembly of the frame — eliminated; (4) machining of the frame — almost eliminated; and (5) many assembly fasteners and other small parts — eliminated.

Add to these savings one of the major advantages of die casting — its ability to produce metal components with a very smooth surface. The design and production of a dense, nonporous, smooth die cast frame eliminated the need for a primer coat in the finishing process.

Die cast aluminum (ASTM Spec. B85-52T, Alloy SC 84A) was specified for the frame because of its great characteristics combined with lightweight. Many cores in the single cavity die provide the frame's various undercuts and intricate shape. These walls, characteristic of die casting, are a key factor in keeping the weight down on each of the 120,000 frames produced annually. Unique in die casting practice is the retention of the casting's "gate" throughout the machining cycle, to provide extra rigidity and to ensure dimensional accuracy. Afterwards, the gate is removed in a simple punch and die.

The one-piece die cast frame gives this typewriter a "built-in" strength and dimensional stability that eliminates variations often occurring in assemblies. ★

#### PENSIONERS

##### MEN SOON TO RETIRE

With experience as salesmen, branch managers, sales managers or background of experience at sales or supervisory level, are invited to answer this advertisement. If you are active and in good health we have, because of our circulation expansion program, exclusive local and home territories throughout Canada arranged for 15 hours to full time weekly effort. Generous commissions with drawing account, as qualified, successful applicants would cover 5 to 11 different retail fields including this one. A limited number of applications of sales minded but inexperienced applicants are also invited. Scores of old customers in each territory as a result of our 69 years in business. Write John Foy, Maclean-Hunter Publishing Company, Business Services Division, Room 500, 481 University Avenue, Toronto 2, Ont.



*The  
Proof  
of  
Quality*




## STAINLESS STEEL

From the balanced blending of metals to the close and careful inspection of the finished casting, 'Shawinigan' laboratory control produces the finest stainless steel in Canada.

This 'Shawinigan' *full control* is your proof of quality . . . your guarantee that 'Shawinigan' Stainless Steel corrosion and heat resistant castings meet every rigid specification for uniformity, longer life and carefree service.

For a quarter of a century, 'Shawinigan' has pioneered the production of superior Stainless Steel for your particular requirements. Investigate the possibility of saving money in your business with 'Shawinigan' Stainless Steel corrosion and heat resistant castings.




**SHAWINIGAN CHEMICALS LIMITED**  
*Stainless Steel and Alloys Division*

Head Office: Shawinigan Building, Montreal, Que. — Plant: Shawinigan Falls, Que.



# Non-Habit-Forming



Pressure gage courtesy J. E. Lonergan Co., Philadelphia 6, Pa.

## *Beryllium Copper Tubing by Superior*

This unusual term describes perfectly one of the most important properties of beryllium copper tubing. The Bourdon tube shown above is an excellent example. Once the beryllium copper tube is in the gage, it "remembers" its job and acquires no new habits. It yields constantly to pressure and as constantly returns to its original position without taking a new "set."

Beryllium copper tubing by Superior has this and many other important characteristics to a marked degree, such as hardenability, corrosion and fatigue resistance, thermal and electrical conductivity. It is easy to fabricate, it is nonmagnetic.

Beryllium copper tubing lends itself to a wide variety of applications. It can be severely worked to form convoluted flexible waveguides and bellows. Cold drawn to specifications, followed by proper hardening, it

makes an excellent aircraft antenna, with the strength to withstand thousands of hours' vibrating in 100 mph winds. Used as a contact roll in a business machine collator, it is wear and corrosion-resistant, and a good electrical conductor. Or, as above, shaped for use as a Bourdon tube, it is tough, ductile, durable—and holds its original shape.

Superior produces tubing in over 63 analyses... in stainless, alloy and carbon steels, nickel and nickel alloys, beryllium copper, titanium and zirconium. Let Superior's tubemanship and experience help you solve your tubing problems. You'll like the service and the products—they *are* habit-forming. Send for your free copy of Data Memorandum No. 7 on beryllium copper tubing. Write Superior Tube Company, 2031 Germantown Ave., Norristown, Pa.

# *Superior Tube*

The big name in small tubing

**NORRISTOWN, PA.**

*All analyses .010 in. to 3/8 in. OD—certain analyses in light walls up to 2 1/2 in. OD*

**Lyman Tube & Bearings, Ltd., Montreal, Toronto and Winnipeg**  
**Alloy Metal Sales, Limited, Montreal, Toronto and Winnipeg**  
**Robert W. Bartram, Montreal**

## Book Department

### Handbook of fastening and joining of metal parts.

One of the basic keys to mass production is an intimate knowledge of how to fasten parts together. Efficiency depends not only on how fast and cheaply a part can be made, but also on how quickly a product can be assembled.

Yet few books have been written on the subject of fastening and joining and those that have are either directed to the production engineer or confined to one specialized technique. In only a few has information issued by technical societies and associations, such as the ASME, SAE, AWS and others been correlated for the designer. In none have standards been supplemented with solutions to fundamental problems of joining and assembly. In this volume the authors, **Vallory H. Laughner** and **Augustus D. Hargan**, have attempted to overcome such deficiencies.

The ultimate aim has been to provide the design engineer with both a reference and an idea source covering all known methods of joining metal parts. The production engineer should also find the book of value, if only from the standpoint of how to redesign to minimize assembly problems. Information on production methods, machines, jigs and fixtures has, however, been included only when necessary to establish clearly the advantages and limitations of any one technique or fastener.


The first section covers fundamentals of various fasteners and fastening techniques. The approach in each chapter is different because the techniques are basically unrelated. Thus, the chapters on threaded fasteners consist mostly of descriptions of standard types, guidance on where they can be used and tables of established sizes. The chapters on welding and brazing, on the other hand, cover the advantages, limitations and application for each welding and brazing method; recommended joint design; and types of materials and products to which each technique can be adapted.

The second section — the Supplement — is based on the principle that no designer has difficulty in calling to mind several methods of fastening, say, glass to metal . . . or a number of low cost shaft couplings . . . or a few ways of joining sheets without fasteners . . . but that none will remember a score of ways of accomplishing each objective. The solutions to such problems are presented in sketch and caption form in the hope that each page will provide a refresher and an idea reference for engineers in all phases of industry.

The book is published by McGraw-Hill and the price is \$18. It should prove an invaluable source of reference and make a worthwhile addition to your shelves.


**JOHN CRANE**

## Shaft Seal Design With A Purpose!




### POSITIVE DRIVE

This gives long seal life. Drive is transmitted through the driving band and washer driving notch which absorb all breakout and running torque. Damaging stresses on the bellows or flexible sealing member are eliminated. Slippage is also eliminated, thus protecting shaft or sleeve against galling.



### FLEXIBILITY

Axial and radial misalignment problems are eliminated. Self-adjusting bellows or sealing head automatically compensates for shaft end play or run out. Minimum spring pressure is required for axial shaft movement and uniform spring pressure is maintained during radial shaft movement.



### PRECISION MANUFACTURE

Leakproof performance is assured. Washer and seat surfaces are precision lapped to a perfect mate under a patented "John Crane" process.

### A SEAL FOR EVERY SERVICE

All "John Crane" Seals are constructed to the particular service requirements . . . from hot or cold water to the most destructive acids, corrosives and gases . . . temperatures up to 1000°F. . . pressures to 1200 psi. They can be furnished in types and sizes to meet practically any mechanical or dimensional condition.

Request Bulletin S-204-2. Containing full information on "John Crane" engineered shaft seals.

### GET COMPLETE DETAILS



Crane Packing Co., Ltd.,  
631 Parkdale Ave. N.,  
Hamilton, Ontario



## Pacemakers IN PLASTICS



The right kind of moulding does much to increase the sales appeal of plastic products. And the right production method can do a great deal to reduce costs. If you are considering the use of plastics, investigate the services we offer. They include facilities for engineering, development, tooling, manufacturing and assembly.

Please write for further details.

SERVING  
INDUSTRY  
WITH

COMPRESSION MOULDING  
INJECTION MOULDING  
EXTRUSIONS . . . FABRICATING  
LOW PRESSURE LAMINATING  
VACUUM FORMING . . . SILASTICS

*If the job calls for Plastics, call in*

# SMITH & STONE



**LIMITED**  
GENERAL OFFICES: 50 ST. CLAIR AVENUE WEST • TORONTO  
Sales Offices: Montreal • Toronto • Winnipeg • Calgary • Vancouver

## Sampling switches

(Continued from page 39)

ground station equipment then reverses this procedure so as to separate, identify, and/or record the transmitted information. Close synchronization must constantly be maintained between the ground and airborne equipment placing emphasis on accuracy of duty cycles and sampling rates.

Airborne and missile applications have divergent requirements. An expendable, low-cost, medium life switch is usually required for the smaller missile evaluation tests. A typical 2 pole, 30 channel 5 rpm expendable unit, complete with a 28 or 6 volt dc magnetically shielded PM motor is illustrated. A precision worm reduction and separate completely shielded RF filter is included.

On the other hand, recoverable missile programs require extensive ground testing and as with airplane flight testing, require longer life, serviceable units. Figure shows a special hermetically sealed, 6 pole, 12 channel, 400 cycle AC motor driven switch.

The current impetus in missile and airplane advancement is constantly increasing the severity of the environmental specifications required.

The shock, acceleration, vibration, altitude and of course the ambient temperatures specified impose strict limitations on materials and on switch packaging.

The single gun, cathode ray oscilloscope's usefulness can be greatly expanded by the effective use of time-sharing techniques. Common applications include the simultaneous display of the outputs of up to 100 or more signals, such as, tube characteristic or transistor curve displays radar, navigational and fire control systems.

In each case, a large number of different input signals are connected to a single gun oscilloscope at a high sampling rate so as to make them appear simultaneous and to prevent the appearance of flicker. A sampling rate range of from 5 to 10 rps is normally used.

Shown is a 6 pole, 45 non-shorting channel unit provided with a dynamic phase adjustment feature. This type of unit is particularly useful in the early stages of system development as it allows phasing and wiring to be frequently changed without necessitating disassembly of the switch. Usually, if the system goes into production, a transition is afforded into a precision fixed phase, Inside-Out switch construction for the resultant savings in space and ease of servicing.

One is tempted to use the much discussed term, automation in describing the broad scope of switch applications to industrial instrumentation. Many of



the applications mentioned in this article under other headings are also used industrially.

With the current trend of increasing mechanization and feedback electronic control of complex processing equipment, the effective utilization of time sharing techniques provides appreciable savings in equipment, space, and cost.

Requirements for amplifying recording, displaying or simulating the output signals from banks of transducers, are frequent. Sampling switches provide a practical answer for time-sharing the expensive and bulky equipment required. New, lower cost designs have been made available in answer to the constant demand for increased economy.

Since long life is consistently a requirement, unusual stress is placed on ease of access and servicing.

A single, specially designed 2 pole switch can be used to advantage to chopper stabilize a bank of high gain dc amplifiers. The switch continuously samples the input and output of each amplifier in turn, compares them and then automatically applies the corrective signal necessary. One switch can thus replace as many as 100 choppers and their associated balancing amplifiers, affording increased economy, reliability, as well as reduction of the space required.

Precision computers require unusually long total lives of 10,000 hours or more as many are operated continuously 24 hours a day, seven days a week. In such applications, reliability, freedom of access and simple servicing are important.




Down hole logging of oil wells is a rapidly growing field. A common means for checking or predicting the performance of an oil well is electronically to measure and record the earth resistivity, potential or electrical field variations. It is interesting to realize that since space is limited, no cooling can be provided. Hence, in the deeper wells, the environmental temperatures may be as high as 300 F or higher.

Switches mounted with the measuring instruments are lowered into the well and are used to time-share the miles of cable and the recording equipment located topside.

The continued technical advance in high speed rotary switch design provides a reliable, high performance new component to tax the ingenuity of the design engineer.

It is hoped that this article will lend encouragement to the application of high speed switches to meet new requirements. Suitability to low level applications, dependability, small size, long service-free life and simple servicing make sampling switches the preferred means for low frequency time-sharing duties. ★

## G-E PERMANENT MAGNETS can help you solve production and design problems



There are thousands of ways for using G-E Alnico Permanent Magnets in manufactured products, production methods or in making simple, time-saving tools for use in factories, offices or the home. To help you make money . . . to help you save money, many of these ideas are gathered in a free Folder of Ideas . . . complete technical data for engineers and technicians is covered in the 40-page Design Manual. To get these ideas and factual data, simply fill out and mail the coupon below.



# PERMANENT MAGNETS

CANADIAN GENERAL ELECTRIC  
COMPANY LIMITED



Permanent Magnet Sales  
Canadian General Electric Co. Ltd.  
940 Lansdowne Ave.  
Toronto, Ontario.

462W—356


Please send ☐ Magnet Ideas for Industrial Plants  
☐ Design Manual on G-E Alnico Permanent Magnets

Name.....  
Company.....  
Address.....  
City..... Prov.....

**SPEED UP**  
hole punching  
**OVER 50%**

WITH THE  
**WALES FABRICATOR**  
AND THE  
**positive DUPLICATOR**

IMMEDIATE  
DELIVERY



• Here's a big money maker in any sheet metal shop. Punches and dies for round and shaped holes take only seconds to remove and replace. Complete sets are always ready in handy cabinet. For holes up to 3½" diameter the "WALES-WAY" quick change method saves plenty of time on your job. The WALES FABRICATOR is the PRACTICAL single-hole punching equipment with plenty of reserve power for punching up to ¼" plate.

• The NEW positive DUPLICATOR

This husky WALES DUPLICATOR increases the scope of your WALES FABRICATOR to make production runs both practical and profitable. It permits positive duplication of unlimited hole patterns from master templates to jig borer tolerances. The templet is secured in steel work table of DUPLICATOR. Cam action clamps position work piece. Holes are located quickly and easily by a stylus type locator pin. Press gently and the hole is duplicated exactly on the work piece. The WALES positive DUPLICATOR DOES a terrific job. Any man in your shop can handle it perfectly in a few minutes.



Send for Bulletin No. 00  
Get the complete story of the  
WALES FABRICATOR AND DUPLICATOR

**WALES Strippit OF CANADA LTD.**

"...the Wales-WAY is the PLUS-PROFIT way"

1105 MAIN STREET EAST — Hamilton, Ont.

WALES-STRIPIIT COMPANY, N. YONAWANDA, N. Y.

Can these parts be  
made in **STEEL?**



IT'S SIMPLE IN  
**PRECISION CASTINGS**  
AND ECONOMICAL TOO!

Parts difficult to fabricate or to machine are readily and inexpensively produced as Precision Castings.

Precision Castings by the LOST WAX PROCESS offer:

1. Lower initial tooling costs.
2. An ideal process for short runs.
3. Castings with greater density and strength.
4. Wider selection of alloys.
5. Wider scope in design.
6. Greater savings for items having intricate shapes and requiring complicated machining.

Write For Further Information To-day!



**INDUSTRIAL FINE CASTINGS LTD.**

272 GEARY AVENUE


TORONTO 4, ONTARIO

**EYELETS  
AND  
"POP"  
RIVETS**

USMC Standardized Eyelets reinforce as well as fasten—they're easy, fast and economical to apply.

"POP" Rivets handle blind spots and open sections—can be driven at rate of 1200 per hour.

Write for catalogues.



**USMC**

**UNITED SHOE MACHINERY COMPANY**

OF CANADA LIMITED

MONTREAL • TORONTO • GALT • QUEBEC

## Loudspeaker

(Continued from page 49)

A tandem permanent magnet assembly is used. The circumferential surface of the centre plate provides a good position for supporting the overhanging mass of the speaker unit when mounted in a cabinet. Due to the separate airgaps for the LF and HF sections of the magnet assembly, and the low reluctance common flux path in the centre plate, electro-magnetic intermodulation is negligible. Alcomax II magnet material is used which results in gap flux densities as follows:—

	LF	HF
Gap flux density (gauss)	14,300	12,700
Total flux (Maxwells)	285,000	48,000

These flux values, in conjunction with the moving coil and diaphragm details, provide a balanced output from the relatively high efficiency horn-type HF unit and the direct-radiator LF diaphragm.

The conventional frequency/intensity response curve can be misleading with regard to the expected subjective results when a listening test is carried out. A method of delayed resonance response measurement has therefore been used as a method for determining the frequency response characteristic of the speaker.

A train of waves having a square envelope of a selected frequency is applied to the moving coil of the speaker, and the resultant sound intensity is measured at the time of the signal and at suitable intervals after the electrical input has ceased. Measurement is carried out by a microphone with amplifier and a suitable presentation measuring unit, such as a cathode ray oscilloscope.

Tests were carried out under conditions where reflected energy from the surroundings was so low that it did not appreciably affect the readings.

The response of the loudspeaker, particularly at the bass end of the audio range, is dependent to a large extent upon the conditions of mounting. BTH provides a suitable bass reflex cabinet in wood with an internal air volume of 7 cu. ft. and grill which is both decorative and relatively non-absorbent to the high audio-frequency output. ★

### Changing your address?

If you change your address be sure to notify our subscription department quoting both your old and new addresses.

# Norgren

## NOW OFFERS

### FASTER, BETTER LOCAL SERVICE



**Norgren**  
PNEUMATIC  
PRODUCTS



## PHONE

your nearby Norgren  
District Representative and Distributor

#### BALTIMORE, MD.

A. L. Hacker Co.  
308 Wyndhurst Ave.  
HOpkins 7-5700

#### BIRMINGHAM, ALA.

J. T. Sudduth & Co., Inc.  
3017 Sixth Ave., South  
AL 2-6101

#### BUFFALO, N. Y.

F. Bjerre Co.  
120 Pierce Ave., Hamburg  
EMerson 5282

#### CHARLOTTE, N. C.

L. W. Kinnear & Co.  
1909 Shoreham Drive  
EDison 2-6560

#### CHICAGO, ILL.

Walter Norris Engineering Co.  
20 North Wacker Drive  
StAte 2-2804

#### CLEVELAND, OHIO

F. & W. Ursem Company  
1548 West 117th Street  
LAKewood 1-9136

#### DALLAS, TEXAS

Leo J. Schindler Co.  
6007 Berkshire Lane  
EMerson 7774

#### DAYTON, OHIO

K. C. Mosier Company  
628 South Ludlow Street  
Michigan 9805

#### DENVER, COLO.

E. C. Wild Company  
695 South Garfield Street  
SPRuce 7-2852

#### DETROIT, MICH.

Wm. H. Nash Company  
10300 Grand River Ave.  
TEXas 4-1111

#### FT. WAYNE, IND.

Neff Engineering Co.  
2339 Crescent Avenue  
EAsbrook 7391

#### HARTFORD, CONN.

Pearse-Pearson Company  
1005 B. Farmington Ave. Plaza  
JACKson 3-5261

#### KANSAS CITY, MO.

Ellis Akin Engineering Co.  
2934 Cherry Street  
WEStport 1-9189

#### LOS ANGELES, CALIF.

Teglen Engineering Co.  
1942 Huntington Drive, So. Pasadena  
PYramid 1-2856

#### LOUISVILLE, KY.

Charles Weber Company  
536 Eastern Parkway  
MEIrose 7-2574

#### MILWAUKEE, WIS.

C. L. Thompson Company  
4417 West Lisbon Avenue  
Hilltop 4-4817

#### MINNEAPOLIS, MINN.

H. U. Rogness, Inc.  
135 South 11th Street  
FEDeral 3-5595

#### NEWARK, N. J.

K. E. Knotts Company  
106 Millin Street, Cranford  
CRanford 6-3887

#### OKLAHOMA CITY, OKLA.

Nix Industrial Supply Co.  
2702 South High  
MEIrose 7-5400

#### PHILADELPHIA, PA.

J. A. Moody Company  
10 West Avenue, Wayne  
WAYne 3441

#### PITTSBURGH, PA.

Leonard R. Nourie, Inc.  
2414 West Liberty Avenue  
LOCust 1-1628

#### PORTLAND, OREGON

Power Transmission Products  
1107 Northwest 14th Avenue  
CAPitol 7-1271

#### SAN FRANCISCO, CALIF.

The Burke Company  
1455 Bayshore Boulevard  
DElaware 3-8261

#### SEATTLE, WASH.

George W. Warden Company  
1305 Dexter Avenue  
ALder 0622

#### SHREVEPORT, LA.

Harris Frederic & Company  
100 Edwards Street  
3-8038

#### ST. LOUIS, MO.

Sturgis Equipment Company  
601 South Taylor Avenue  
OLive 2-5380

#### SYRACUSE, N. Y.

Ralph W. Earl Company  
530 East Washington Street  
2-1655

#### CANADA

**MONTREAL**  
Cowper Company Limited  
515 Fourth Avenue  
NE 7-6746

#### TORONTO

John Spotton Company Ltd.  
21 Carson Street  
CLifford 9-3788

#### VANCOUVER

Galbraith & Sulley Ltd.  
1331 West 6th Avenue  
CHerry 5121



**C. A. NORGREN CO.**

*Wherever Air is Used in Industry*

1445 So. Elati Street, Englewood, Colorado



## New products & materials


### New items which can help you on the job

Hermetically sealed, moisture and dust proof Ledex rotary selector switches and stepping relays have been developed by **G. H. Leland, Inc.**

The switches and relays, which are applicable in the automation, electronics and aircraft fields, are protected from the effects of salt spray, fungus and humidity.

Both are hermetically sealed in an inert atmosphere of dry nitrogen with a slight addition of helium tracer. Sealing is to test No. 1 of MIL-R-25018.

This type of installation protects against any tampering with the contacts or the relay mechanism. It also prevents shock or injury to personnel.



**Where no mushrooms grow**

This hermetically sealed package is available in several standard enclosure sizes. Standard hermetically sealed switches are available with a maximum of four wafers and 105 pins in the header. (206)

#### Portable Spacing Comparator

This instrument checks the spacing on flat and circular thread rolling dies, thread chasers, circular and flat form tools, wheel crusher rolls, gear racks, broaches, aircraft parts, such as turbine blades, and checks the location of forms from their locating face or surface as well as inspection on all threaded products. It is made by the **Jerpbak-Bayless Company.** (207)

#### Paste type brazing flux

A new paste type flux for high temperature brazing of stainless and other high alloy steels is now available from the Stainless Processing Division of **Wall Colmonoy Corporation.**

Called Microbraz Flux, the new material cleans and promotes wetting of the surfaces to be joined and helps dissolve

oxides during the brazing action. The oxidation protection accomplishes four important brazing objectives: (1) it contributes to production of better joints on stainless steels, particularly when brazing difficult alloys such as Inconel X and other special alloys containing elements that place them high in the electromotive series; (2) it permits high temperature brazing with an oxy-acetylene torch and without special atmospheres; (3) it permits use of less expensive atmospheres when furnace brazing stainless steels and high chromium alloys; and (4) it permits the brazing of titanium or aluminum bearing stainless alloys in hydrogen atmospheres. (208)


#### Disc Dial

Precision engraved disc dial and vernier sets are available from **Pic Design Corp.** in 4 ranges of diameter 1½ in., 2 in., 3 in., and 4 in. The complete set consists of the disc dial and vernier, which allows reading within an accuracy of 6 minutes.

The vernier sets are made of aluminum and are finished black anodized to military specification. The engraving is filled with white.

Stock standard units are engraved in 1 deg. steps reading from 0 to 360 deg.

Type K1 and K2 stainless steel hubs are also available from stock for assembly to these dials, thus offering a wide range of availability of bore sizes. (209)




**The vernier is aluminum**

#### Low-Pressure Boiler

The low horse-power field has been entered by **Orr and Sembower, Inc.** with a compact, rugged packaged automatic low-pressure boiler for oil and gas firing that embodies top engineering features of its well-known Powermaster units for heavier industrial use.

The new Power-Pak is designed to provide steam or hot water heating or hot water service with power demand of 10, 15, 20 and 25 hp. Thus it may be used in such applications as smaller schools, office buildings, apartments, greenhouses, hospitals and churches. It is also intended for auxiliary use in large industrial plants and warehouses.



**Bath anyone?**

It is the only unit of its type and capacity that meets ASME standards of 5 boiler hp per sq. ft. of heating surface throughout its full range.

It is described as the first low-priced, packaged automatic boiler, in this horsepower range, that has the rugged construction and precision engineering of industrial boilers. It is fully firetested and guaranteed before being shipped. Like the Powermaster, it can be equipped with either oil or gas firing equipment. (210)

#### Self-tapping Studs

A new double-ended stud that cuts its own thread when driven in an ordinary drilled hole, and locks securely in the same operation, has been announced.

Known as the Schweppe stud, it is a product of the **Pheoll Manufacturing Co.,** makers of screws, bolts, nuts and industrial fasteners.

Further, it is claimed that this stud is the only commercial stud which can be automated. This is because it can be located accurately from the slotted end to permit hopperizing for automatic feeding and driving of studs.

The studs can be installed at high speed with a normal power stud driver. (211)





*Write for  
Technical  
Details*

**① HIGH STABILITY CARBON RESISTORS**

Available in 1% tolerance ohmic values from 10 ohms to 100 megohms, and in 6 physical sizes. The Welwyn Panclimatic coating assures a long stable life under the most severe service conditions. Manufactured in Canada.

**② VITREOUS ENAMELLED CAPACITORS**

A new tropicalized capacitor, completely vitrified both as to dielectric and coating. The Welwyn Vitricon features a low power factor and an operating range up to 150°C.

**③ GLASS ENCLOSED HIGH VALUE RESISTORS**

A glass enveloped hermetically sealed resistor for use where resistance values up to  $10^{12} \Omega$  are required.

**④ METAL FILM RESISTORS**

A true gold-platinum film resistor with a stability and performance comparable to that of many wire wound resistors.

**⑤ VITREOUS WIRE WOUND RESISTORS**

A superior power wire wound resistor designed for high temperature service. Power ratings from 3 watts to 300 watts.

**ALSO AVAILABLE BUT NOT ILLUSTRATED**

Insulated Carbon Resistors, High Voltage Resistors, Coaxial Line Terminating Resistors.



**Welwyn Canada Limited**

1255 Brydges Street, LONDON, Ontario

Operating in the U.S.A.

WELWYN INTERNATIONAL INC., 3355 EDGECLIFF TERRACE, CLEVELAND 11, OHIO

## New Products

(Continued from page 80)


A new tube fitting anchor or mounting stud to simplify support of tubing lines is offered by **Parker Appliance Co.**

The stud, featured at the recent Instrument Show in New York, is a bolt type adapter made in both the Intrulok and Triple-lok styles. The former is the brass, flareless-type tube fitting especially suitable for instrumentation lines of either copper or plastic tubing. The latter is a flare-type fitting, made in brass, aluminum, steel or stainless steel.

The stud is used to mount a tee or cross fitting directly to a bracket or in a threaded boss. The mounting adapter is convenient for lead-off locations in banks of tubes. (212)

### Delay Valve

A line of 2 way, 3 way and 4 way time delay valves is announced by **Airmatic Valves, Incorporated.**



Delayed as much as 5 minutes

The time delay valve provides delayed actuation with immediate reversal or immediate actuation and delayed reversal.

Working on a volume principle, an operating time of from 0 to 5 min. delay may be accomplished by manual pre-set adjustment.

Since they are pilot operated, these valves may be remotely located and controlled from a central station.

They are available in standard pipe sizes 1/4 in., 3/8 in., 1/2 in. and 3/4 in. (213)

### Enclosure covers

Another instance of unobtrusive yet valuable refinements made possible, at low cost, by intelligent industrial product design is provided by new-style enclosure covers for certain types of **Square D Company Canada Ltd.** starters. Concealed under the name plate on the cover of the smart new Quik-Change Series A starter is a knockout, by means of which a push button or a selective switch can be added to the field, quickly and easily. Normally such changes involve considerable shut-down time and costly wiring. Space is also provided in the enclosure for adding four extra auxiliary contacts.

Another feature is the molded coil. Of improved design, this coil is less subject to mechanical injury, operates cooler because of more rapid heat transfer and makes for easier coil changes. (214)

### Improved battery

Transport batteries made by **Exide** now have silvium alloy positive grids, a lead oxide active material known as GOX and Pormax plate separators. The weight and size of the batteries remain within commercial and military requirements.

Silvium, a patented alloy of silver, lead and other metals, gives added assurance of reserve power for a plane's electrical load. Having the highest resistance to electrolytic corrosion yet attained in lead-acid battery grid alloys, silvium is best able to withstand abuse from overcharging, a risk on long distance flights. Grid alloy durability has been increased to keep pace with the trend toward heavier generating equipment required for bigger electrical loads. In this way, silvium insures against battery failures which cause take-off delays or loss of vital reserve power for communications and controls. GOX has at least three times more surface area exposed to the electrolyte than ordinary active metals. (215)

### Transducer Unit

A new transducer unit, known as Nultrax, has been developed by the electronics division of **Canadian Westinghouse.** It makes possible the measurement of linear displacement to accuracies of one part in 100,000 over its full length and can be used for applications where effective travel lengths of up to 10 ft. are involved. This range is expected to be increased in the future.

The accuracy is accomplished by converting dimensional data into precise electrical equivalents. The name is derived from the fact that the device operates by seeking or tracking a null point in a sinusoidal function.

Incorporated in either simple measuring systems or in complete positioning systems, the new unit provides the ex-

treme accuracy necessary for the automatic control and programming of machine tools. Although particularly suitable for automatic control and programming, the new unit can be used for any operation requiring precise linear measurement.

A few typical applications in the machine tool field are: lathes, jig borers, boring mills, milling machines, grinders, drilling machines, gear cutters and other special machines. It can also be used for precision instruments such as microscopes, testing machines, gauges and comparators.

High accuracy and a repeatability greater than 20 microns makes the unit suitable for a variety of operations in the aircraft, automotive, chemical, petroleum and other industries. (216)

### Vacuum Gauge

A new single meter type vacuum gauge, 0-100 microns Hg full scale, is announced by **Hastings-Raydist, Inc.**

The new instrument has a 4-in. indicating meter with a knife edge pointer for direct reading on a logarithmic mir-




Measuring the microns

ror meter scale. Half scale on the dial face is 15 microns, providing excellent readability for low micron measurements. The instrument is highly accurate throughout the entire range.

An improved design of the gauge tube, incorporating a patented temperature compensated noble metal thermopile, provides greater sensitivity and higher accuracy in the low micron range. The noble metal thermopile is housed in a nickel plated gauge tube, thus affording freedom from outgassing, system contamination and corrosion. The gauge tube is extremely rugged, has quick response and is not damaged by release to atmospheric or positive pressures. The gauge tube need not be removed during cleaning of the vacuum system.

The instrument operates on 115 volt ac and includes an internal voltage regulator to eliminate any effect from line voltage variations. (217)

# If You Need Metal Enclosures Save Time and Tooling with—



## LINDSAY PREFABRICATED ASSEMBLIES

A Lindsay Prefabricated Assembly for the housing on a 38 ft high "Cold Box." The lower LS panels withstand a pressure of about 500 pounds per square foot.

Lindsay prefabricated assemblies are tailored to your exact needs from die-formed, standardized Lindsay Structure components... fabricated in 78,085 panel sizes... available in mild steel, stainless steel, copper, or aluminum... shipped k/d for quick assembly with standard tools. LS shipments can be scheduled to keep pace with your production needs. Fast service on pilot units.

Put this versatile, prefabricated structure to work for you... simplify designing, save on dies and tooling, conserve skilled man power. Write, today, for descriptive folder or send single-line drawing for prompt cost estimate.



Model machine enclosed in Lindsay Structure.



LINDSAY-WILSON LIMITED  
1466 Lake Shore Rd., Long Branch, Ont.  
Toronto 14



# Patents

## Some new ideas win protection in Canada

A DIAL AND POINTER, designed to assist motorists to park their cars, is covered by Canadian Patent 523,853, issued April 17, 1956 to Julius C. Basso of Owosso, Mich., who invented the device. The dial is designed to be mounted on the shelf above the dashboard of the car and the pointer is set at an angle that is found by experience to give good results when backing a particular car into the parking space. An angle of 35 deg is suggested by the inventor as generally suitable.

When the driver wants to park his car, he drives up beside the vehicle behind which he is to park, cuts his wheel sharply and backs up until the pointer is parallel to the roadway. The wheels are then turned sharply in the other direction and the parking operation completed.

### Glass building block

A GLASS BUILDING block that automatically prevents mortar from adhering to the transparent surfaces is covered by Canadian Patent 524,868, issued on May 8, 1956 to Pittsburgh Corning Corporation of Pittsburgh. Invented by Dominic D'Eustachio, of Port Allegany, Pa., the building block has its opposite exterior faces covered with a transparent organopolysiloxane resinous film. Only the marginal edge surfaces between the exterior faces are free from the film and thus these are the only surfaces to which mortar will bond.

### Vacuum tube electrode

A NEW KIND OF electrode for vacuum tubes has been patented by Westinghouse Electric Corporation in Canada Patent 519,064, reissued November 29, 1955.

Invented by John H. Findley of Upper Montclair, N.J., and Dewey D. Knowles of Lowman, N.Y., the new electrode is said to have the low secondary emission ratio of powdered carbon without suffering from the usual disadvantages of this material—its inability to stick to the base metal tightly enough.

The electrode has a supporting base metal of molybdenum or tantalum having a smooth surface. On this a layer of fine particles of tantalum powder is painted or sprayed, and then fired or sintered so that the powder adheres firmly to the base metal. This layer of small particles of tantalum is graphitized by

heating in a hydrogen atmosphere containing benzene vapor.

The patented structure has the advantage that electrons emitted from the region between the tantalum particles are likely to strike another particle of graphite-coated tantalum powder instead of moving out into the open space beyond thus accounting for the low secondary emission ratio.

### Heat-insulating material

A NEW INSULATED fabric that is suitable for heat-insulating gloves and other articles of protective clothing has been patented by Johns-Manville Corporation of New York. Invented by Jesse L. Tucker, of North Plainfield, New Jersey, and covered by Canadian Patent 524,842, issued May 8, 1956, the fabric consists of outer and inner laminations of flexible asbestos cloth, with an intermediate lamination of metal foil. Between the metal foil and the asbestos there is a woolen-fabric liner.

### For the land of nod

A CONVERTIBLE MATTRESS for either twin or double bed use is covered by Canadian Patent 524,716, issued May 8, 1956 to the inventor Dwight A. Griggs, of Braintree, Mass. The mattress is composed of two standard twin-bed size mattresses that have well-defined beading around their edges. Under the upper edge beading on one side of each of the mattresses is one of the two sections of a standard slide fastener. To make a single mattress of double-bed size, the two twin-bed mattresses are placed side by side and zipped together along the upper edges.

### Flanges for tubes

A METHOD FOR flanging thin-walled metal tubing that uses a helical coil of strip metal was patented in Canada on December 13, 1955 by the inventor, James J. Kraus, of Neenah, Wis.

According to Patent No. 519,332, the metal strip is coiled edgewise in the plane of the strip to form a tight helix, and the helix is applied to the end of the tube so that the end turn of the helix can be progressively attached to the end of the tubing.

When the length of strip required to form a continuous flange is determined, it is cut from the helix, the extremities of the strip aligned with each other and joined, and the remainder of the length of the strip attached to the end of the tube.

### Canadian Patent Laws

THE PATENT LAWS of Canada do not slavishly follow those of the U. S., stated John H. Graham of Esso Research recently. Rather, they are set in a somewhat similar mold. As in all other countries which are considered to follow a Master system and are classified by their common features of prosecution and procedural requirements, the parallel regulations of Canada and the U. S. A. become traps for the unwary if careful attention to the deviations from that parallel is not exercised.

With the Royal Commission currently investigating all phases of Canadian industrial property rights, many investigators are scrutinizing the law of patents and all the controlling regulations with respect thereto, to determine whether radical changes are needed. It has been proposed variously to orient those laws more closely to those of the U. S. or to those of Great Britain or to leave the Canadian patent laws as they are.

There are, apparently, advocates for each of these three propositions. Those who cleave to the idea that Canadian patent law should be most closely patterned on the U. S. patent statutes, usually contend that the present laws of the two countries are practically equivalent. Those who advocate the British system advance the theory that, whatever the form of statute, the philosophy behind the patent law is that of the English Statute of Monopolies of 1624 and since Canadian patent jurisprudence leans heavily on British decisions and interpretations, the laws should be more closely allied.

The third proposition, namely, whether Canadian law should be left in its present form, warrants a careful analysis. Contrary to the opinion of many, Canadian patent law is in its major provisions by no means parallel in force, effect or scope to that of the U. S. Nor is there in any way a similar direct parallel to comparable British patent provisions. It assumes a position intermediate to the two patent statutes, having similarity in some sections, equivalency in others, and complete differences in still other regulations. Thus, the Canadian Patent Law of today, while recognized as a hybrid of the Statutes of Great Britain and the U. S. A. is, in essence, autonomous. Like many mutations, it has established its own environment and while turning occasionally to each parent for that guidance concomitant of a greater experience, manages to carry on a separate existence.



**Would you like further  
facts about advertised  
products in this issue?**

# reader's SERVICE

LET OUR READER'S SERVICE department help you with full information about any products or Literature mentioned in this issue of **Design Engineering**.

• This is all you have to do: Each advertisement is indexed alphabetically. Turn to the index where you will find the advertisement that interests you listed with two numbers beside it. One of these numbers is the page, the other the Readers' Service identification number—set in bold face type.

• On the postage-free tear-out card (this page) circle the identification number and mail the card.

• Quickly the Reader's Service department will be working for you. All available information will be mailed at once to help you build a useful up-to-the-minute library from the technical booklets, pamphlets and pictures prepared for your use.

• Two Reader's Service Cards are provided to allow two readers to make use of the service where copies of **Design Engineering** are passed on.

• There is, of course, no charge for this service and no obligation.

DESIGN ENGINEERING SEPTEMBER 1956

BUSINESS REPLY POST CARD  
No postage necessary if mailed in Canada

5c postage will be paid by

**DESIGN ENGINEERING**

481 University Avenue,

Toronto, Ontario.

READER'S SERVICE DEPARTMENT



SEPTEMBER, 1956

Send DESIGN ENGINEERING for 1 year (\$5) ☐ or 2 years (\$9) ☐  
and bill me later.

**Advertisement key numbers**

100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115  
116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131  
132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147  
148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163  
164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179

**New products and literature**

200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215  
216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231

PLEASE PRINT

Name ..... Position .....

Company .....

Address .....

# reader's SERVICE

Would you like further  
facts about New Prod-  
ucts or File items de-  
scribed in this issue?

SEPTEMBER, 1956

Send DESIGN ENGINEERING for 1 year (\$5) ☐ or 2 years (\$9) ☐  
and bill me later.

## Advertisement key numbers

100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115  
116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131  
132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147  
148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163  
164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179

## New products and literature

200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215  
216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231

PLEASE PRINT

Name ..... Position .....

Company .....

Address .....

.....

LET OUR READER'S SERVICE department help you with full information about any New Products or Literature mentioned in this issue of **Design Engineering**.

• Following each announcement on the New Products and File pages are identification numbers in brackets.

• This is all you have to do: Circle the corresponding numbers of any items that especially interest you on the postage-free tear-out card on this page. Then mail the card.

• Quickly the Reader's Service department will be working for you. All available information will be mailed at once to help you build a useful up-to-the-minute library from the technical booklets, pamphlets and pictures prepared for your use.

• Two Reader's Service Cards are provided to allow two readers to make use of the service where copies of **Design Engineering** are passed on.

• There is, of course, no charge and no obligation.

BUSINESS REPLY POST CARD  
No postage necessary if mailed in Canada

5c postage will be paid by

DESIGN ENGINEERING

481 University Avenue,

Toronto, Ontario.





**This is a Production Manager**

(in a desperate situation)

**keeping the line rolling**

(on a rush order)

**by trying to bridge the gap**

(requiring special components)

**a dependable service  
on forgings could close**

(from Wallaceburg, of course)

If the situation demands fast service on components it's time to call in the man from Wallaceburg. For fifty years we've been supplying industry with component parts—at the right time and at the right price.

Now, with Wallaceburg-Singer Limited producing cored brass forgings we've more than ever to offer. Call us for Cored Brass Forgings, Die-Castings in zinc and aluminum, Machined Sand Castings in brass and bronze, and Automatic Screw Machine Products in brass, steel and aluminum.

**WALLACEBURG**

BRASS LIMITED

WALLACEBURG, ONTARIO

AND AFFILIATED COMPANIES

WALLACEBURG-SINGER LIMITED  
DOMINION DIE CASTING LIMITED


BRANCHES: MONTREAL, TORONTO, MONCTON, LONDON, WINNIPEG, CALGARY, VANCOUVER

## Design news in pictures



**The heart of the matter**

*An Atomics International physicist checks the core of a nuclear reactor built by his company for Chicago's Armour Research Foundation. This is the first built for private industrial research. 'Atom-splitting' takes place in this stainless steel core. Output of reactor is 50,000 watts. (218)*




**A shaver shows its teeth**

*Improved internal shaver hails from National Broach and Machine Co. Ease of use merely requires hanging the gear on the cutter, button pressing and removal. (219)*



**"Noteworthy and fresh approach . . ."**


*One of three designs to capture 1956 awards from the Industrial Designers Institute was William E. Clements' new-type electric thermometer for the nursing and medical professions. Producer of the "Therma Meter" is the Medical Research Institute Inc., Cincinnati. (220)*



**For buttoning-up boxes**

*New idea in fasteners is North American Aviation "Klimp." These spring steel clips have 30 times the holding power of nails and the boxes can be used over again. (221)*





**Changeover for the big stuff**

A giant stator for a power generator frames million volt lightning test equipment at Canadian Westinghouse. The company is rebuilding several for 60 cycle operation and they return to duty at No. 1 station Niagara Falls. (222)

## Some modern designs making news today



**Passengers in their pod**

Designed to eliminate the costly ground run of jet craft and the hazard of engine blast is Clark Equipment's new Mobile-Cruiser. It boards passengers at the gate, drives to the plane and raises them to the airliner door. (223)



**House you can take with you**


A Welsh firm, Elliott Equipment, recently developed a new inflatable hut. The firm's chief promotion man packs one in the trunk of his tiny car, inflates it with a small compressor and drives in out of the British rains. (224)



**The coin and silver paper trick**

New to Avro Aircraft at Malton is this hydraulic press. A 15,000 ton upward pressure stamps impressions through sheet metal into the giant rubber pad made by Goodyear. Siempelkamp of Germany designed and built press. (225)

# DESIGNEERING



From one source you can obtain engineering personnel ready to work at your office or ours.

- design . . . . • layout drafting
- detail drafting . . . . • tracing
- technical illustrating and writing

- Electro-Mechanisms
- Mechanical
- Aeronautical
- Electronic
- Hydraulic
- Jig and Tool

All work is produced in accordance with armed services specifications. Our office and all personnel satisfy defense security requirements.

Our experience has enabled us to work with many of Canada's largest companies.

Let us help you solve your engineering project problems efficiently and inexpensively. Phone or write today.

# DESIGNEERING

1161A WESTON RD.  
TORONTO, CANADA

ROger 2-8401

## Letters

### Readers' viewpoints . . .

● We are interested in receiving one copy of the article, "How Best You Can Heat Treat Aluminum" by J. F. Whiting, from the March, 1956 issue of your periodical, *Design Engineering*.

Please advise us if you can supply either tear sheets of the article or a back-issue of the periodical, quoting prices.

Thank you.

MRS. JETTA MARSHALL  
Librarian

California Hunter Engineering Co.

A copy of the March issue was sent free of charge—Ed.

### Textbook wanted

● It would be highly appreciated if you could arrange for C.O.D. delivery of one volume of "Turboblowers" by A. J. Stepanoff, Ph.D., as announced in *Design Engineering*.

It should arrive in Delhi after the 10th of July, as I will be on holidays until then.

Thank you.

ERIC W. SULEK  
P. Eng.

Delhi, Ont.

Arrangements have been made with the publishers to do this—Ed.

### Fuel injection

● Mr. Elliott Street is to be congratulated on his most interesting and informative article on gasoline injection.

May I add some notes from my own experience. My interest in gasoline injection has been in its use in bus engines. In a well-run fleet, these engines will consume 25 times their own first cost in fuel, in their useful life of one million miles. Thus, any device that promises even a minor saving in fuel is well worth considering.

We found that gasoline injection improved the full-load economy by 3% on the dynamometer, compared to that of the best carburetor. The road-load economy was improved by as much as 8% on service test. The difference is probably made up of saving in fuel on the over-run (coasting), since, with fuel injection, the fuel supply is entirely cut off until the engine speed has fallen to idling speed—an important point.

We found that it was more difficult to develop a satisfactory control device than a satisfactory pump. The gasoline injection project was abandoned because the bus market was by then turning exclusively to diesel engines.

Finally, may I add that I believe the German Air Force went into War II with gasoline injection as standard equipment. My congratulations to Mr. Street for his excellent article.

Toronto

P. E. BIGGAR

### Industrial design

● I would like to obtain information about any good course in general industrial design. This would have to be either extension or correspondence.

If you have any data on organizations carrying this type of course, or possible persons who could direct me, I would certainly be grateful for your help.

F. A. SEEDHOUSE  
Engineering Dept.,

Oshawa

Field Aviation

To the best of our knowledge there is only one such course in Canada. This is at the Ontario College of Art, under the direction of Charles E. Wetmore—Ed.

### Creativity movement

● Would you please arrange to pass on my name to the organizers of the creative engineering movement, as an interested party.

My own approach is concerned with the development of the notion that materials, particularly metallic, are only acceptable from the one source and conversely how the supply and fabrication from this one source affects individual thinking.

ERIC C. BELL  
Metallurgist

Malton, Ont.

Avro Aircraft Ltd.

● I should be interested to receive any further information on creativity in industry.

Yours very truly,

G. C. HEATON  
P. Eng.

Toronto

Ferranti Electric Ltd.

These names have been passed on to the chairman of the new society so that they may be kept well informed.—Ed.

### Interest in new product

● Kindly forward me at your earliest convenience leaflet from Propellair, concerning direct connected fans, as on page 68 of the July, 1956 issue of *Design Engineering*.

S. A. RODWIN  
Refrigerator Engineer

Toronto

Major Appliances, C.G.E.

● On Page 62, of the July issue of *Design Engineering*, a picture was shown of a Case-Maul toggle clamp. I am interested in more information on this but cannot find it in this issue.

Would you kindly advise me of the supplier of this clamp.

JOHN H. BECKER  
P. Eng.


Propane Containers of Canada Limited

# DEXION

## SLOTTED ANGLE

225  
—PHOSPHATED STEEL  
.080" x 2.25" x 1.5"  
ALUMINUM ALLOY  
.092" x 2.25" x 1.5"

300  
—PHOSPHATED STEEL  
.100" x 3.00" x 1.5"




**A versatile, complete SLOTTED ANGLE SYSTEM—the quickest, cheapest, simplest way of getting equipment when you want it, as you want it.**

For literature, **FREE SAMPLES** and name of your nearest distributor, write to

**Dexion (Canada) Limited, P.O. Box 114, Weston, Ont.**

## NESTLER



The most modern and most productive Drafting Room equipment made.

Fully adjustable tables,

Fully counterbalanced.

Precision drafting machines.

Request the latest 24-page catalogue

Sole Canadian Distributor

**JAMES W. STEVENSON & COMPANY**

Importers of Precision Instruments

15 ST. MARY ST.

TORONTO, ONTARIO

WALnut 1-0460



Bristol screws shown are 1 1/2 times actual size

## Miniature Socket Screws are Standard with Bristol

These tiny socket screws have been standard with Bristol since 1950. Many millions of Bristol's Hex and Multiple-Spline Socket Set and Cap Screws are in industrial use in sizes No. 0 and up. Available in alloy and stainless steel, they're designed to fit right in with today's automation techniques. Leading makers of computers, instruments, guided missiles, razors, cameras and other precision instruments, are yearly increasing the demand for them.

Ask your industrial distributor for Bristol's Hex and Multiple-Spline Socket Screws today.



Precision Socket Screw Manufacturers Since 1913

B51

**THE BRISTOL COMPANY OF CANADA LIMITED**

TORONTO HAMILTON MONTREAL VANCOUVER

## Recommended ... SATISFACTION



Peak performance, minimum maintenance and long service are assured by SealMaster's exclusive combination of features.

**1 PERMANENT SEAL** Patented centrifugal seal excludes dirt and retains lubricant.

**2 SELF-ALIGNING.** Bearing assembly is self-aligning in housing. Shaft misalignment cannot distort seals.

**3 PRE-LUBRICATED.** All SealMasters are shipped ready for use—with lubricant sealed in.

**4 PATENTED LOCKING PIN.** Positions unit for re-lubrication. Prevents outer race rotation and housing wear.

MFG. CO.  
OF CANADA  
LIMITED

**STEPHENS-ADAMSON**

Car Pullers  
Car Loaders  
Winches

SealMaster  
Ball Bearings

Speed  
Reducers

Conveyors  
Elevators  
Screens


BELLEVILLE, ONT. BRANCHES ACROSS CANADA

ELECTRONICS



DIVISION

*Now manufacturing under license for Lambda-Pacific*



\* SEE US AT  
BOOTH 441  
AT THE  
C.I.R.E. CONVENTION



MICROWAVE LINKS

TV, STL, common carrier, industrial and government service

100 mW short haul

1.0 watt heavy duty


"KU" band — 100 mW and 250 mW

Black and white and/or Color microwave Systems

**BOP LTD. • ELECTRONICS DIVISION • 455 CRAIG STREET WEST, MONTREAL**



## **LIBRARY BINDER** *for* **DESIGN ENGINEERING**



We offer this binder file at  
cost price to our readers.

**\$2.25**

A handsome and durable library binder in which to keep your copies of Design Engineering. Binder is bound in bright red library fabric and stamped in gold leaf.

Address your order, enclosing  
cheque or money order, to: ➡

**LIBRARY BINDER  
DESIGN ENGINEERING**  
481 UNIVERSITY AVE.  
TORONTO, ONT.



## Advertising index — September

A		
100	Aeroquip Canada Ltd. ....	15
101	Aluminum Co. of Canada Ltd. ....	2nd cover
102	Alloy Metal Sales Ltd. ....	10
103	Avro Aircraft Ltd. ....	2
B		
104	Bach-Simpson Ltd. ....	6
105	Beaconing Optical & Precision Materials Ltd. ..	92
106	Bellows Pneumatic Devices of Canada Ltd. ....	26
107	Bristol Company of Canada Ltd. ....	91
C		
108	Canada Iron Foundries Ltd. ....	25
109	Canadian-Allis-Chalmers Ltd. ....	24
110	Canadian General Electric Co. Ltd. ....	12, 29, 77
111	Canadian S.K.F. Ltd. ....	11
112	Canadian Industries Ltd. (Paints Div.) ....	30
113	Crane Packing Co. Ltd. ....	75
D		
113A	Dalic Metachemical Ltd. ....	22
114	Designing ....	90
115	Dexion (Canada) Ltd. ....	91
116	Dominion Engineering Ltd. ....	17
117	Dominion Fasteners Ltd. ....	61
118	Dupont Company of Canada Ltd. ....	7
F		
119	Fiberglas Canada Ltd. ....	65
H		
120	Heim Company ....	34
I		
121	International Nickel Co. of Canada Ltd. ..	8 & 9, 71
122	Industrial Fine Castings Ltd. ....	64
L		
123	Lindsay-Wilson Limited ....	83
M		
124	Minneapolis-Honeywell Regulator Co. Ltd. ....	66
125	Minnesota Mining & Mfg. of Canada Ltd. ....	19
126	Morse Chain Company ....	69
127	Morrow Screw and Nut Co. Ltd. ....	20
N		
128	Noranda Copper & Brass Ltd. ....	67
129	C. A. Norgren Co. ....	79
130	North American Cyanamid Co. Ltd. ....	27
O		
130A	Ohmite Mfg. Co. ....	16
P		
131	Parker Rustproof Co. ....	21
132	Peacock Bros. Ltd. ....	31
133	Polymer Corp. Ltd. ....	4
134	P.S.C. Applied Research Ltd. ....	13
S		
135	Saginaw Steering Gear Div. General Motors Corp. ....	23
135A	Servospeed Div. ....	70
136	Shawinigan Chemicals Ltd. ....	73
137	Smith & Stone Ltd. ....	76
138	Standard Tube & T.I. Ltd. ....	62 & 63
139	J. W. Stevenson & Co. ....	91
140	Steel Co. of Canada Ltd., The ....	18
141	Stephens-Adamson Mfg. Co. of Canada Ltd. ..	91
142	Superior Tube Co. ....	74
143	Super Oil Seal Mfg. Co. ....	29
T		
144	Torrington Company ....	14
145	Torrington Mfg. Co. of Canada Ltd. ....	32
146	Timken Roller Bearing Co. ....	Back Cover
U		
146A	United Shoe Machinery Co. of Canada Ltd. ....	64
147	Union Carbide Canada Ltd. ....	3rd Cover
W		
148	Wallaceburg Brass Ltd. ....	87
149	Wallace Barnes Co. Ltd. ....	22
150	Wales-Strippit Corp. ....	64
151	Werner Co. (Canada) Ltd., R. D. ....	93
152	John Wiley & Sons ....	68
153	Welwyn Limited ....	81



# Werner Aluminum

Extrusions, Drawn  
and Roll Formed Shapes

## SERVE CANADIAN INDUSTRY

Let us show you how to save money and production time through the use of light metal pre-formed shapes. You are assured of the close co-operation of our trained technical staff in solving your problems. The use of the latest and most efficient production techniques assures you of the best quality and fastest delivery. Heat treatment, polishing, bending and fabricating facilities are available. The following are a few industrial applications of aluminum shapes: household appliances; prime and combination storm-screen windows; automotive accessories; aircraft equipment; scaffolding; electrical appliances; trailers; buses; trains; signs.

Werner's extensive manufacturing and production facilities are geared to produce extruded, drawn and roll formed shapes to your individual specifications at economical prices.

Your inquiry will  
be appreciated and receive  
our prompt attention

**R.D. WERNER CO. (CANADA) LTD.**  
**ALUMINUM**

OSHAWA, ONTARIO

# Tell us—what do you think?

---

DESIGN ENGINEERING, while still an infant, and a healthy one, is no longer a baby. This issue marks the completion of a year and a half of publication — time perhaps to take a backward glance over those 18 months, restate the magazine's original aims and pause to assess our achievement.

DESIGN ENGINEERING was introduced in April of last year to fill the large gap in the Canadian publications field for a magazine catering to the design engineer and his increasing importance in a country of such rapid economic growth. You, as a design engineer, must be forever on the alert for the latest and best materials, methods, finishes and components. To do this is a hard task if, to keep up to date, you have to combine the functions of design engineering with those of news scouting and a heavy program of reading and interviewing.

That's where we come in. As a magazine aimed directly at the design engineer we are in a good position to get the information most likely to keep you in step and in front. In fact we act as both gatherers and originators of this material for final clearance to you in a concise and readable form.


Just how do we rate for achievement? We think we score high but . . . are we really in a position to make the assessment?

There's an old and well-known saying that the proof of the pudding is in the eating. We, the editors, are just the cooks. It is you, the design engineers, who monthly have to approve the value of the product. What then, is your opinion? Since the best way to find the answer to a question is first to ask it, that's what we'll do.

We extend to you in this editorial an open invitation to tell us just how **you** think we've been doing as far as **you** are concerned. Tell us, if you will, what you have liked and disliked and what trends you'll be looking for in DESIGN ENGINEERING.

Obviously, we can't please everyone but why not take up your critic's pen and send us a "no holds barred" letter?

**RSVP**



. . . . filled here

It takes tons and tons of materials  
to fill the prescriptions that give strength and stamina to the steel you use

THE STEEL that's everywhere—in your automobile, in trains, machines, and buildings—is stronger and more enduring because it has been treated with special 'vitamins and tonics.'

**STEEL GETS ITS VITAMINS** from the industry's 'drug-stores'—the plants where alloying metals are made. Here, prescriptions usually call for ingredients by the ton. Their huge 'mixing bowls' are white-hot electric arc furnaces, in which temperatures reach over 3,500 degrees Fahrenheit.

These alloying metals are refined and concentrated forms of both rare and common metals. Among them are manganese, silicon, chromium, boron, tungsten, columbium, and vanadium. Individually, or together, they give steel durability, toughness, hardness, rust and

corrosion resistance, and other special qualities. Chromium, for example, is the secret of making steel stainless.

**VARYING COMBINATIONS** of these and other alloys are added to every ton of molten steel produced today. Without them we wouldn't have the hundreds of different kinds of steel that do so much for all of us in so many ways.

**MORE THAN 50 ALLOYS**—The people of Union Carbide pioneered in the development and production of alloying metals. They make available more than 50 different alloys for steel and other metals that go into products that serve you.

**FREE:** Learn how **ALLOYS, CARBON PRODUCTS, CHEMICALS, GASES, and PLASTICS** improve many things that you use. Ask for 'Man-Made Miracles' booklet D.E.-4.

## UNION CARBIDE CANADA LIMITED

2221 YONGE STREET



TORONTO 7, CANADA

### OPERATING DIVISIONS

#### ALLOYS AND METALS

Electro Metallurgical Co.  
Welland

#### CARBON PRODUCTS

National Carbon Company  
Toronto

#### CHEMICALS


Carbide Chemicals Company  
Montreal

#### INDUSTRIAL GASES


Linde Air Products Co.  
Toronto

#### PLASTICS

Bakelite Company  
Belleville



**OTIS ELEVATOR COMPANY LIMITED** cuts friction and power loss in its hoisting machines by using Timken bearings to take side thrust of the sheave driving shaft.



## How TIMKEN bearings cut friction and power losses in Otis Elevator hoisting machines

**E**NGINEERS at Otis Elevator Company Limited had the problem of side thrust in designing their hoisting machines. Especially on the driving sheave shaft in the larger models. Unless this thrust was handled efficiently, there would be high friction and resulting high power loss.

Otis engineers solved the problem by equipping these hoisting machines with Timken tapered roller bearings. And they get the following results:

1. Less friction loss and therefore less power loss.
2. Elimination of the need for a separate side thrust unit on the sheave shaft.
3. Easy adjustment of wear between

worm and gear by simply lowering the pillow block which retains the roller bearing, instead of having to rebabbit the bearing.

#### 4. Reduction of shutdown time.

Timken bearings can deliver these advantages because they can take thrust as well as radial loads, in any combination. And full line contact between rollers and races gives Timken bearings extra load-carrying capacity. In addition, Timken bearings practically eliminate friction with their true rolling motion. The result: Otis hoisting machines operate smoothly, easily.

Other advantages are low maintenance and lubrication costs. Timken


bearings hold housings and shafts concentric, making closures more effective. Lubricant stays in—dirt stays out.

It's easy to understand why Otis, like so many other manufacturers of fine machinery, uses Timken bearings. They last longer, for the life of the machines, make machines run better, cost little to maintain. Whether you buy or build machinery, it will pay you to see that it is equipped with Timken bearings. The Timken Roller Bearing Company, Canton 6, Ohio. U.S.A. Cable: "TIMROSCO". **CANADIAN PLANT:** St. Thomas, Ontario.



*This symbol on a product means its bearings are the best.*

**TIMKEN** *Made in* **CANADA**  
TRADE-MARK REG. IN CANADA AND U. S. PAT. OFF.  
**TAPERED ROLLER BEARINGS**  
**FOR CANADIAN INDUSTRY**



NOT JUST A BALL  NOT JUST A ROLLER  THE TIMKEN TAPERED ROLLER  BEARING TAKES RADIAL  AND THRUST  LOADS OR ANY COMBINATION 



